

RAILROAD GAZETTE

QUARTO VOL. IX.—NO. 4.
TWENTIETH YEAR.

A Journal of Transportation, Engineering and Railroad News.

\$4.50 PER ANNUM.
POSTAGE FREE.

NEW YORK: 73 Broadway.

FRIDAY, JANUARY 26, 1877.

CHICAGO: 77 Jackson St.

GEORGE A. EVANS,
Bethlehem Steel Rails,
74 WALL STREET.

BOOKS.

STEEP GRADIENTS.—A Treatise on an improved method for overcoming Steep Gradients on Railways, whereby any ordinary Locomotive capable of hauling a given load up a Gradient of 1 in 80, can take the same up 1 in 8. By Andrew Handley. 8vo, paper, 40 cents.

ALGEBRA SELF-TAUGHT.—By W. P. Higgs, M. A. 8vo, cloth, \$1.

CONSTANTS.—Symbols and the Signs of Operation. The Equation and the Unknown Quantity. Positive and Negative Quantities. Multiplication, Involvement, Exponents. Negative Exponents, Roots, and the Use of Exponents as Logarithms. Logarithms, Compound Multiplication and the Binomial Theorem. Division, Fractions, and Ratio. Equations, etc., etc.

TRAMWAYS.—Their Construction and Working. By J. E. and A. Dawson. 8vo, cloth, \$1.50.

WORKSHOP MANIPULATION.—The Economy of Workshop Manipulation. A logical method of learning Constructive Mechanism. Arranged with Questions for the use of Apprentices, Engineers and Students. By J. Richards. 8vo, cloth, \$2.

DESIGNING BELT GEARING. By E. J. C. Welch. 16mo, paper, 20 cents.

HINTS TO YOUNG ENGINEERS, upon entering upon their Profession. By Joseph W. Wilson. 8vo, paper, 20 cents.

BOILERS. On Boiler Incrustation and Corrosion. Read before Section G, British Association, Sept., 1876. By E. J. Ryan. 8vo, paper, 40 cents.

* List of our publications sent free by mail on application.

E. & F. N. SPON, 446 Broome Street, N. Y.

SAFETY RAILROAD SWITCH

WITH
MAIN TRACK UNBROKEN,
RAILROAD CROSSINGS, FROGS,
AND OTHER

ROADWAY SUPPLIES,
Manufactured by

THE WHARTON

RAILROAD SWITCH COMPANY.

Office, 28 South 3d street.

Works, 23d and Washington avenue,
Philadelphia.

THE SAFE DEPOSIT CO.

OF NEW YORK.

140, 142 and 146 Broadway.

FRANCIS H. JENKS, President.

For the safe-keeping of Valuables, Bonds, Stocks,

Plate, Jewelry, Wills, etc., (at \$1 a year for \$1,000 of

Bonds), and the renting of Safes (at from \$15 to \$200

a year), in its fire and burglar proof vaults.

ROOMS FOR LADIES,

with every convenience, separate desks, etc., are

provided.

RAILROAD GAZETTE DIRECTORY.

[This index to the advertisements in the RAILROAD GAZETTE is published in order that they may be more convenient and valuable to those who make use of them as a directory of railroad supplies and equipment. A number of advertisements appear only "every other week" or "once a month," in such cases, where the advertisement is not in the current number, a blank appears instead of the folio opposite the name.]

Accountants:

Calhoun & Steele, 20 Nassau street, N. Y.

Air Brakes:

Wm. Loughridge, Baltimore.

Westinghouse Air Brake Co., Pittsburgh.

Annual Meetings:

U. S. Rolling Stock Co., 74 Wall st., N. Y.

Annual Reports:

U. S. Rolling Stock Co., 74 Wall st., N. Y.

Axles:

A. & F. Roberts & Co., Philadelphia.

Wilson, Walker & Co., Pittsburgh.

Bolts, Nuts, Boiler Rivets, etc.:

Roopes & Townsend, Philadelphia.

Books:

E. & F. N. Spon, 446 Broome st., N. Y.

Brackets:

American Bridge Co., Chicago.

Baltimore Bridge Co., Baltimore.

Cincinnati Bridge Co., Cincinnati.

Clark, Reeves & Co., Philadelphia.

Delaware Bridge Co., Philadelphia.

Delaware Bridge Co., 22 Wall street, N. Y.

Detroit Bridge & Iron Works, Detroit.

Edgemoor Iron Co., Wilm. & 79 Liberty st., N. Y.

E. W. Jones & Co., Milwaukee, Wis.

R. H. Hopkins & Co., St. Louis.

Kellogg & Maurice, Athens, Pa.

King Iron Bridge & Manufacturing Co., Philadelphia.

Keystone Bridge Company, Philadelphia.

Lowthorp & Henderson, Trenton, N. J.

GEORGE WESTINGHOUSE, JR.,
PRESIDENT.

RALPH BAGLEY,
SECY & TREASURER.

T. W. WELSH,
SUPERINTENDENT.

THE WESTINGHOUSE AIR-BRAKE COMPANY,

PITTSBURGH, PA., U. S. A.,

Manufacturers of the

WESTINGHOUSE AUTOMATIC BRAKE.

WESTINGHOUSE LOCOMOTIVE DRIVER BRAKE.

VACUUM BRAKES (Westinghouse & Smith Patents).

WESTINGHOUSE AIR BRAKE.

Particular attention is called to the "AUTOMATIC" and "LOCOMOTIVE DRIVER BRAKES," now being

tested and adopted by the prominent lines.

With the "DRIVER BRAKE" the engineer can handle an ordinary freight train better than with brakesmen.

The saving in car wheels and wages will therefore be apparent. On shifting or yard engines it is invaluable.

The "AUTOMATIC" has proved itself to be the most efficient train and safety brake known. Its application is

instantaneous; it can be operated from any car in the train, if desired, and should the train separate, or a hose or

pipe fail, it applies automatically. A GUARANTEE is given customers against LOSS from PATENT SUITS on the

apparatus sold them.

FULL INFORMATION FURNISHED ON APPLICATION.

"LOUGHRIDGE AIR BRAKE,"

Adopted by the Balt. & Ohio, W. Md. C. & Pa.

(with Mountain grades of 182 feet to the mile), St. L.,

L. & W. in Kansas and others. It has been used on

a thousand or more cars long enough to convince

the most incredulous that it is the best. The best

stop yet accomplished in the world with air brakes

was made with this practical invention on the B. &

Ohio R. R. The train weighed 250 tons and con-

sisted of ten cars, speed 42-6-10 miles per hour;

time in stopping, 16 seconds; distance run, 587-8-12

feet. It is capable of much better results now.

Cheap in construction and repair, of but few and

simple parts, uniform and reliable in action, quick

to apply and relieve the brakes, and accomplishes

all desirable ends required in running trains that

competing brakes do. For further information ad-

dress, WILLIAM LOUGHRIDGE, P. O. Box 441.

Office Morse Building, Room 17, Baltimore, Md.

W. CALHOUN, J. G. STEELE,

ACCOUNTANTS & AUDITORS.

No. 30 Nassau Street.

Complicated accounts of Estates and Partnerships

investigated and adjusted. Accounts prepared for the

Surrogate. Books of Public Companies, Firms,

etc., opened, written up or closed.

Special attention given to Railroad investigations in

any part of the United States or Canada.

REFERS BY PERMISSION TO

Geo. S. Coe, Esq., Pres't American Exch'ge Bank.

W. A. Wheelock, Esq., Pres't Central Nat. Bank.

Wm. Lynch, Esq., Pres't Irish Emigrant Society.

Col. H. S. McComb, Pres't N. O. St. L. & C. R. R.

Ex. Norton, Esq., Pres't Paducah & Mem. R. R. Co.

Jos. F. Joy, Esq., Receiver Dutchess & Col. R. R.

Parker Handy, Esq., Banker.

H. W. Smithers, Esq., Agent.

Hon. H. A. Smythe, late Collector of Port of N. Y.

Hon. Jas. P. Sinnott, Judge of the Marine Court.

Messrs. Van Winkle, Candler & Jay, Counselors.

JOHN A. WILSON,
Civil Engineer.

FRED. G. THORN,
Architect.

JOS. M. WILSON,
Civil Engineer and Architect.

WILSON BROTHERS & CO.,

Civil Engineers and Architects.

410 Walnut St. Philadelphia, Pa.

Surveys and estimates made for railway lines.

Plans, specifications and estimates furnished for

roads, bridges, stations, machine shops, engine

houses, hotels, dwellings and all engineering and

architectural structures. Construction of engineer-

ing and architectural works attended to.

J. S. KENNEDY & CO.,

BANKERS AND MERCHANTS,

41 CEDAR CORNER WILLIAM STREET,

New York.

Buy and sell Railroad Investment Securities, Col-

lect Coupons and Dividends, Negotiate Loans and

draw Bills of Exchange on London.

Agents of the

CAMBRIA IRON COMPANY,

of JOHNSTOWN, Pa., for the sale of their IRON and

STEEL RAILS.

All business relating to the Construction and

Equipment of Railroads undertaken.

RAILROAD IRON.

50 and 56 lbs. in store at New Orleans.

50 and 56 lbs. in store at New York.

Bessemer Steel Rails.

46, 56 and 60 lbs. in store at New York.

For sale by

DANA & COMPANY.

20 Nassau street.

RAILWAY ECONOMY

And Security.

Hall's Automatic Electric Railway Signal

System.

Best in the World.

THE HALL RAILWAY SIGNAL COMPANY.

THOMAS S. HALL, Gen'l Manager,

West Meriden, Conn.

OFFICE OF THE

UNITED STATES ROLLING

STOCK CO.

No. 74 and 76 Wall Street.

New York, Jan. 8, 1877.

The annual meeting of the stockholders of this

company will be held at the office of the company,

No. 74 and 76 Wall street, on Monday, the 5th day

of February next, at 12 o'clock m., for the reception

of the annual report, the election of five Trustees

for the ensuing year, and the transaction of such

other business as may be brought before the meet-

ing.

A. HEGEWISCH,

Secretary.

OFFICE OF THE

United States Rolling Stock Co.,

New York, Dec. 31, 1876.

ANNUAL REPORT

Of the United States Rolling Stock Co.

The capital stock of this company is five millions

of dollars, all issued and paid in cash.

The debts of the company amount to \$140,-

550.40. JAS. B. HODGSKIN, President.

JAS. B. HODGSKIN,

Wm. H. GUION,

ADV. BRELIN,

E. G. FABBRI,

City, County and

State of New York. Trustees.

Adolfo Hegewisch, being duly sworn, says that he

is the Treasurer and Secretary of the United States

Rolling Stock Company, and that the foregoing

Report is true and correct to the best of his knowl-

edge and belief.

A. HEGEWISCH.

Subscribed and sworn to before me, at the city of

New York, this seventeenth day of January, A. D.

1877.

WILLIAM H. BOWEN,

Notary Public, N. Y. County.

Railroad Manuals:

H. V. & H. W. Poor, 68 Broadway, N. Y.

Railroad Securities:

J. S. Kennedy & Co., 4 Cedar st., N. Y.

Railroad Car Brakes:

Wm. Loughridge, Baltimore.

Rubber Steps:

Rubber-Step Manufacturing Co., Boston.

Safe Deposit:

Safe Deposit Co., 140 Broadway, N. Y.

Sash Chains:

T. S. Morton, 65 Elizabeth st., N. Y.

Shafting:

Wm. Sellers & Co., Phila. & 79 Liberty st., N. Y.

Signals:

Hall Signal Co., West Meriden, Conn.

Snow Flows:

C. L. Heywood, Boston.

Spikes:

Dilworth, Porter & Co., Pittsburgh.

Tudor Iron Works, St. Louis & Chicago.

Steel and Steel Tiles:

Midvale Steel Works, Nictown, Philadelphia.

Thomas Frosser & Son, 15 Gold st., N. Y.

Randall & Jones, Boston.

Standard Steel Works, Philadelphia.

Switches:

Pennsylvania Steel Co., Harrisburg.

Wharton R. R. Switch Co., Philadelphia.

H. R. Manning & Co., 113 Liberty st., N. Y.

L. O. Crocker, Weymouth, Mass.

Track Tools:

Metcalfe, Paul & Co., Pittsburgh.

Tri-Nitro Glycerine:

G. M. Mowbray, North Adams, Mass.

Turn Tables for Railways:

Wm. Sellers & Co., Phila. & 79 Liberty st., N. Y.

Valves:

Ladlow Valve Manufacturing Co., Troy, N. Y.

Peet Valve Co., Boston.

Varnishes:

Berry Bros., Detroit.

Mad. & Co., Cleveland.

Forest City Varnish, Oil & Naptha Co., Cleveland.

Valentine & Co., 323 Pearl st., N. Y.

Watches:

Giles, Bros. & Co.

Watchman's Time Detectors:

J. E. Buerk, Boston.

Welding Compound:

Schierloh Manufacturing Co. Jersey City.

Wire Rope:

J. A. Roebling's Sons, Trenton, N. J.

Wrenches:

A. G. Coes & Co., Worcester, Mass.


L. Coes & Co., Worcester, Mass.

Wanted and For Sale:

.....

CULMER SPRING CO.

MANUFACTURERS OF



RAILWAY CAR SPRINGS,

Spiral Buffer, Freight Bolster, Journal and Equalizing Bar Springs.

SPIRAL SPRINGS, OF ALL DESCRIPTIONS, A SPECIALTY.

OFFICE & WORKS, Cor. 26th and LIBERTY STS.

HENRY A. BREED,
General Manager and Treasurer.

PITTSBURGH, PA.



Copyright secured.

PITTSBURGH CAST-STEEL
SPRING WORKS

A. FRENCH & CO.

MANUFACTURERS OF

Extra tempered light elliptic

CAST-STEEL SPRINGS,

FOR
RAILROAD CARS & LOCOMOTIVES,

From best Cast Steel.

Office and Works: Cor. Liberty and 21st
Streets, Pittsburgh, Pa.

ST. LOUIS BRANCH—M. M. BUCK & CO.
CHICAGO BRANCH—145 E. LAKE ST.



**COLUMBIA
CAR SPRING CO.,**


322 Seventh Ave., cor. 28th St.,
NEW YORK.

BRANCHES:

109 Milk St., Boston,

123 Central Ave., Cincinnati,

17 So. Canal St., Chicago.



Rubber Plates for Car Steps.

Accidents from slipping prevented—icy steps
avoided—the elasticity of the rubber breaks the
ice when stepped upon.


Our step and panel having the name of a rail-
road moulded thereon is very ornamental, and adds
much to the appearance of car steps.

MANUFACTURED BY


Rubber Step Manufac'g Co.,
43 Haverhill Street, Boston.

Send for circular.

JOHN SOUTHER & CO., Boston, Mass.,
Exclusive Manufacturers of the



Otis Patent Steam Excavators
WITH CHAPMAN'S IMPROVEMENTS, AND DREDGES.



**ALGER'S
Patent Friction
EXCAVATORS**

AND
DREDGES,

MANUFACTURED BY

Vulcan Iron Works Co.,

Oswego, N. Y.,

AND

S. B. ALGER,
Long Island City,
N. Y.

THE HAMILTON STEELED-WHEEL CO., OF PHILADELPHIA.

W. G. HAMILTON,
President.
WM. M. SPACKMAN,
Treasurer.
CHAPMAN BIDDLE,
Solicitor.



OFFICES.

68 NORTH SECOND STREET
Philadelphia, Pa.

24 BROADWAY
New York.

Grant Licenses to manufacture and use Car Wheels made under Patents of W. G. Hamilton and Geo. Whitney, adding largely to the strength of the metal, and rendering available the use of Non-Chilling Irons.

WHEELS AND AXLES
MADE OF THE
BEST STOCK
AND IN THE MOST
careful
MANNER
FURNISHED
SEPARATELY
OR
COMPLETE
SETS

TAYLOR IRON WORKS
ON THE LINE
OF THE
CENTRAL R.R. OF NEW JERSEY
HIGH BRIDGE, N.J.
CAR WHEELS & AXLES
DRAW HOOKS AND FORGINGS.
LEWIS H. TAYLOR Pres't
S. P. RABER Sec'y
JAS. H. WALKER
NEW YORK OFFICE 93 LIBERTY ST.

**STEEL TIED
WHEELS**
MADE UNDER
SAX & KEAR'S
PATENT
FOR LOCOMOTIVE
AND TENDER
PASSENGER CAR
SERVICE

Southern Agent, WM. J. NICOLLS, 5 Post Office Avenue, Baltimore.



G. G. LOBDELL, Pres't
P. M. BRENNAN, Treas.

Lobbell Car-Wheel Co.,
WILMINGTON, DEL.


Manufacturers of

LOBDELL'S PATENT COMBINATION (DOUBLE PLATE),
IMPROVED SINGLE PLATE and IMPROVED
HOLLOW SPOKE WHEELS,

Furnished with or without Axles: adapted for Broad and
Narrow Gauge and Street Roads.

MAKERS OF IRON AND BRASS CASTINGS, ETC.

Also Manufacturers of **CHILLED ROLLS**, for Paper
Press, Copper and Rolling Mills.



UNION FORGE AND IRON MILLS,
(WILSON WALKER & CO.)

MANUFACTURERS OF



Equalizing Bars for Car Trucks, "Miller Hooks" and Buffers.


UNIVERSAL PLATES FOR GIRDERS, BRIDGES, &c.
Works, corner Twenty-ninth and Railroad Streets, Pittsburgh, Pa.

GEORGE BUNTIN.

CHARLES H. SMITH.

GEORGE BUNTIN & COMPANY,

Sole Manufacturers
for the United States
of
BUNTIN'S
PATENT
Iron
SEAT FRAME



Now in use in
over 2,000 cars
on all the prin-
cipal railroads in
the United
States.

OFFICE AND
MANUFACTORY
1042 Ridge Ave.,
Philadelphia, Pa.

THE LANE & BODLEY CO.,

John and Water Sts., Cincinnati,

Manufacturers of their Perfectly Graduated

Stroke Power

MORTISING MACHINE

Hangers, Pulleys, Couplings and

Shafting.

LOWEST PRICES AND BEST QUALITY.

Send for our Price Lists.

FERRIS & MILES,

24th and Wood Sts.,
PHILADELPHIA,

Manufacturers of



Engine Lathes, Axle Lathes, Planing and
Machines, Wheel Bore, Upright Drills, Ro-
dial Drills, Punching and Shearing
Machines, &c. Steam Ham-
mers, Drops, &c.


BARNUM RICHARDSON CO., SALISBURY, CONN.,



MANUFACTURERS OF
CHARCOAL PIG IRON FROM SALISBURY ORES,
AND CHILLED  **CAR WHEELS.**

All Work from this Establishment made from Salisbury Iron
AND WARRANTED.
ADDRESS OR,
WM. H. BARNUM, Pres't. **ALBERT ALLING, Agent for Sale of Pig Iron,**
LIME ROCK, CONN. 64 SOUTH JEFFERSON ST., CHICAGO, ILL.

BARNUM & RICHARDSON MANUFACTURING CO.,
64 South Jefferson Street, Chicago, Ill.



MANUFACTURERS OF
Chilled Car and Locomotive Wheels, from Pure Salisbury Iron,

ALSO MANUFACTURERS OF
CAR AND ALL OTHER DESCRIPTIONS OF CASTINGS.
All Work Warranted.

WM. H. BARNUM, President, **ALBERT ALLING, Gen'l Manager,**
Lime Rock, Conn. Chicago, Ill.

ENSIGN MANUFACTURING COMPANY


Huntington, W. Va.,

MANUFACTURERS OF



WHEELS,

For Passenger, Freight and Coal Cars, and Locomotive Trucks and Tenders. Also all kinds of Car and Bridge Castings.

W. H. BARNUM, Pres.,
Salisbury, Conn.
E. ENSIGN, Treas.,
Huntington, West Va.




RAMAPO WHEEL AND FOUNDRY COMPANY,



MANUFACTURERS OF
Wheels for Drawing Room and Sleeping Coaches, Locomotives, TENDERS, PASSENGER AND FREIGHT CARS

W. W. SNOW, Sup't & General Manager, Ramapo, Rockland Co., N. Y.



A. WHITNEY & SONS, CAR WHEEL WORKS,
Callowhill and Sixteenth Streets, Philadelphia, Pa.



BALTIMORE CAR WHEEL COMPANY,
OFFICE 15 SOUTH STREET,

Manufacture Wheels

FOR

City and Steam Railways,

With or without Axles.

WHEELS OF ALL PATTERNS

Made to Order and in Stock.

This Company using strictly Baltimore Charcoal Iron, (which has no superior and few equals, for making Car Wheels,) and annealing their Wheels by the most approved process, warrant them free from strain, and equal in tenacity and uniformity of chill to any made.


W. S. G. BAKER, President.
J. M. LAWFORD, Secretary.

Works, corner Essex and Concord Streets. Canton, Baltimore, Md.

LEHIGH CAR-WHEEL WORKS,

McKEE & FULLER,

Catasauqua, Lehigh County, Pennsylvania,



MANUFACTURERS OF
Wheels for Locomotives, Tenders, Passenger, Freight, Coal, City Passenger and Mine Cars.
Wheels Fitted to Axles, and Prices Furnished on Application.
CAPACITY, 200 WHEELS PER DAY.

Makes All Kinds of FREIGHT CARS,

and the BEST of CAR WHEELS.

J. L. GILL
Columbus, Ohio.



MOWRY CAR AND WHEEL WORKS,

Manufacturers of Cars and CAR WHEELS of all descriptions. Wheels and Axles, Chilled Tires; Engine, Car and Bridge Castings, of any pattern, furnished to order at short notice. Wheels of all sizes constantly on hand.
OFFICE: No 29 WEST THIRD STREET, Cincinnati
WORKS: Eastern Av. & Lewis St. Cincinnati, O.
N. G. GREEN, Sup't, Cincinnati.

THE AMERICAN BRIDGE CO.



H. A. RUST, President.
L. B. BOOMER, Resident Director.

EDWARD HEMMEL, } Engineers.
W. G. COOLIDGE, Sec'y.

MANUFACTURERS AND BUILDERS OF

BRIDGES,

Roofs, Turning-Tables, Pivot Bridges, Iron Trestles Wrought Iron Columns
Heavy Castings,

GENERAL IRON AND FOUNDRY WORK.

BUILDERS OF

PNEUMATIC MASONRY, AND SCREW-PILE SUBSTRUCTURES.

Iron Bridges and Roofs upon the principal Railroads in the United States illustrate designs and attest the character and extent of products of Works.
Proposals accompanied by Plans, Specifications and Lithographs promptly submitted upon application.

WORKS: Cor. Egan and Stewart Aves. | OFFICE: No. 210 LaSalle st., Cor. Adams.
THE AMERICAN BRIDGE CO., Chicago.

CINCINNATI BRIDGE COMPANY.



365 FT. SPAN BRIDGE OVER THE GREAT MIAMI RIVER, FRANKLIN, OHIO.

Manufacturers and Builders of Whipple's Iron Truss and Arch Bridges,
FOR RAILWAYS AND HIGHWAYS;

Also ROEBLING'S CELEBRATED STEEL WIRE SUSPENSION BRIDGES.

All kinds of Bridge irons made to order. Only best quality of material used. Send notice of Bridge lettings.

J. W. SHIPMAN, Pres. and Eng.

Address CINCINNATI BRIDGE CO.,

31½ West 3d St., Cincinnati, O.

J. D. HUTCHINSON, Vice-President and Eastern Manager, Peekskill, N. Y.

NIAGARA BRIDGE WORKS

BUFFALO, N. Y.,



BUILDERS OF IRON LATTICE BRIDGES


FOR RAILROADS AND HIGHWAYS.

PLATE GIRDERS, COMPOSITE BEAMS, ROOFS, PLATE TURNABLES, &c
S. J. FIELDS, ENGINEER. GEO. C. BELL, MANAGER.

Office and Works: Forest avenue, cor. Niagara street.

KELLOGG & MAURICE,

OFFICE AND WORKS: ATHENS PA.



Iron and Wooden Bridges, Roofs, Turn-tables, Etc

THE MILWAUKEE BRIDGE AND IRON WORKS

G. W. JAMES & CO., Milwaukee, Wis.



BALTIMORE & OHIO RAILROAD BRIDGE, SOUTH CHICAGO, ILL.

BALTIMORE BRIDGE CO.,

54 Lexington Street, Baltimore.



C. SWALER SMITH, Pres. & Ch. Eng.

F. H. SMITH, A. Eng. & Gen. Supt.

LATROBE, A. Eng., Sec. & Treas.

O. C. WARESHALL, Supt. of Erection.

Design and Construct Iron, Steel and Composite Bridges and Roofs of any form or span desired. Special attention is called to our Wrought-Iron Trestles and Viaducts, patented in United States, England, France and Belgium, and built of any height or length. Lithographs and information promptly furnished.

THE DELAWARE BRIDGE COMP'Y

Office
52 WALL STREET
NEW YORK.



ENGINEERS AND CONTRACTORS FOR THE CONSTRUCTION
OF IRON AND WOODEN BRIDGES, STEEL SUS-
PENSION BRIDGES, ROOFS, VIA-
DUCTS AND TURN TABLES.

Manufacturers of Die Forged Eye-bars, Truss Bolts, Compression Members and Bridge materials generally.
O. MACDONALD, President and Engineer. WM. M. FINCKE, Secretary and Treas.



BRIDGES, TRUSS ROOFS, TURNABLES AND DEPOTS.


BUILDERS OF BOTH, SUB- & SUPERSTRUCTURES.

H.S. Hopkins

ST. LOUIS, MO.

Wm. McCully

DETROIT BRIDGE AND IRON WORKS, OF DETROIT, MICH.



ENGINEERS AND MANUFACTURERS OF


Iron Bridges. Iron Roofs, Etc.

WILLARD S. POPE, Pres. and Engineer.

WM. C. COLBURN, Sec. and Treas.

THE KEYSTONE BRIDGE COMP'Y,

PITTSBURGH, PA., Builders of Long-Span Bridges.




Newport & Cincinnati, 620 ft. Parkersburg, 350 ft. Cincinnati Southern Ry., 520 ft. Steubenville, 320 ft. Bellair, 350 ft.
Engineers and Builders of WROUGHT-IRON and WOODEN BRIDGES, IRON ROOFS and BUILDINGS
Manufacturers of Wrought-Iron Turntables, Wrought-Iron Columns, Weldless Chords, Castings, Rolls,
General Machine and Mill Work. Illustrated Album sent on application to undersigned.

J. H. LINVILLE, President.

218 SOUTH-FOURTH STREET, Philadelphia.

PHOENIXVILLE BRIDGE WORKS.

CLARKE, REEVES & CO., Engineers and Builders of



Iron Bridges, Viaducts, Roofs, Turn Tables, etc

SPECIALTIES:—Accurate workmanship; the use of double-refined iron; no welds; Phoenix upper
chords and posts, the best form of strut known; all work done on the premises, from ore to finished
bridge.

ILLUSTRATED ALBUM mailed on receipt of 75 cts. at 410 WALNUT STREET, PHILADELPHIA, PA.

LOUISVILLE BRIDGE & IRON CO.,

Office and Works: Corner Oldham and 11th Streets, Louisville.



BUILDERS OF

FINK'S SUSPENSION AND TRIANGULAR TRUSSES,
and other forms of Iron and Combination Bridges. Also Manufacturers of Iron Roofs, Turn-tables
Frogs, Switches, etc.

ALBERT FINK, President.

A. P. OHROGAN, Secretary.


F. W. VAUGHAN,

GILMAN TRAFLET,

} Engineers.

E. BENJAMIN, Superintendent of Works.

LEIGHTON BRIDGE AND IRON WORKS, ROCHESTER, N. Y.




THE SPRINGFIELD BRIDGE, BY LEIGHTON BRIDGE AND IRON WORKS.
Wrought-Iron Riveted Lattice Railroad and Highway Bridges, Wrought-Iron Water Pipe and General Riveted Work.
ORDERS SOLICITED FROM CIVIL ENGINEERS AND CONTRACTORS.

WROUGHT-IRON BRIDGE CO.



D. HAMMOND, President. | Office and Works, CANTON, O. | JOB ABBOTT, H. G. MORSE, Engineers.
Manufacturers and Builders of all Wrought-Iron Railway and Highway Truss, Arch and Swing Bridges, Plate and Lattice Girders, Iron Roofs, Turn-Tables, Iron Piers and Trestles. Have over TWENTY-FOUR MILES of their IRON BRIDGES now in use in twenty-four different States and Canada. ILLUSTRATED ALBUM and estimates sent on application.

KING IRON BRIDGE & MANUFACTURING CO., CLEVELAND, OHIO.



WROUGHT IRON BRIDGES

Paid in Capital - - - - \$325,000 00

Edge Moor Iron Co.,

{ Works at Edge Moor, on Delaware River, }
{ Post Office, Wilmington, Delaware, }
MANUFACTURE ALL KINDS OF

IRON WORK

FOR

BRIDGES, ROOF TRUSSES AND BUILDINGS.

SPECIALTIES :

HYDRAULIC FORGED EYE BARS.

HYDRAULIC FORGINGS and HYDRAULIC RIVETED WORK.

Specifications from Railroad Companies, Engineers and Contractors solicited, upon which estimates will be promptly furnished.

WILLIAM SELLERS, President. | ELI GARRETT, Sec'y & Treas'r. | GEORGE H. SELLERS, Gen'l Sup't.

WILLIAM B. BEMENT & SON,

MANUFACTURERS

RAILROAD

Engine-Lathes,
Axle-Lathes,

Wheel-Lathes,
WHEEL-BORERS,
WHEEL-PRESSES,

PLANERS,
SLOTTING MACHINES,
SHAPING MACHINES,

BORING AND TURNING
MACHINES,
STEAM-HAMMERS,

SHAPING, HANGERS,
&c., &c.



MACHINE TOOLS,

Radial, Horizontal and
Upright Drills,

MILLING-MACHINES,
CENTERING-MACHINES,
Axle Cutting-Off Ma-

chines,
BOLT-CUTTERS AND
NUT-TAPPERS.

Punching and Shear-
ing Machines,
Riveting Machines.

BENDING ROLLS.

SPECIAL TOOLS FOR LOCOMOTIVE, CAR AND BOILER WORK.

Office and Works, Corner Callowhill and Twenty-first streets Philadelphia.

LOWTHORP & HENDERSON, ENGINEERS AND BUILDERS

OF
BRIDGES AND TURN TABLES
OF WROUGHT IRON, OR COMBINATION OF
WROUGHT AND CAST.

78 East State street, Trenton, N. J.
F. C. LOWTHORP, C. E. J. J. HENDERSON,

J. H. COFRODE.

J. H. COFRODE & CO., Engineers and Bridge Builders.

DESIGN AND CONSTRUCT IRON, WOODEN AND COMBINATION BRIDGE
AND ROOF TRUSSES, &c.,

OFFICE :

No. 530 Walnut Street, Philadelphia.

"TAYLOR'S"

HAMMERED CRUCIBLE CAST STEEL

LOCOMOTIVE TIRES,

AND

BEST YORKSHIRE BAR IRON,

RANDALL & JONES,

Oliver street, Boston.

F. H. SAYLOR.

PENCOYD IRON WORKS. A. & P. ROBERTS & CO., MANUFACTURERS OF CAR AXLES. BAR, ANGLE, TEE AND CHANNEL IRON.

Office, No. 305 South Fourth St., Philadelphia.



S. SHELTON, Sec'y & Treas.

H. M. CLAFLEN, Pres.

M. W. BRA

THE LOOMIS NUT LOCK WASHER CO.,

CLEVELAND, OHIO.



Sole Manufacturers of the celebrated LOOMIS NUTLOCK WASHER, for Railroad Tracks, Cars, etc. It is a PERFECT NUT HOLDER. It is made to fit any sized bolt or fish-plate (requiring but one nut), and is of the best cast or spring steel, with a perfect spring; therefore WARRANTED not to break or set. It entirely compensates the expansion and contraction of the iron, and the nut will, in NO CASE, turn off of its own accord, however great the jar or strain. ORDERS SOLICITED AND PROMPTLY FILLED.

METCALF, PAUL & CO.,

Make a Specialty of,

SOLID STEEL

RAILROAD TRACK TOOLS

Also Sole Manufacturers of

THE PATENT

VERONA NUT LOCK.

331 Penn Ave.

Send for our New Catalogue.

W. H. WAKEFIELD, Chairman.

WENLEY WILSON, Treasurer.

H. LONG, Secretary.

THE AMERICAN RAILWAY SUPPLY CO. (Limited),



Manufacturers of the Samson Railway Joint, and Dealers
in and Agents for Railway Supplies Generally.

P. O. LOCK BOX 1,177.


OFFICE, No. 376 Penn

Ave., Pittsburgh, Pa.

CHAS. I. WICKERSHAM, General Eastern Agent,
Office, 265 South Fourth St., Philadelphia,

Patented Nov. 9,
1875.

ATWOOD CONICAL LOCK NUT.



This nut is represented in the engraving on the right, and is made of a conical form on the under side, and fits into the bolt hole which is made of the same shape. The cone and square portions are slotted so that when screwed up into the conical hole, the nut is compressed and clamps the bolt tightly, so that it cannot be shaken loose. The effect of wear is to make it fit the hole more accurately, so that when it is again tightened up it will be less liable to become loose than before it was worn. The conical nut is intended especially for fish plates and bolts. The engraving on the left represents a square nut cut apart on the top side only. The under side is made concave, so that in screwing it up the hole on the upper side is contracted and clamps the bolt in the same way as the conical nut. The square nut is intended for car work bridges and similar purposes. The conical nuts are now extensively used in the track of the Philadelphia, Wilmington & Baltimore and Boston & Albany, and have been applied on a number of other railroads. It is simple in construction, being in one piece, has a longer bearing on the bolts than other nuts, and cannot strip the threads, and will always fit the bolts, no matter how loosely the thread is cut.

THE ATWOOD CONICAL LOCK NUT AND MANUFACTURING CO.,
No. 40 Broadway, Room 41, P. O. Box 1,049, New York.

For Uniformity, Durability and Economy, use

"The Murphy Railway Varnishes"

MURPHY & COMPANY,
Newark, N. J.

MURPHY, SHERWIN & CO.
Cleveland, O.

PATENT METALLIC SHEDS AND WAREHOUSES.

These Sheds are
LIGHT, STRONG,
AND
ELASTIC,
therefore especially well
adapted to

RESIST VIBRATIONS
From Machinery
and the pressure of heavy
winds.
They can be taken apart and
put up again in a very short
time by any intelligent la-
borer, and also take little
room for shipping by cars or
steamers; they are conse-
quently

PORTABLE
in the fullest sense of the
word. Being built entirely of



Price List with Cuts furnished on application. Non-Combustible
Material.

they can not be ignited by
sparks from locomotives,
steamers, or neighboring
fires, and in view of this fact
they are very

ECONOMICAL,

as the small excess of the
cost over a wooden structure
is fully compensated by the

REDUCTION

IN THE
INSURANCE RATES
and the greater safety of the
property stored.

Manufactured by

SCHWEIZER & CRUWE, 71 BROADWAY, N. Y.

BALDWIN LOCOMOTIVE WORKS.



BURNHAM, PARRY, WILLIAMS & CO., Philadelphia, LOCOMOTIVE ENGINES.

Especially Adapted to Every Variety of Railroad Service, including

Mining Engines and Locomotives for Narrow-Gauge Railways
All work accurately fitted to gauges, and thoroughly interchangeable. Plan, Materials, Work-
manship, Finish and Efficiency fully guaranteed.

GEO. BURNHAM.
EDWARD H. WILLIAMS.

CHAS. T. PARRY.
EDW. LONGSTRETH.


WM. P. HENSZEY.
JOHN H. CONVERSE.

CAYUTA WHEEL & FOUNDRY CO.,

P. O. Address: WAVERLY, N. Y.,
Works at Sayre, Pa.

MANUFACTURERS OF WHEELS

FOR
TENDERS,
PASSENGER,
FREIGHT
AND
COAL
CARS;
ALSO
CASTINGS OF EVERY DESCRIPTION
REGINALD CANNING, Supt.




THE "EUREKA" STATION TICKET

Is a combination of Station, Stop Over and Half Fare Ticket. Only one form required for an entire line
which is good at all stations and in all directions; it also does away with Conductors' Private Checks.
Manufactured solely by the Am. Duplex Ticket Co., who also apply their principle to Cash Fares,
Excess Baggage, Stop Over, and numerous other forms of

RAILROAD AND STEAMBOAT TICKETS.

These tickets have been in successful operation for the past four years, and are now in use upon more
than One Hundred and Twenty-five Roads, including most of the principal lines in this country and
Canada. Samples and information furnished with pleasure by
W. H. CAMPBELL, Manager, 800 Broadway, New York.



LOUISVILLE CAR-WHEEL

AND

RAILWAY
SUPPLY COMPANY,
491 East Jefferson St.,
LOUISVILLE,
KENTUCKY.

ELIZABETHPORT STEAM CORDAGE COMPANY,

MANUFACTURERS OF

Manilla, Sisal and Tarred Cordage,
46 SOUTH STREET,

NEW YORK.

E. M. FULTON,
D. B. WHITLOCK,
A. W. LUKENS.

DILWORTH, PORTER & CO., RAILROAD

SPIKES AND FASTENINGS,
PITTSBURGH.

TANGYE'S Hydraulic Jacks.

Best and Cheapest in the market and
the easiest to work. No valves to stick
in lowering.



Wrought Iron Blocks for
rope, chain and wire rope.

McCoy & Co.

134 Duane Street, N. Y.

FOREST CITY VARNISH, OIL & NAPHTHA CO.,

MANUFACTURERS OF

Fine Railway and Coach Var-
nishes.
CLEVELAND, O.

TO RAILROAD OR COAL COMPANIES
desiring to purchase land for coal docks. For
sale a piece of land 380 ft. deep and with frontage
of 82 ft. on S. I. Sound, within a quarter of a mile
of the Easton and Amboy coal docks at Perth Am-
boy, N. J. Further particulars may be learned of
JAS. L. FORD, office Railroad Gazette.

FOR SALE AND IMMEDIATE DE-
livery: fifteen or twenty first-class passenger
cars, partly used. Address H. F. KENNEY, Super-
intendent Philadelphia, Wilmington & Baltimore
Railroad, Philadelphia, Pa.

WANTED—A SITUATION AS SHORT-
hand writer for some railway official. Six
years' experience. GEO. F. BENEDICT, Litchfield,
Mich.

WANTED—A TRAVELING SALESMAN
of first-rate abilities and acquaintance
among railroad companies for canvassing that trade
exclusively and for one line of goods (connected
with the paint-shop supplies). Only such as can
point to a similar past record and experience need
apply. The right man will find a good opportunity
with a first-class house. Address, stating past em-
ployment, &c., B. B. SALESMAN, P. O. Box 3,778, N.
Y. City.

A GENTLEMAN DESIRES POSITION
as Assistant Superintendent, Resident En-
gineer, or Engineer of Permanent Way and Machin-
ery. Is thoroughly "PRACTICAL," "PROGRESSIVE"
and "SYSTEMATIC." Experience in United States
and Spanish America. Address "A," Superintendent,
Office Railroad Gazette.



FRIDAY, JANUARY 26, 1877.

Consolidation Locomotive Constructed at the Baldwin Locomotive Works.

This week we give the remaining engravings of this engine, a double-page view of which was published last week. We are indebted to *Engineering* for these engravings, excepting the detailed views of the truck, which have been made from original drawings furnished us by Mr. Ely, the Superintendent of Motive Power of the Pennsylvania road. The engine was built from designs furnished to the Baldwin Locomotive Works by that company.

In the *Railroad Gazette* of Dec. 1 of last year (page 519) we published engravings of an engine of the same type for the Lehigh Valley Railroad. In describing the one illustrated this week and last, *Engineering* compares it with that represented in the *Railroad Gazette* of Dec. 1, as follows:

The engine made for the Pennsylvania Railroad is constructed for burning bituminous coal, whereas the engine for the Lehigh Valley Railroad, previously described, was arranged for burning anthracite. Thus a comparison of the two boilers will show that the one now illustrated has a smaller grate surface and fewer and larger tubes, the total heating surface being, however, very nearly the same in the two cases, it being 1,281 square feet for the Lehigh, and 1,258 square feet for the Pennsylvania engine. The cylinders of the two engines are the same size, namely, 20 in. and 24 in. stroke, while the coupled wheels are also practically the same size, the Lehigh engine having 50½ in., and the Pennsylvania engine 50 in. wheels. We give below the proportions of the boiler of the engine now illustrated, and for convenience of comparison we annex similar data relating to the engine for the Lehigh Valley Railroad:

	Consolidation Locomotive for Pennsylvania Railroad: fuel, bituminous	Consolidation Locomotive for Lehigh Valley Railroad: fuel, anthracite
Ratio of fire-grate to heating surface ..	1 : 54.7	1 : 51.79
Ratio of fire area to grate surface ..	1 : 5.87	1 : 6.87
Ratio of least sectional area of chimney to grate surface ..	1 : 10.55	1 : 17.1
Ratio of fire-box surface to external tube service ..	1 : 12.67	1 : 10.1
Number of internal diameters in length of tubes ..	66	73.3

The chief dimensions of the boiler of the engine now under notice are given in the tabular statement on our two-page engraving, and it will be unnecessary, therefore, that we should repeat them here. We may, however, direct attention to some of the special constructive features. In the first place it will be noticed that the boiler instead of being of the "wagon-top" type—as it is called in the United States—like that of the engine for the Lehigh Valley line, has the fire-box casing considerably lower than the top of the barrel of the boiler, the top of the casing sloping away until at the rear end it is only about on a level with the centre line of the barrel. The crown of the fire-box also slopes downwards towards the rear, but less sharply than the top of the casing, and thus the fire-box crown and crown of the casing gradually approach each other, the distance between them being 10½ in. at the front, and but 3½ in. at the rear end. The crown of the fire-box and casing are stayed together in the same manner as the sides, there being no girder stays.

The impression conveyed by this arrangement of fire-box is that there is an insufficient space for proper circulation above the fire-box crown, and that the rush of the steam generated from this spot to cause priming. We have not, however, heard of any difficulty arising from this cause, and the fact that this form of fire-box and casing has now long been in use in America must, we suppose, be accepted as evidence that its performance is fairly satisfactory. It will be seen from our two-page engraving, and from the transverse section on the present page, that the gauge-glass fittings and gauge-cocks are mounted on a hollow column fixed on the top of the fire-box casing near the rear end, the top of this column being connected with the steam space of the boiler by a pipe, which is led up to the roof of the cab, and then passes down to join the tube through which the regulator rod passes, this tube having at its end inside the boiler a pipe which is led up to the top of the dome. The tube for the regulator rod has also at its rear end a drain pipe which passes down to the gauge-cock column. The whole arrangement is chiefly shown by our two-page engraving.

Although the engine is, as we have stated, designed for burning bituminous coal, it is, as will be seen, fitted with a water-tube grate similar to that employed for anthracite. The movable solid bars, provided for dropping the fire instead of being made to draw out, as in the case of the Lehigh Valley engine, are, however, in the engine now under notice cranked, as shown in our longitudinal section, and made to turn over

laterally on the crank centres. There are two of the solid bars in the width of the grate, and they are connected by a link at the rear end outside the fire-box, so that they can be moved together.

The boiler is provided with a large dome, and as in some of the other American locomotives we have described, the opening in the barrel is the full size of the dome, and is strengthened by flanging the barrel plate outwards, as shown. The top of the dome is of cast iron, as is usual in American practice. It will be noticed that the ring of the barrel on which the dome is placed is tapered, its underside sloping downwards to join the fire-box casing. This gives it an oval form in cross-section, and necessitates the introduction of transverse stays, these being placed just above the tubes, as shown. The smoke-box tube-plate is strengthened by two diagonal stays, not shown in our engraving. The feed enters the boiler at the sides of the barrel near the front end, and passes into a transverse pipe or chamber of rectangular section situated just above the tubes, this chamber having distributing pipes led off from it towards the rear, as shown in

what may be called the standard features of American locomotive practice.

The springs of the three hind pairs of wheels are connected by compensating levers, while those of the front pair of coupled wheels are similarly connected to the pony truck at the leading end. This truck is of the swing-beam type, instead of being a Bissell truck, as in the Lehigh Valley engine, and its construction is shown by the longitudinal section and by the transverse section. From these views it will be seen that a strong transverse stay between the frames carries a casting in which a hollow plunger slides, this plunger having an opening at one side through which the end of the compensating beam passes. As will be seen from the views above referred to, the end of the compensating beam takes hold of a stirrup at the bottom of a link hanging from the top of the plunger, this link being provided with adjusting nuts, as shown. The lower end of the plunger bears upon a kind of bridge-piece, which spans—but is clear of—the transverse bar connecting the axle-boxes of the truck, this bridge being coupled to the centre of a pair of transverse springs, as shown. The ends of the springs just mentioned are coupled by pendulum links to the bar which connects the axle-boxes, and the latter are thus left free to move laterally. Radius bars from the bottom of the axle-boxes, and from the transverse bar which connects these boxes, are led back to centres just in front of the first pair of coupled wheels, as shown in the longitudinal section.

The coupled wheels of the engine under notice are of cast iron, with crucible cast-steel tires, the tires of the two middle pairs of wheels being without flanges and 6½ in. wide. The wheels have hollow spokes, and the section of the rim is shown by the transverse section, Fig. 2. The truck is provided with Messrs. A. Whitney & Sons double-plate chilled wheels.

The type of engine we have been describing does some very heavy work on the Pennsylvania Railroad. Thus, on the Philadelphia & Columbia Division, where the maximum grade going eastward is 40 ft. to the mile, or 1 in 152, the load, taken at a speed of 15 miles per hour consists of a train of 35 loaded cars weighing 735 tons, exclusive of the engine; while going westward over the same division, a maximum grade of 49 ft. per mile, or 1 in 107.8 to be surmounted, and the load is then 30 loaded cars weighing 630 tons. The consumption of fuel on this part of the road averages 4.2 lbs. per mile per car hauled. On the Columbia & Harrisburg Division there is a short grade of 30 ft. per mile, or 1 in 176 going eastward, and a short grade of 37 ft. per mile or 1 in 142.7 going westward, and on this section the loads in the two directions are 70 cars weighing 1,470 tons, and 65 cars weighing 1,365 tons respectively, the consumption of fuel averaging 2.7 lbs. per car per mile. On the Erie & Langdon's Division the maximum gradient going eastward is 71 feet per mile, or 1 in 74.4, and up this gradient the engines haul 24 loaded cars weighing 504 tons. On the Renovo & Jersey Shore section going eastward there is a gradient of 26 ft. per mile, or 1 in 233, for about 4 miles, the remainder of the line being practically level, and on this division the load for the engines consists of 80 loaded cars weighing 1,680 tons, with a consumption of 2.7 lbs. per car per mile. Finally, on the Susquehanna Division, which is about level, the load going eastward consists of 85 loaded cars weighing 1,785 tons, this load being frequently taken at a speed of 25 miles per hour, and the fuel consumption being 2.5 lbs. per car per mile. These performances are of much interest, the loads being unlike anything hauled in this country.

The Ashtabula Accident.


The investigation of the causes of this accident by the committee of the Ohio Legislature was begun last week, and meanwhile the coroner's inquest has continued. The following is a report of the examination of Mr. Amasa Stone, President of the Lake Shore Company when the bridge was built, before the Committee of the Legislature:

Mr. Stone being in delicate health, the committee met at his residence, on Euclid avenue. Being sworn, he testified as follows: He was at first Superintendent of the Lake Shore road, from Cleveland to Erie, for two years, and was afterward President from 1856 to 1867, and has since been a director of the road. The bridge across Ashtabula Creek was built in 1863; witness designed the bridge, but only superintended the drawing of the plan, while the details of construction were given into the hands of Mr. Albert Congdon, who was supervised to Mr. Joseph Tomlinson; the witness has not now the original plan of the structure, and does not certainly know where it may be found.

Q.—Were there full written specifications of the bridge at the time of its construction, and if so, where are they now? A.—There were all the specifications usually given, but I do not know where they now are.

Q.—Were there full specifications at the time? A.—There were.

Q.—Were the other papers preserved till the bridge was completed? A.—I am not aware that they were. The span of the bridge was 154 feet; the width of the bridge, from outside to outside, was 19 feet 6 inches, perhaps 20 feet; the width of the bridge between the chords, 14 or 14½ feet; the width of the truss was 19 feet 6 inches, and 20 feet in height from the lower edge to the upper edge; the width of each panel was 11 feet; there were four in all; there was no change in the plan of the works as projected by witness; there was no departure from the original plan as to strength, &c.; there was an error which gave the builders some trouble; this error was that they put in some parts horizontally that should have gone in vertically; the lugs may have been chipped off in remedying the mistake; the witness does not remember as to that point; the original design of the braces was not to be six inches flange, six inches webs; it was to be seven inches in both cases. The lugs upon the brace-block do not show, so far as I know, that they should be six inches; I was advised that the work was going on very slowly,



CONSOLIDATION LOCOMOTIVE AT THE PHILADELPHIA EXHIBITION.

Built at the Baldwin Locomotive Works, Philadelphia.

the longitudinal section on our two-page engraving. The boiler is fed by one pumpworked direct from the right-hand cross-head and one of Messrs. Sellers & Co.'s injectors. The external steam pipes, front of the smoke-box door, and base of the chimney are of cast iron. The boiler and fire-box are of cast steel, the plates for the shell being made by the Bay State Iron Company, and those for the fire-box by Messrs. Singer, Nimick & Co., while the tubes are of charcoal iron, and made by Messrs. Morris, Tasker & Co.

In the case of the "Consolidation" engine for the Lehigh Valley Railroad, to which we have already referred, two of the coupled axles were under the fire-box and two under the barrel of the boiler. In the engine now under notice, owing to the longer tubes and shorter fire-box, there are three axles under the barrel, while there is a somewhat greater amount of overhang at the rear end. In the present case, too, the second axle from the rear is the driving axle, and the connecting rods are thus much longer than in the Lehigh Valley engine, while the eccentric rods, which are also very long, have to be bowed to clear the next axle, as shown in the longitudinal section. The valve motion is of the ordinary lifting link type, and as is usual in American engines, the motion is transmitted to the valve spindles through rocking shafts as shown in Fig. 4. The frame is of the usual bar type, but of this and some other details we shall have more to say in a future notice when dealing with

and I went down to see what the trouble was. I heard of no trouble after the change from horizontal to vertical was made; Mr. Tomlinson was intrusted with the construction of the bridge in the beginning, but he was found very inefficient, and he was discharged, and Mr. Rogers was put in his place; Mr. Rogers had no experience either before or since in the erection of iron bridges, so far as the witness knows. There could have been no other mistake made than the one that was made. The weight and pressure of the bridge, bound by the vertical truss-rod, would hold it in place. The unscrewing of the rods from the bearings would loosen them; the dropping out of three or four counter braces would not affect the strength; one-half of them out of place would not affect the strength; at the centre the counters become main braces, but at either end they are not so important; the dropping out of a few at the centre would injure its strength; no other means was devised to keep the counters in their places, because the lugs were placed on almost entirely for convenience in raising; they were for no especial purpose after the bridge was raised; the braces were held by other means; there would be no means of elongating the tie-rods sufficiently to injure the strength of the bridge; the struts upon the lower part of the bridge were 22 feet, perhaps, I don't recollect.

The bridge would be a very safe one without any lateral braces, it is so very thick. Witness has known bridges erected without any lateral braces to stand for years. There were in the bridge various iron cross-ties, fastened to the upper chords of the bridge by loop bolts, upon which the rails were laid. The resting of the iron rails upon the top chord in the center of the panels would not weaken the upper chord; it is usual to have those beams thus rest; it is not usual to strengthen the top chords for this purpose, for they are supposed to be strong enough; the bridge must be twice as strong to carry two tracks as to carry one track in the center; I have carefully considered the matter, and my conclusion is that the dead weight of the bridge and its load would not strain the bridge more than 8,000 or 9,000 pounds to the square inch, while it was capable of supporting 32,000 pounds to the square inch; one train on one side of the bridge would strain the trusses about 85 per cent. as much as it would were two trains passing over at the same time; when the bridge broke, it swung to the north, while the load was pitched to the south; it is very conclusive evidence to my mind that the bridge was carried down by the second locomotive leaving the track in some way; the bridge was not strong enough to carry a train across off the track; had the bridge broken of its own weakness it would have swung to the south; a model tested to the extent of breaking a truss would show that that truss would break to the south and carry the bridge to the south; an engine dropping on the cross floor beams would tend to deflect them, and pull the truss which the train was passing over on to the north, and when pulled to the north it would then go down; the braces were fastened together in the centre by loop bolts, which kept them all in position; this bridge would have been stronger if the tie-rods had been perpendicular and the braces oblique; I have never constructed any other Howe truss bridge with wrought-iron braces, and know of no other anywhere in the country; when Mr. Rogers made the mistake in putting in the braces it was not negligence in permitting him to continue the superintendence of the erection of the bridge, for there was no other particular in which he could have made a mistake; it was not even unwise to permit him to continue; the directions of the witness were that the ends of the sway rods be enlarged so as not to be weakened by the cutting of the thread upon them; if this was not done, and the thread did actually reduce the strength of the rods, it was a poor job; when the bridge was changed, in correcting the mistakes there were no more braces inserted, no parts of the bridge were reduced in size because the rollers in the shop were not sufficient in size; witness had no interest in the mill where the iron was made; his brother, A. B. Stone, the Chisholms, and Mr. Jones, owned it at that time.

Q.—Ought not such bridges as the one under consideration to be examined by an experienced bridgeman as often as once in three months, and by the trackmen quite frequently? A.—There would be no necessity of tightening and loosening the nuts on account of the changes of the temperature, as the nuts are practically tight in warm or cold weather; the examination should be for the purpose of seeing whether the nuts had become loosened or any of them were off; the wrecked train and the passengers were burned up from fire kindled by the locomotive or stoves in the cars, probably by the latter.

Q.—Why did not your company comply with the law in regard to safety from fire in case of accident? A.—I examined the stoves called safety stoves, and consider them more dangerous than those now in use.

Q.—Why did you not use steam for heating? A.—It is not practicable. No engine can furnish enough steam for its regular work and to heat the cars also; the work of braking with steam comes when the train is slackening up, and the steam for running the train is not in use. While the bridge was going up the witness gave no personal supervision to the work; the ironwork was done by a thorough master machinist as the witness knows of; witness was at the shops afterward while the bridge was being built; he was at the bridge only once during its erection; that was when there was a report that there was trouble in putting it up. When the bridge was tested it was stiffer and the deflection was less than expected; the difference in cost between the bridge built and stone arches would have been about \$18,000; the bridge itself cost about \$15,000; the bridge and arches cost perhaps nearly \$75,000.

TESTIMONY OF MR. CHARLES COLLINS, CHIEF ENGINEER.

Mr. Charles Collins gave the following testimony before the same committee:

I do not know where the original plans of the bridge are, unless they are at Ashtabula, before the Coroner's jury; they are the full working plans; I never saw them, however; such plans are generally preserved; they belonged to my office, but at

about the time the bridge was constructed I was put on other work, and this was put into the hands of another man; I never saw the plans, therefore, as they were not sent to my office; I think they were up at the shop when the work was done; they would also be wanted when the bridge was set up; the examination of the bridge belongs to men under me; my instructions are to report everything wrong; G. M. Reed is at the head of the examining corps; he has no set time, but works on a general order; some time in September he reported verbally that the bridge was all right; they have not been required to report in writing in ordinary business; I never ordered any special examination of that bridge; I never made any statements to the effect that "the bridge was not mine but Stone's;" I was once staying at Ashtabula, and Mr. Rogers asked me to go and visit the bridge, and I told him the braces were in wrong, but that I had nothing to do with it; he requested me to have Mr. Stone come down; I went with Mr. Stone who remarked that he was surprised the braces were in wrong; it was still resting on the trestle-work; when I saw it next it was tested; the braces were afterward turned and an

blocks; since the accident I have been too busy in the erection of a new bridge to examine as carefully as I desired the material of the wreck; if one or more of the sway rods were to break, the floor would go one way, the train the other; the application of air brakes would check the train and possibly jump a car from the track.

TESTIMONY OF THE MASTER MECHANIC.

Mr. Alfred Congdon, of Elyria, who was Master Mechanic of the Lake Shore road when this bridge was built, gave testimony, which is reported as follows:

That the bridge was intended for a double track when built, but was not used as such for some time; that after the bridge was completed, the supports being removed, it was found that the middle portion sagged so much that it was necessary to put in new braces and change the beams. Witness always thought that there should have been an additional cord under the bridge, but says that, as the bridge was, it was perfectly safe if it had received proper attention. He believed the stirrups which had been put into it to strengthen the braces and rods had worked out, and this could not have occurred without detection had the bridge been inspected at proper intervals.

Fig. 3.

British Railroads in 1875.


The following is the report of Capt. H. W. Tyler, Chief Inspector of the British Board of Trade, on the share and loan capital, traffic, working expenditure and net profits of the railroads of the United Kingdom in 1875:

RAILWAY EXTENSION.

The total length of railway open for traffic on 31st December, 1875, was 18,656 miles, of which 8,898 miles were laid with two or more lines, and 7,760 miles with a single line of rails. They were distributed as follows: In England, 11,789 miles, including 4,460 miles of single line; in Scotland, 2,721 miles, including 1,661 miles of single line; in Ireland, 2,148 miles, including 1,639 miles of single line. There was an increase of 209 miles between 31st December, 1874, and 31st December, 1875—namely, from 16,449 miles to 16,658 miles, or at the rate of 1.27 per cent. This increase was made up as follows: From 11,622 miles to 11,789 miles, or 1.44 per cent. in England; from 2,700 miles to 2,721 miles, or .78 per cent. in Scotland; and from 2,127 miles to 2,148 miles, or .99 per cent., in Ireland. But much has still to be done. While the length of new lines opened for traffic during the six years, 1870 to 1875 inclusive, amounted to 1,513 miles, application has been made to Parliament in the last seven years in regard to 6,080 miles; and Parliament has sanctioned during the same period the construction of 2,500 miles, all of which will, no doubt, sooner or later, be completed. Additional lines are being laid down on the busiest portions of existing railways, which are also being otherwise improved; some of the lines which have been partly constructed and temporarily abandoned will be recommenced; and new or widened lines become, as traffic continually increases, more and more necessary for separating, on through routes, the fast and the slow traffic from one another.

CAPITAL.


The total capital raised by shares, stocks and loans on 31st December in each of the years from 1871 to 1875 inclusive was as follows: 1871, £552,361,551; 1872, £607,346; 1873, £588,320,308; 1874, £608,895,931; 1875, £630,233,494; showing an increase of £20,327,663 raised during 1875. The average cost per mile of railway open, which was £34,099 at the end of 1870, had increased to £34,106 at the end of 1871, to £35,944 at the end of 1872, to £35,984 at the end of 1873, to £36,574 at the end of 1874, and to £37,078 at the end of 1875. The more recent railways have, with the exception of the Metropolitan and some others, been constructed at a much lower rate of cost per mile than the above figures of rather more than £34,000 for 1858 to nearly £38,000 for 1875. But the rate of cost on the total mileage continually increases in consequence of the constant necessity for laying down additional lines and sidings, and improving the accommodation in goods and stations, and otherwise providing for working safely and economically the ever-increasing traffic on the older lines. And the same result must be expected from year to year as long as the traffic of the country continues to increase in the same ratio. But the capital has thus increased in very different proportions as regards the various descriptions of stocks and loans. The increase in ordinary shares for the year 1871 over the year 1870 was rather under a million, or only .42 per cent.; for the year 1872 over the year 1871 nearly 9 millions, or 3.8 per cent.; for the year 1873 nearly 5 millions, or 2.26 per cent.; for the year 1874 rather over 4 millions, or 1.67 per cent., and for the year 1875 rather more than 6 millions—viz., from £248,528,241 to £254,600,738, or 2.4 per cent. The increase in guaranteed and preference stocks or shares was from £173,051,875 at the end of 1871, to £177,764,674, or 2.7 per cent., at the end of 1872; to £188,127,069, or 5.8 per cent., at the end of 1873; to £212,193,324, or 6.8 per cent., at the end of 1874; and to £213,429,438, or 1.9 per cent., at the end of 1875. The increase also in loans and debenture stocks was from £149,375,080 in 1871 to £152,205,728, or 1.9 per cent. in 1872; to £155,743,434, or 2.3 per cent. in 1873; to £160,437,061, or 3.01 per cent. in 1874; and to £163,429,438, or 1.9 per cent., in 1875. The increase in debenture stocks increased at the rate of 28 per cent. in 1872, 16 per cent. in 1873, and 11 per cent. in each of the years 1874 and 1875—viz., from £27,382,355 in 1871 to £55,981,511 in 1872, to £59,855,120 in 1873, to £111,170,991 in 1874, and to £123,008,684 in 1875; while the terminable loans decreased at the rate of 19 per cent. in 1872, 16 per cent. in 1873, 12 per cent. in 1874, and 18 per cent. in 1875—viz., from £22,095,545 in 1871 to £26,224,217 in 1872, to £25,888,314 in 1873, to £29,266,070 in 1874, and to £24,420,754 in 1875. The process of converting terminable debentures into debenture stocks, which was proved some years since to be so necessary, has thus been further continued.



CONSOLIDATION LOCOMOTIVE AT THE PHILADELPHIA EXHIBITION.

Built at the Baldwin Locomotive Works, Philadelphia.

additional number put in; I made inspection of it afterward when the trains were passing over it; looked at it as an engineer, and thought the yokes about the angle blocks would hold the braces in position; I did not anticipate any trouble on account of the position of the braces; I considered the fastenings of the braces sufficient; in the change that was made the corners of the braces were clipped off, but this, I do not think, would affect it materially; I have never made any estimate of the weight of the bridge; I have had no experience in building that kind of a bridge, but it would have been stronger if the braces had been united so as to make them act together; I have never known of another bridge to be built of wrought iron on this plan; this bridge was an experiment; I think the upper chords were not all the same size; I never saw or examined the strain-sheet of the bridge; I never myself made a mathematical examination of the bridge with a view to ascertaining its safety; there was a guard-rail which would prevent the wheel from jumping unless something had been tampered with; I think a locomotive might run across if there was nothing wrong; below the floors were beams or stringers; the bridge was built for a double track; the outside rail was immediately over the chord; the bridge would not be stronger if wider; it would have to be more than double as strong for a double track as for a single one; I have examined the wreck and found that some of the braces had slipped out of the angle



SINGLE-AXLE TRUCK OF CONSOLIDATION LOCOMOTIVE FOR THE PENNSYLVANIA RAILROAD.

The percentage of loans to the total capital has decreased from 15 per cent. in 1871 to 12 per cent. in 1872, to 9 per cent. in 1873, to 8 per cent. in 1874 and to 6 per cent. in 1875; while the percentage of debenture stocks has increased from 12 per cent. in 1871 to 15 per cent. in 1872, to 17 per cent. in 1873, to 18 per cent. in 1874 and to 20 per cent. in 1875. The proportion of ordinary capital remained at 42 per cent. of the total capital for each of the three years 1871, 1872, 1873, but decreased to 41 per cent. in 1874, and to 40 per cent. in 1875; the proportion of debenture stock and loan capital taken together, which was 27 per cent. of the total capital for the years 1871 and 1872, has decreased for the years 1873, 1874 and 1875 to 26 per cent.; and the proportion of guaranteed and preference

ferential and loan capital taken together decreased from 4.63 per cent. for 1858 to 4.48 per cent. for 1870, to 4.42 per cent. for 1871, and to 4.39 per cent. for both 1872 and 1873, but improved to 4.41 per cent. for 1874, and to 4.42 per cent. for 1875.

The above facts are interesting, as showing at a glance the net results of railway working in the United Kingdom for the five years. It will be observed that the rate of interest on the total capital expended slightly exceeded the interest on the loans, debenture stock and preferential capital taken together, the former being 4.54 per cent. and the latter 4.42 per cent. for 1875; while the rate of interest on the ordinary share capital which (including the portion on which no dividend was paid)

averaged 4.72 per cent., exceeded the fixed interest on stocks and loans preferred to it, which (including also those which received no cash payment) averaged 4.42 per cent.

PROPORTIONS OF CAPITAL IN RELATION TO RATES (OR ABSENCE) OF INTEREST.

Of the ordinary share capital, amounting to over 254½ millions, nearly 38½ millions, as above stated, or 5¼ millions less than in the previous year, received no dividend at all.

Of the remaining 216 millions, in round numbers, 9 millions received dividends of less than 1 per cent., 3 millions from 1 to a fraction under 2 per cent., 11 millions from 2 to a fraction under 3 per cent., 14 millions from 3 to a fraction under 4 per cent., 31 millions from 4 to a fraction under 5 per cent., 28 millions from 5 to a fraction under 6 per cent., 43 millions 6 per cent., 9 millions 6½ per cent., 39 millions 6¾ per cent., 4 millions from 7 to a fraction under 8 per cent., 20 millions from 8 to a fraction under 9 per cent., 1 million from 9 to a fraction under 10 per cent., 4 millions from 10 to 13 per cent.

There is, however, included in the above a large amount of capital of companies whose lines are under lease, or of capital which receives fixed rates of interest. Although this amount was subscribed, and has been returned as ordinary capital of companies whose lines are thus leased, it might perhaps more properly be considered as guaranteed capital of the leasing companies. The rates of interest on this amount are not, however, generally high, excepting in one case, in which nearly 2½ millions received 11½ per cent. of interest.

Of the 38½ millions of ordinary share capital on which no dividend was paid, 32½ millions belonged to English companies, 3 millions to Scotch companies, and 3 millions to Irish companies. The total ordinary capital at the end of 1875 of the English companies was nearly 214 millions, of the Scotch companies about 24½ millions, and of the Irish companies about 16 millions.

The average dividend on the 254½ millions of ordinary share capital, computed from the rates returned as having been paid on 216 millions, and considered to be spread over the whole, amounted, as already stated, to 4.72 per cent.; while the average amount of dividend or interest, computed from the rates returned as having been paid on £583,164,549, but spread over the whole of the share and loan capital—namely, £630,223,494, amounted to 4.54 per cent. This last percentage may, as stated in former reports under similar circumstances, appear at first sight to clash with the percentage of net receipts to total share and loan capital given in Table No. 2, column 7, and quoted under the last heading, as only 4.25 per cent. It is necessary, therefore, again to explain that the difference arises, partly in consequence of the subscriptions by certain companies to the undertakings of other companies being credited to the capital of the company subscribed as well as to the capital of the company subscribed to, but mainly to the exclusion from the calculations on which column 7 of Table 2 is based, of the receipts and expenditures on account of navigations, harbors, canals, steamboats, &c. These latter are, of course, included in Table No. 3, as regards both the capital outlay and the proportionate rates of interest paid on the different descriptions of capital raised for railway and other purposes.


Of the capital returned as guaranteed, amounting to nearly 78 millions—2¼ millions received dividends of 2¼ or less per cent.; 1½ millions from 3 to a fraction under 4 per cent.; 15½ millions from 4 to a fraction under 4½ per cent.; 12 millions from 4½ to a fraction under 5 per cent.; 35½ millions of 5 per cent.; 2 millions from 5½ to a fraction under 6 per cent.; 5¼ millions of 6 per cent.; 1¼ millions from

During the year 1875 of the capital of those companies whose lines were open for traffic no interest was paid upon £7,687,081 of preference stock, apparently from a want of sufficient profit in working; this was a falling off as compared with 1874, in which year the proprietors of £7,326,169 of preference stock received no dividend. The holders of £48,000 of loans and of £769,464 of debenture stock were also without interest in 1875. This, too, was a falling off as compared with 1874, both as regards loans and debenture stock. In that year the holders of £8,000 of loans and £514,674 of debenture stock were without interest. No interest was paid upon £35,678,393 of ordinary stock in 1875, which was an improvement as compared with 1874. In that year the proprietors of £41,121,014 of ordinary stock received no interest. But the difference, as I have pointed out in previous reports, between the nominal value of many of these stocks and loans and the amounts actually received by the companies for them, is, in consequence of the mode in which the money has been raised, very considerable.

RATES OF INTEREST.

The average rate of interest paid on ordinary capital in 1875 was 4.72 per cent., against 4.49 per cent. for 1874, 4.99 per cent. for 1873, 5.14 per cent. for 1872, and 5.07 per cent. for 1871; showing an increase for 1875 of .23 per cent. over 1874, but a decrease of .27 per cent. below 1873, of .42 per cent. below 1872, and of .35 per cent. below 1871; while on guaranteed, preferential and loan capital the average interest paid was 4.42 per cent. for 1875, against 4.41 per cent. for 1874, 4.39 per cent. for each of the years 1873 and 1872, 4.42 per cent. for 1871, and 4.48 per cent. for 1870. The average interest on debenture loans decreased from 4.37 per cent. in 1870 to 4.25 per cent. in 1871, and to 4.19 per cent. in 1872, from which rate it has varied but little, being 4.21 per cent. in 1873, 4.20 per cent. in 1874, and 4.18 per cent. in 1875; and that on debenture stock decreased from 4.47 per cent. in 1870 to 4.37 per cent. in 1871, to 4.34 per cent. in 1872, to 4.33 per cent. in 1873, to 4.32 per cent. in 1874, and to 4.28 per cent. in 1875. The 4.54 per cent. of interest paid on £158,692,084 of guaranteed and preference stock in 1870 decreased continuously to 4.51 per cent. on £173,049,413 in 1871, to 4.49 per cent. on £177,764,674 for 1872, and to 4.48 per cent. on £188,127,069 for 1873, but rose to 4.52 per cent. on £200,820,629 in 1874, and to 4.54 per cent. on £212,198,324 in 1875.

The average net earnings on the total capital increased from 3.75 per cent. for 1858 to 4.19 per cent. for 1870, to 4.43 per cent. for 1871, and to 4.51 per cent. for 1872, but decreased to 4.35 per cent. for 1873, and to 4.14 per cent. for 1874, and again increased to 4.25 per cent. for 1875; while the average interest on pre-



CONSOLIDATION LOCOMOTIVE AT THE PHILADELPHIA EXHIBITION.

Built at the Baldwin Locomotive Works.

6½ to a fraction under 7 per cent.; 2 millions of 7 to 11½ per cent.

Of the capital returned otherwise as bearing preferential interest, amounting to 134½ millions, about 7½ millions received no dividends at all. 5½ millions received dividends from 1 to a fraction under 2 per cent., 2½ millions from 2 to a fraction under 3 per cent., ½ of a million from 3 to a fraction under 4 per cent., 40½ millions from 4 to a fraction under 5 per cent., 69½ millions 5 per cent., 5½ millions from 5½ to a fraction under 7 per cent., 2 millions from 7 to 10 per cent.

Of the loans, amounting to nearly 40½ millions, —1½ millions received interest at rates under 4 per cent., 24½ millions 4 per cent., 5½ millions 4½ per cent., 4½ millions 4¾ per cent., 8½ millions 5 per cent., ½ million rates varying from 5½ to 8 per cent.

Of the debenture stocks, amounting to 123 millions, ¾ of a million received no interest, 1 million received less than 4 per cent., 68½ millions 4 per cent., 6½ millions 4½ per cent., 24½ millions 4¾ per cent., 19½ millions 5 per cent., 2½ millions 6 per cent.

REVENUE.

Under this head are omitted on the one side the receipts from navigation, steamboats, tolls, rents, etc., and on the other side the expenses connected with steamboats, harbors and canals, etc. It appears that the total receipts from railway working amounted to £28,982,753 on 16,658 miles for 1875, against £26,899,495 on 16,449 miles for 1874, against £25,675,421 on 16,082 miles for 1873, against £21,304,114 on 15,814 miles for 1872, and against £17,107,539 on 15,376 miles (as returned by companies, but which may more correctly be stated as 15,611 miles) for 1871; while the total expenses of railway working were £23,198,186 for 1875, against £21,647,517 for 1874, against £20,060,112 for 1873, against £18,652,753 for 1872, and against £17,632,046 for 1871. The proportion of working expenses to gross receipts was, therefore, 54.6 per cent. for 1875, against 55.6 per cent. for 1874, against 54.0 per cent. for 1873, against 50.0 per cent. for 1872, and against 48.4 per cent. for 1871; and the percentage of net receipts to total capital was, as already stated, 4.43 for 1871, 4.51 for 1872, 4.35 for 1873, 4.14 for 1874, and 4.25 for 1875.

The proportion per cent. of expenditure to receipts for the years 1870, 1871, 1872, 1873, 1874 and 1875 in each division of the United Kingdom was as follows:

In England and Wales—1870, 48; 1871, 47; 1872, 49; 1873, 53; 1874, 55; 1875, 55. In Scotland—1870, 50; 1871, 50; 1872, 51; 1873, 57; 1874, 57; 1875, 52. In Ireland—1870, 52; 1871, 53; 1872, 53; 1873, 56; 1874, 57; 1875, 55.

Looking at the above it may be noticed that, while the proportion of expenditure to receipts in England and Wales remained at 55 per cent. in 1874 and 1875, in Scotland, after having remained at 57 per cent. for the years 1873 and 1874, it decreased to 52 per cent. in 1875; and in Ireland, after having been 56 per cent. in 1873 and 57 per cent. in 1874, it decreased to 55 per cent. in 1875.

The total receipts from passenger trains increased from £20,622,580 for 1871 to £22,287,555 for 1872, to £23,553,892 for 1873, to £24,893,615 for 1874, and to £25,714,081 for 1875; while the total receipts from goods trains increased from £26,484,978 for 1871 to £29,016,559 for 1872, to £31,821,529 for 1873, to £32,005,883 for 1874, and to £33,268,072 for 1875.

The percentage of receipts from passenger and goods traffic for the United Kingdom, which was in 1858 as 49 from passengers to 51 from goods, and which remained in 1872 the same as in 1870 and 1871—namely, as 44 from passengers to 56 from goods, became in 1873 as 43 from passengers to 57 from goods, and in 1874 and 1875 as 44 from passengers to 56 from goods. But it was very different in the three kingdoms. In England the percentage proportions of receipts from passengers and goods were nearly the same as in the three kingdoms combined. In Scotland those proportions decreased from 41 in 1858 to 37 in 1876 for passengers, and increased from 59 in 1858 to 63 in 1875 for goods. In Ireland they decreased from 66 in 1858 to 54 in 1875 for passengers, and increased from 34 in 1858 to 46 in 1875 for goods.

PASSENGER RECEIPTS.

There has been during the year an increase of £226,155 from first-class, a decrease of £256,589 from second-class and an increase of £639,224 from third-class passenger receipts. The receipts from first-class passengers were £3,948,812 in 1870, £4,148,108 in 1871, £4,319,185 in 1872, £4,373,274 in 1873, £4,499,351 in 1874 and £4,725,506 in 1875; and those for second-class passengers were £4,925,542 in 1870, £5,167,535 in 1871, £4,198,201 in 1872, £3,984,718 in 1873, £4,099,181 in 1874 and £3,942,592 in 1875; but those from third-class passengers increased from £7,473,727 in 1870 to £2,115,304 in 1871, to £10,318,761 in 1872, to £11,750,588 in 1873, to £12,346,805 in 1874 and to £12,985,829 in 1875. The numbers of first-class passenger journeys increased from 31,839,091 in 1870 to 35,642,199 in 1871, to 37,678,538 in 1872, to 38,310,754 in 1873, to 39,274,759 in 1874, and to 40,708,886 in 1875; and while the second-class passenger journeys were 74,153,113 in 1870, 81,021,940 in 1871, 72,459,562 in 1872, 70,327,428 in 1873, 72,262,963 in 1874, and 70,525,171 in 1875; the passenger journeys of the third-class increased continuously from 224,012,194 in 1870 to 258,556,615 in 1871, to 312,736,722 in 1872, to 346,682,006 in 1873, to 366,302,689 in 1874, and to 392,741,177 in 1875.

The general inference may be drawn from these figures, that the first-class fares and facilities are so far satisfactory as to lead to a progressive and continuous increase of first-class passengers; that the second-class fares, in proportion to the advantages afforded, are not sufficient even to keep up the number of second-class passengers; and that the third-class traffic is the most elastic and most worthy of attention, with a view to increase of facilities and accommodations, as the most profitable to the companies. At the same time, it must not be forgotten that such general inferences are subject to important modifications on different systems, and that the conditions of passenger traffic vary materially on different parts of the same system.

The numbers of season and periodical tickets increased from 156,403 in 1870 to 189,392 in 1871, to 272,342 in 1872, to 314,579 in 1873, to 493,957 in 1874, and to 507,257 in 1875; these totals being inclusive of workmen's weekly tickets. The figures below show the numbers of workmen's weekly tickets issued by a few important companies during the year 1875: Great Eastern, 52,837; London, Chatham & Dover, 26,715; North Staffordshire, 19,584; Caledonian, 17,017; Manchester, Sheffield & Lincolnshire, 12,022.

The receipts from season and periodical tickets have increased from £286,488 in 1870 to £781,778 in 1871, to £802,348 in 1872, to £978,967 in 1873, to £1,069,181 in 1874, and £1,151,248 in 1875. The receipts from luggage, parcels, carriages, horses, dogs, mails and such miscellaneous sources of traffic by passenger trains, have increased from £2,262,669 in 1870 to £2,406,002 in 1871, to £2,553,595 in 1872, to £2,764,020 in 1873, to £2,876,893 in 1874, and to £3,009,060 in 1875.

GOODS RECEIPTS.

The receipts from goods traffic as distinguished from those from passenger traffic are taken to include receipts on account of the conveyance of minerals, general merchandise, live stock, and all traffic by goods trains. But it must be remembered that on some railways the greater portion of the traffic, and on other railways smaller portions of the traffic are carried in mixed trains; and that while the receipts from goods and passenger traffic are kept separately, no attempt is made to separate the expenses of goods and passenger trains from one another. The total receipts from goods trains have increased from £24,115,159 in 1870 to £26,484,978 in 1871, to £29,016,559 in

1872, to £31,821,529 in 1873, to £32,005,883 in 1874, and to £33,268,072 in 1875; and of these the receipts from the conveyance of minerals were £9,392,518 in 1870, £10,029,253 in 1871, £11,226,157 in 1872, £12,605,462 in 1873, £12,450,256 in 1874, and £13,405,283 in 1875; while those from the conveyance of general merchandise increased from £13,810,196 in 1870 to £15,418,171 in 1871, to £16,687,890 in 1872, to £18,047,756 in 1873, to £18,375,922 in 1874, and to £18,630,490 in 1875; and those from the conveyance of live stock increased from £912,450 in 1870 to £1,087,558 in 1871, to £1,077,967 in 1872, to £1,144,760 in 1873, to £1,156,381 in 1874, and to £1,204,548 in 1875. In considering the relative importance of these branches of traffic, it may be pointed out that the general merchandise receipts were for 1871 about 15 times; and for the years 1872 to 1875 between 15 and 16 times the live stock receipts; while the mineral receipts, after having decreased, as between 1873 and 1874, from 11.1 to 10.8 times, again reached 11.1 times the live-stock receipts in 1875. In other words, in the year 1875 the receipts from the conveyance of general merchandise formed 56.00 per cent., those from the conveyance of minerals 40.30 per cent., and those for the conveyance of live stock 3.62 per cent. of the total goods receipts; leaving .08 per cent., representing a sum of £27,761, accounted for under the head of unclassified receipts from goods traffic.

RECEIPTS PER OPEN MILE.

The total receipts per mile of open railway, which increased from £2,786 in 1870 to £3,064 in 1871, to £3,244 in 1872, and to £3,462 in 1873, fell to £3,459 in 1874, but again increased to £3,540 in 1875. The increase in passenger traffic was £1,235 in 1870 to £1,340 in 1871, to £1,409 in 1872, to £1,483 in 1873, to £1,513 in 1874, and to £1,545 in 1875; while the goods traffic, which increased from £1,551 in 1870 to £1,724 in 1871, to £1,885 in 1872, and to £1,979 in 1873, after having fallen to £1,946 in 1874, again increased to £1,997 in 1875.

The total receipts per open mile were, for 1875 £1,225 in Ireland, £2,417 in Scotland, and £2,222 in England; against, for 1874, £1,186 in Ireland, £2,309 in Scotland, and £2,142 in England; against, for 1873, £1,209 in Ireland, £2,324 in Scotland, and £2,139 in England; against, for 1872, £1,140 in Ireland, £2,144 in Scotland, and £2,895 in England; against, for 1871, £1,118 in Ireland, £1,986 in Scotland, and £3,672 in England; and against, for 1870, £1,049 in Ireland, £1,847 in Scotland, and £3,322 in England. The receipts per open mile from mail traffic were for the United Kingdom £47 for 1858, £37 for 1870, £38 for 1871, £39 for 1872, and £40 for each of the years 1873, 1874 and 1875.

WORKING EXPENDITURE PER OPEN MILE.

The total expenditure per open mile for the United Kingdom was £1,357 in 1870, £1,471 in 1871, £1,622 in 1872, £1,866 in 1873, £1,924 in 1874, and £1,933 in 1875. In England it was £2,316 in 1875, against £2,294 in 1874; in Scotland, 1,266 in 1875, against £1,312 in 1874; and in Ireland, £677 in 1875, against £676 in 1874. The following is a detailed statement of the different branches of expenditure per open mile for the years 1873, 1874 and 1875:

	1873.	1874.	1875.
Maintenance of way and works.....	£366	£398	£393
Locomotive department.....	567	549	519
Rolling stock.....	148	156	165
Traffic expenses.....	594	550	573
General charges.....	70	72	76
Rates and taxes.....	67	73	74
Government duty.....	31	36	45
Compensation for personal injuries.....	23	22	23
Compensation for damage to goods.....	14	15	17
Legal and parliamentary expenses.....	24	19	16
Miscellaneous.....	32	35	30
Total.....	£1,866	£1,924	£1,933

TRAIN-MILEAGE RECEIPTS AND EXPENSES.

The total number of miles run by trains during the year 1875 was 209,528,156, against 200,494,263 during 1874, showing an increase of 9,043,923 miles, or, say, 4½ per cent., which was about 3 per cent. more than the increase of 1874 over 1873. Of the above 100,731,071 miles were by passenger trains, and 104,635,085 miles by goods and mineral trains. The receipts per train mile were 61.63d. for 1870, 63.13d. for 1871, 64.66d. for 1872, 67.71d. for 1873, 68.11d. for 1874, and 67.56d. for 1875; while the working expenses per train mile were 30.02d. for 1870, 30.38d. for 1871, 32.27d. for 1872, 36.57d. for 1873, 37.89d. for 1874, and 36.88d. for 1875. Analyzing these train mileage receipts and expenses as regards the three kingdoms, it would appear that the train mileage receipts were for 1870, 1871, 1872, 1873, 1874 and 1875 respectively: In England, 63.64d., 64.93d., 66.21d., 69.48d., 69.55d. and 68.44d.; in Scotland, 51.69d., 52.58d., 54.81d., 57.58d., 60.03d. and 62.08d.; and in Ireland, 60.36d., 61.73d., 62.02d., 64.31d., 64.19d. and 66.05d.; while the train mileage expenses during the same periods were—in England, 30.68d., 30.81d., 32.83d., 37.18d., 38.52d. and 37.54d.; in Scotland, 25.86d., 26.22d., 28.33d., 32.61d., 34.10d. and 32.52d.; and in Ireland, 31.54d., 32.66d., 33.30d., 35.85d., 36.61d. and 36.45d.

TRAIN MILEAGE EXPENSES IN DETAIL.

The details of the expenses per train-mile for the United Kingdom for the years 1873, 1874 and 1875 were as follows:

	1873.	1874.	1875.
Way and works.....	7.15d.	7.86d.	7.49d.
Locomotive charges.....	11.09	10.80	9.90
Rolling stock.....	2.90	3.06	3.15
Traffic expenses.....	10.25	10.85	10.94
General charges.....	1.37	1.41	1.45
Rates and taxes.....	1.31	1.42	1.41
Government duty.....	0.62	0.73	0.86
Compensation for personal injury.....	0.44	0.43	0.44
Compensation for damage to goods.....	0.28	0.30	0.32
Legal and parliamentary expenses.....	0.48	0.38	0.34
Miscellaneous.....	0.63	0.69	0.58
Total.....	36.57	37.89	36.88

The total cost per train mile showed an increase in 1871 of .31d., in 1872 of 1.94d., in 1873 of 4.30d., and in 1874 of 1.32d., but a decrease in 1875 of 1.01d. It will be seen also that while the total expenditure per open mile increased by £114 in 1871, £115 in 1872, £244 in 1873, and £58 in 1874, the increase in 1875 was only £9; and that while in the permanent way and locomotive departments there had been both per train mile and per open mile a continuous increase until 1874, in the year 1875 there was a decrease in both these branches of expenditure. It will also be noticed that while the rolling stock charges in 1875 increased from £156 to £165 per open mile, and from 3.06d. to 3.15d. per train mile, the traffic expenses only increased from £550 to £573 per open mile, and from 10.83d. to 10.94d. per train mile, being less than the average annual increase, and this, too, in spite of the outcry which has been raised in some quarters against the expense of working the block system and employing extra signalmen for the purpose.

The figures in Table No. 8 showing the details of the train-mileage expenditure on the lines of certain companies will be found to vary considerably for the same branches of expenditure, and to a much greater extent than might, on a fair consideration of the different conditions and circumstances under which the various lines were worked, be reasonably expected. Thus the total expenditure per train mile varied in 1875 from 31.85d. for the Caledonian to 43.34d. for the Lancashire & Yorkshire; the charges for maintenance of way and works varied from 4.97d. for the London, Brighton & South Coast to 11.64d. for the Great Southern & Western (of Ireland); the total charges for locomotive and rolling stock varied from 11.01d. for the Great Western to 18.00d. for the Northeastern; and the traffic and general charges varied from 9.26d. for the Great Southern & Western of Ireland to 18.07d. for the Lancashire & Yorkshire.

shire & Yorkshire. It is very difficult, on any supposition of annual charges against revenue for maintenance and renewals being continuously and regularly made, to account for some of the excessive variations in the charges so made in the same year on the above and other lines of railway.

NET PROFIT PER TRAIN MILE.

The net profit per train mile increased from 31.61d. in 1870 to 32.8d. in 1871, decreased to 32.29d. in 1872, to 31.14d. in 1873, and to 30.22d. in 1874, but again increased to 30.68d. in 1875. The following statement shows the net profit per train mile in each division of the United Kingdom for each of the years 1870, 1871, 1872, 1873, 1874 and 1875: England and Wales, net profit—1870, 32.96d.; 1871, 34.12d.; 1872, 33.38d.; 1873, 32.30d.; 1874, 31.03d.; 1875, 30.90d. Scotland, net profit—1870, 25.83d.; 1871, 26.36d.; 1872, 26.48d.; 1873, 24.97d.; 1874, 25.93d.; 1875, 29.56d. Ireland, net profit—1870, 28.82d.; 1871, 29.07d.; 1872, 28.72d.; 1873, 28.46d.; 1874, 27.58d.; 1875, 29.60d.

COMPENSATIONS FOR PERSONAL INJURY AND DAMAGE TO GOODS, &c.

The total amounts paid for personal injury were—in 1870, £232,500; in 1871, £212,334; in 1872, £299,389; in 1873, £364,509; in 1874, £355,876, and in 1875, £381,038; and there was paid for damage to goods, &c., in 1870, £123,931; in 1871, £141,288; in 1872, £186,619; in 1873, £231,707; in 1874, £251,293, and in 1875, £278,917. But these amounts do not represent the total cost of accidents on railways. They do not include the cost of repairs to the rolling stock or to the permanent way and works, or the deterrent influence, which is sometimes considerable on passenger traffic; but the damages to goods on account of which compensations are paid are not, on the other hand, all the result of accidents. The compensations paid on account of injury or damage together amounted, in 1875, for England, to £591,891; for Scotland, to £39,595, and for Ireland, to £28,469, making a total for the year of £659,955. And the totals under the same heads were, in 1858, £123,071; in 1870, £446,431; in 1871, £453,622; in 1872, £486,008; in 1873, £596,216, and in 1874, £607,169.

ROLLING STOCK.

It will be seen from Table No. 10 that on the railways in the United Kingdom the number of locomotive engines increased from 9,379 in 1870 to 10,490 in 1871, to 10,933 in 1872, to 11,435 in 1873, to 11,935 in 1874, and to 12,439 in 1875; and that the number of vehicles, exclusive of locomotives, increased from 289,994 in 1870 to 311,427 in 1871, to 337,899 in 1872, to 362,785 in 1873, to 379,899 in 1874, and to 393,799 in 1875, giving an increase per open mile from .60 for 1870 to .68 for 1871 and 1872, to .71 for 1873, to .73 for 1874, and to .75 for 1875, as regards locomotive engines; and an increase per open mile from 18.66 for 1870 to 20.25 for 1871, to 21.36 for 1872, to 22.56 for 1873, to 23.10 for 1874, and to 23.64 for 1875, as regards other vehicles. The number of vehicles other than locomotives showed per open mile a slight decrease from 1858 to 1870, but a comparatively large increase for the five years from 1870 to 1875. In 1875 the numbers of locomotive engines and vehicles were respectively considerably more than double the numbers of engines and vehicles in 1858. As regards the rolling stock in use on railways which is the property of private owners, or of companies other than railway companies, no returns are received or can be obtained; but the number of such vehicles is known to be very considerable and it would be very desirable to have information in regard to them. The question, which is a very important one, of the railway companies becoming the owners of all the rolling stock employed on their lines does not appear to have made further progress.

SUMMARY.

The leading features of the railway system of the United Kingdom at the end of 1875 are, then, as follows: A total sum of £280,223,494 had been expended on 16,658 miles of railway, of which 8,898 were laid with two or more lines of rails, and 7,760 were single lines, at a cost of about £37,800 a mile. There were 12,439 locomotive engines or about one to every mile and a quarter; and 393,799 vehicles, or about 23½ per mile, besides great numbers of wagons, of which there is no means of forming an estimate, belonging to traders and companies other than railway companies. By the running of trains over 209,528,156 miles, £58,982,753 were received during the year, of which £33,198,186 were expended in working and maintenance, and £25,784,567 remained as net profit, so that 55 per cent. of the gross receipts were expended in earning them. There were 506,975,234 passenger journeys, besides the journeys of 597,257 season and periodical ticket-holders, and 200,069,651 tons of goods and minerals, besides a large number of live stock, were conveyed. The average rate of dividend on ordinary capital was 4.72 per cent., and on the total capital 4.54 per cent., including £47,058,945 of capital which received no interest or dividend. The average cost of working each train was 36.88d. per mile, the average receipt from each train was 67.56d. per mile, and the average net profit from each train was 30.68d. per mile. The total cost of working was £1,933 per open mile, £3,540 per open mile were received, and the net profit was £1,607 per open mile.

The more prominent facts connected with traffic working in 1875, as compared with 1874, were as follows: There was an increase of gross receipts amounting to £2,083,255, but also an increase of working expenses amounting to £550,679. There was an increase of £226,155 in first-class and of £639,224 in third-class, but a decrease of £256,589 in second-class passenger receipts. While there was an increase of 4,434,127 in the numbers of first-class and of 26,438,488 in the numbers of third-class passenger journeys, there was a decrease of 1,737,799 in the number of second-class passenger journeys. There was an increase in the receipts from goods, minerals, etc., of £1,262,189.

As between 1874 and 1875, the principal differences in the cost of working and maintenance per train mile were in way and works and locomotive charges. In the former of these there was a decrease of .36d., or rather over a third of a penny; and in the latter a decrease of .9d. Comparing 1870 and 1875, there was an increase of 1.6d. in way and works, and of 1.98d. in locomotive charges, while there was also an increase of 2.3d. in traffic expenses.

The gross receipts of the railways increased from £23,856,749 in 1858 to £28,982,753 in 1875, having considerably more than doubled in seventeen years. From 1858 to 1870 the increase was £19,480,321, or 81 per cent., for the period of twelve years; and from 1870 to 1875, £15,555,683, or 36 per cent., for the period of five years. As between 1858 and 1875, the average annual increase taking one year with another, the average annual increase in the gross traffic receipts has been at the rate of 5.48 per cent.; but it may be observed that while the increase in the receipts was at the rate of 8.50 per cent. for 1871, 8.81 per cent. for 1872, 8.52 per cent. for 1873, 2.20 per cent. for 1874, and 3.66 per cent. for 1875, the increase in the total (railway) working expenditure for the same periods was 6.79 per cent., 13.35 per cent., 17.18 per cent., 5.28 per cent., and 1.74 per cent. respectively.

Contributions.

Popular Mistakes Concerning Freight Bolster Springs.

TO THE EDITOR OF THE RAILROAD GAZETTE:

Some railroad men think that if a spring holds up a big load and is low priced, it is the spring to buy in "these hard times."

This is a mistaken idea, and mistakes of this sort make "hard times" for a great many railroads.

I will relate a case in point:

About three years ago I was desired, in competition with a friend in the spring business, to propose an equipment of bolster springs for 300 freight cars, to fulfill the following requirements, viz.:

"The best spring that could be furnished to carry a ten-ton load, and cost not more than \$30.00 per car."

My proposition was to furnish an equipment for each car, of 12 nested spiral springs $5\frac{1}{2} \times 7$, 2 spirals per nest, with a carrying capacity of 21,000 lbs. at one-half compression and containing 210 lbs. steel. Price \$29.40 per car (=14 cents per pound).

My friend proposed to furnish for each car:

4 iron-cased springs, 7 spirals per spring, 7 in. high over castings, capacity of 26,000 lbs. at one-half compression (amount of material not stated). Price, \$25 per car.


The contract was awarded to my friend on the following grounds:

1. That his spring held up the greatest weight, and was therefore the best.

2. That his price was the lowest by \$4.40 per car, thereby "saving" the company \$1,320 on this lot of 300 cars.

These conclusions were the result of a private "test" (?) with a lever machine, from which "test," "interested parties" (i. e., spring men) were excluded.

The most remarkable thing about this remarkable stroke of "economy," as I afterwards discovered, was the fact that the company paid my friend a profit of about 75 per cent. on his



"best spring that could be made for less than \$30.00 per car," while my proposition contemplated a margin of about 10 per cent. (This was in the early part of 1873.)

His springs contained 98 lbs. of steel per car and 116 lbs. iron castings against my 210 lbs. net steel (no castings); yet the "spring tested" showed that his carried the most weight.


I was informed that my friend, in response to the question of a railroad official, explained this discrepancy by saying that it was owing to the superior quality of steel used in making his springs.

The fact was, that we were both buying the same quality of steel, from the same manufacturer, at the same price, at that time, and that this "remarkable" showing was accomplished by a simple mechanical trick, with which all spring men are familiar.

Let us refer to the rudimentary principles of spring-making and see how this railroad company came to pay \$7,500 for "springs" that cost \$4,500 (a liberal estimate of cost in those days), and were really not worth their cost, as springs.

It is a rule, well understood in spring-making, that increase of carrying capacity, or, more properly speaking, resisting force of a spring, is created by distortion of the fibres of steel of which it is composed.

Thus in making a leaf for a semi-elliptic, of a plate of steel say 30 in. long, in proportion as the curve given the leaf defects from the straight line A (its original form), as shown in illustration below, we get increased carrying capacity, but less elasticity and vitality.



If a leaf deflecting 3 in. from A, as shown by line B, takes 500 lbs. to compress it $\frac{1}{2}$ in., a greater weight would be required to compress it $\frac{1}{4}$ in. If the same leaf were made to conform to line C, which shows a deflection of 5 in. from A. Increased strength would be acquired, but less elasticity, and so on until we get to the form of the perfect arch D, when the maximum of strength, or "carrying capacity" is reached, with an entire absence of elasticity.

The vitality or life of a spring is the maximum number of vibrations it is capable of, under a given pressure, before losing "set" or breaking.

If the amount of resisting force required of it at each vibration is increased by changing its form, the number of vibrations of which it is capable will be proportionately lessened.

Thus, in the above illustration, if at 3 in. "set" it requires a pressure of 500 lbs. to produce a vibration of $\frac{1}{2}$ in., and at 5 in. "set" say 800 lbs. to produce $\frac{1}{2}$ in. vibration, this piece of steel would be capable of a less number of vibrations under the second condition than under the first, before becoming worn out or broken, as it must ultimately become under either condition.

It is precisely the same in the spiral, which embodies the same principle.

Now, I believe that if it is important to have "springs" in a car, it is quite as important to have something that contains the element of "spring" (viz., elasticity), which many so-called "springs" do not. If it is not important, we might with propriety proceed further in the direction of cheap spring economy and put in a strong cast-iron "spring" that would "hold up" as much load as any of them, and be much cheaper.

If a spring is designed to absorb the shocks of service, it is

manifestly wrong to deprive it of the very feature upon which it depends for its quality at an absorbent, in pursuit of the mistaken idea that you can thereby get a maximum amount of service from a minimum amount of material.

For purposes of spring, fig. 2 is better than fig. 3, because the latter is not so much like fig. 4, or a simple post.

If, for experiment, you were to ride over a rough road, and try each of the above forms, you would find that the shocks communicated by rough joints, etc., would have the following effects:

No. 4 would hurt a passenger like a succession of kicks.

No. 3 would "bounce" him violently.

No. 2 would absorb the shocks, and a passenger would be sensible only of a slight undulating motion, something like that of a good buggy spring.

If you were confined to these three forms for the selection of a spring to ride upon, you would undoubtedly select the largest, and if your freight cars and road-bed had a voice in the matter, they would undoubtedly agree with you.

This was the mistake in the matter of the 300 cars. The official who decided the matter did not make an intelligent comparison of the two propositions, and here are the results of his error:

1. The "springs" were too rigid for good service under empty cars or light loads, thereby causing serious damage to cars and road-bed.

2. Nearly all of them became broken.

3. All of them have been removed and replaced with other springs.

4. The railroad is now in the hands of a Receiver.

I will not say positively that this clean waste of \$7,500 put the company into a Receiver's hands, but it did it share.

The above experience, and similar instances that have come to my notice, encourage me to suggest that it is not always sound economy to buy a cheap spring because it will carry a big load.

GEO. KINSEY.

CINCINNATI, Jan. 12, 1877.

Railroads from the United States through Mexico and Central and South America to Valparaiso and Buenos Ayres, and through British Columbia, Alaska and Kamtschatka to Japan, China, the East Indies and Europe.

TO THE EDITOR OF THE RAILROAD GAZETTE:

In a late number of your valuable paper there was an article referring to the proposed line of railroad from San Francisco to Valparaiso and Buenos Ayres, through Mexico and Central and South America, respecting which project I take leave to say, that long since it appeared to me to be a most desirable undertaking, opening as it would to the various industries of the United States new outlets for their productions, the several States through which it would be constructed possessing all the elements of commercial wealth, and offering great inducements for the expansion of American enterprise and industry; and with this great object in view, at the opening of the Centennial exhibition, I submitted to the Chamber of Commerce and Board of Trade at Philadelphia a plan for the holding of a convention in that city, for the purpose of bringing the subject not only before the American people, but also before the people of the several States through which it would pass, representatives from which being then present at the exhibition in greater number than ever heretofore. I also submitted it to the Emperor of Brazil and his minister to this country, and also to other ministers from the South American republics, my project being to recommend to the several States of Central and South America the construction of a line of railroad through their respective territories running north and south, and so arranged that all united would form a continuous direct line from Mexico to Valparaiso, Buenos Ayres and Rio Janeiro.

The matter was not brought forward publicly at Philadelphia, but it is now very gratifying to ascertain that it has found favor with the people of San Francisco, and that some of the leading men and capitalists of that city have taken hold of it, and propose to carry it forward energetically, as they do whatever they determine on.

The construction of this road would give a great impetus to our manufacturing and mercantile interests, and to every branch of trade and commerce generally, opening, as it would with others, the markets of the interior of those countries, particularly of the great and rich empire of Brazil, with which important country our speediest mode of communication now is by way of Liverpool, England, and from there by steamship to Rio Janeiro.

By the construction of this route the United States would also be brought into closer connection with the growing settlements of Australia and Southern Africa, by lines of steamships from Valparaiso and Buenos Ayres.

It is evident therefore that the completion of this project is of great importance and deserving of all the aid and encouragement which the American people can give it.

But to complete our system of railroads and bring the United States into direct communication with the other great divisions of the globe there is one route to be constructed which is destined to connect this continent with Asia and Europe.

The European and Asiatic profiles of that line have already been surveyed and marked out by Russian engineers under the authority of their government—that is, from Moscow via Orenburg to Peking and a port on the Yellow Sea in China, and via Irkutsk to Nicholasieff on the Amoor River, and to Ochotsk, thus connecting their empire with the great empires of China and Japan; for through the Russian island of Sagalien by a branch from Nicholasieff the connection with the Japanese empire then becomes a matter of easy accomplishment.

For the people of the United States to share in all the advantages to be derived by the completion of this undertaking, it may be necessary for them through the medium of their government to approach that of Russia, and by treaty lay the foundation for the undertaking simultaneously by both people.

If the people of the United States will construct a railroad from Washington Territory, connecting there with the Northern Pacific, and through British Columbia and Alaska to a port on Behring Strait, which is a total length of only about 1,500 miles, there cannot be a doubt but that the Russian Government will authorize and encourage the construction of a railroad from Ochotsk through Kamtschatka to a port on their side of Behring Strait, thus completing a continuous line of railroad from Valparaiso and Buenos Ayres to Asia and all Europe through the United States.

In aid of commerce between distant nations the greatest achievements have been accomplished frequently through the instrumentality of those not at all engaged in that pursuit.

The missionary, and the man of science, and the explorer, are its pioneers. So it was the Jesuit fathers who first lifted the veil of mystery that separated China, Japan, our western territories, the interior of South America, Brazil and Paraguay from the then outer world. To Humboldt not only the scientific but the commercial world is indebted; and Livingston, at the cost of his life, and Stanley, have penetrated the secrets of Central Africa, and pointed out the road for the engineer to lay the iron bands across the desert to the rich interior regions of that land of mystery. In the quiet of his study our scientist, Professor Henry, whom the learned bodies of all countries delight to honor, has given his consideration to this project submitted to him by me, and he pronounces it not only feasible, but a work of national importance, worthy of the age, and which ought to be carried forward. I have also submitted it to the government of British Columbia, where it has been approved and encouraged, and obtained the promise of all the aid that can be there afforded. I also had it brought before the European Geographical Convention held in Paris, in May, 1875, where it was warmly approved by the Russian delegate.

Through your influential journal, representing as it does so many various interests that would be benefited by the construction of this great work, I submit it for the earnest consideration of the people of the United States, hoping also that the press may lend its powerful aid in calling the attention of statesmen, legislators and the public generally to the consideration of its importance.

JOHN A. LYNCH.

WASHINGTON, D. C., Dec. 26, 1876.

[Before we build these roads, suppose we do two things: first estimate the amount of traffic which they would be likely to get, and second, learn their cost. Meanwhile, we may as well remember that the seas are not unnavigable, that ten miles of railroad will cost as much as a first-class ocean steamer, and that if the steamer don't pay on one route it can be put upon another, while if the railroad don't pay, the capital cannot be transferred but is sunk forever.—EDITOR RAILROAD GAZETTE.]

A Suggestion on Inspecting Bridges.

CLEVELAND, Ohio, January 22, 1877.

TO THE EDITOR OF THE RAILROAD GAZETTE:

I submit, for the consideration of engineers having charge of the erection and maintenance of railway bridges, the subjoined suggestion of a plan for enabling their bridge inspectors to determine whether or not each rod under tension in a bridge has been properly set up in the erection of the structure; and at any time afterward whether or not each such rod is doing its duty.

When a bridge is about to be set up, let one rod out of each lot of a certain length and diameter be suspended at one end and loaded at the other end with an actual weight equivalent to the strain that every rod of that length and diameter ought, according to the calculations of the designer of the bridge, to be subjected to in the structure when ready for the imposition of its live load. Then put upon the rod, with white paint, a ring, at, say, five feet above the highest point at which the rods will be held in the angle-blocks on the lower chord of the bridge. Then provide a steel hammer, of a known weight, fitted with a handle of a known length, and as many tuning-forks as there are sizes of rods in the bridge. Then with his left hand, with his left arm fully extended, let the inspector hold a tuning-fork firmly against the rod, at the painted ring, while with his right hand, with the arm fully extended, he strikes the rod, at the ring, a smart blow with the hammer. Then, immediately, removing the tuning-fork, let him note the sounds given out by the rod and the fork respectively, and by filing the fork bring the fork into tune with the rod. Then let a designating number be stamped upon both rod and tuning-fork; and repeat the operation for each set of rods in the bridge. Thereafter, when the bridge is set up, and still thereafter, when the inspector is to go through that bridge, he will take the hammer and set of tuning-forks belonging to that structure, and tune his rods. Thus may he guard against, or detect, that condition too frequently existing in bridges, under which some rods are unduly strained and some are doing almost no work.

J. M. GOODWIN.

A Woman's Opinion of Passes.

Gail Hamilton says that her experience with free passes has been of the most short, slender and spasmodic kind, but so far as it has extended it has been one of unalloyed delight. "It has always seemed a waste," she says candidly, "to pay money for going from place to place, because you want all your money to spend when you get there. I have never yet refused a railroad pass, and Heaven helping me, I never will!"

Good Wages.

An exchange says that an employee in the repair shops situated in its town, being asked how business was replied: "Oh, first rate. We don't get any pay to speak of; but they don't charge us any admission for going into the shops yet."

A Fast Road.

The Litchfield (Conn.) Engineer tells a story of a man who left a train on the Shepaug Railroad at Washington and started to ride home in his sleigh. Suddenly recollecting that he had left a package in the car, he turned his horse and drove to New Preston, the next station. After waiting there some time the train came up and he entered the car and recovered his package.



Published Every Friday.

CONDUCTED BY

S. WRIGHT DUNNING AND M. N. FORNEY.

CONTENTS:

Page.	Page.
ILLUSTRATIONS:	EDITORIAL NOTES..... 41
Consolidation Locomotive for the Pennsylvania Railroad..... 35, 36, 37	NEW PUBLICATIONS..... 41
Freight Bolster Springs..... 39	GENERAL RAILROAD NEWS:
CONTRIBUTIONS:	Elections and Appointments..... 42
Railroads from the United to the East Indies and Europe..... 39	Personal..... 42
Popular Mistakes Concerning Freight Bolster Springs..... 39	Traffic and Earnings..... 42
A Suggestion on Inspecting Bridges..... 39	The Scrap Heap..... 43
EDITORIALS:	Railroad Law..... 43
Train Accidents in 1876..... 41	Old and New Roads..... 43
The Paris Exhibition..... 40	Train Accidents in December..... 45
Exporting Fresh Meat..... 41	ANNUAL REPORTS:
	Connecticut River..... 45
	Delaware..... 45
	MISCELLANEOUS:
	The Ashtabula Accident..... 35
	British Railroads in 1875..... 41
	Reporting Foreign Cars..... 41

Editorial Announcements.

Passes.—All persons connected with this paper are forbidden to ask for passes under any circumstances, and we will be thankful to have any act of the kind reported to this office.

Addresses.—Business letters should be addressed and drafts made payable to THE RAILROAD GAZETTE. Communications for the attention of the Editors should be addressed EDITOR RAILROAD GAZETTE.

Advertisements.—We wish it distinctly understood that we will entertain no proposition to publish anything in this journal for pay, EXCEPT IN THE ADVERTISING COLUMNS. We give in our editorial columns our own opinions, and those only, and in our news columns present only such matter as we consider interesting and important to our readers. Those who wish to recommend their inventions, machinery, supplies, financial schemes, etc., to our readers can do so fully in our advertising columns, but it is useless to ask us to recommend them editorially, either for money or in consideration of advertising patronage.

Contributions.—Subscribers and others will materially assist us in making our news accurate and complete if they will send us early information of events which take place under their observation, such as changes in railroad officers, organizations and changes of companies, the letting, progress and completion of contracts for new works or important improvements of old ones, experiments in the construction of roads and machinery and in their management, particulars as to the business of railroads, and suggestions as to its improvement. Discussions of subjects pertaining to ALL DEPARTMENTS of railroad business by men practically acquainted with them are especially desired. Officers will oblige us by forwarding early copies of notices of meetings, elections, appointments, and especially annual reports, some notice of all of which will be published.

TRAIN ACCIDENTS IN 1876.

Our record of train accidents for the month of December enables us to make a resume of the accidents of the year, in which we classify the accidents by their nature and causes, hoping thereby to throw some light on causes of accidents, and to indicate the directions in which efforts should be made to lessen their number and mitigate their consequences.

Before going further, we will repeat what we have often said in connection with this record, but concerning which errors are often made by those who comment on it, that it is a record of train accidents only, and not of all casualties occurring on railroads. The numerous cases where men, animals or vehicles are run over by passing trains are not chronicled in our record except when they cause the derailment or other injury to the train (which seldom happens); and such accidents as happen to persons falling from trains, etc., are likewise foreign to our record, which is one of train accidents only. Further, our sources of information are chiefly the newspapers, with some help from correspondents. Papers from all parts of the country are searched, and not many accidents which are reported at all escape us. But there are a great many accidents which are never reported in print. Those which cause death or injury to a person, considerable destruction of rolling stock or considerable delay to trains are usually reported. Thus our record is chiefly of the more serious accidents. Probably not many are omitted which cause death or injury to passengers or train men, and as a record of injuries to persons by train accidents it is approximately complete.

The year 1876 was a favorable year for working railroads because of the mildness of the winter; and the severity of the weather—the degree of cold and the amount of snow—appears to be the greatest predisposing cause of accidents, the months of very severe weather with many snow storms invariably showing a very large number of accidents. January and February of 1876 were unusually mild, and accidents then were few; March was stormy in some parts of the country, and the effect is shown in the list of accidents. December again was a snowy month, or part of it was, in some districts, but it seems not to have increased accidents greatly. The effect of the severe weather we have been experiencing will be seen more fully in the record for January, 1877, when it is made up.

There was one unusual occasion for accidents in 1876 in the extraordinary passenger traffic of the three fall months due to the Centennial Exhibition. On many roads trains were almost constantly overloaded, and very frequently behind time; on several they were multiplied to an extent never known before. This complication and irregularity of traffic is likely to lead to accidents; but in this case the number of accidents, though larger than usual, seems not to have been in proportion to the increased traffic, and the railroad companies showed decided ability in adapting their operations to the emergency.

There was one other reason why it might have been suspected that 1876 would go hard with the railroads, and that is their poverty. For three years the managers of most roads had been giving their best energies to the enforcement of severe economy, and it was to be expected that in many cases the roads were the worse for it—that road and rolling stock were not in condition to endure hard service much longer. As we have said, they had the mild winter in their favor; but that they endured the other nine months of the year so well seems to us an indication that the number of "starved" roads could not have been unusually great: there always are some.

We have now made records of train accidents for four complete calendar years. The numbers of accidents and of persons killed and injured in them for each of these years have been:

	1873.	1874.	1875.	1876.
Accidents.....	1,263	990	1,201	982
Killed.....	276	204	234	328
Injured.....	1,172	778	1,107	1,097

The number of accidents thus appears to have been nearly the same last year as in 1874, but fatal injuries were more than for any preceding year reported. This is due largely to the catastrophe at Ashtabula, by which 80 persons lost their lives—nearly one-fourth of the victims of all the train accidents of the entire year. Without this, however, the accidents were more than usually fatal, one of the causes of which, doubtless, is the unusual amount of passenger traffic last fall, there having been more accidents to passenger trains than usual. The average number of killed and injured per accident for the four years has been:

	1873.	1874.	1875.	1876.
Killed.....	0.216	0.206	0.195	0.334
Injured.....	0.914	0.800	0.923	1.117

Killed and injured, 1.129 1.009 1.118 1.451

Thus 1876 enjoys the distinction of having had the deadliest accidents. If we were to omit the Ashtabula disaster, there would still be 0.253 killed and 1.113 injured per accident, so that this disaster was not needed to give it this distinction.

The classification of the accidents of each year according to their nature or causes gives the following results:

	1876.	1875.	1874.	1873.
COLLISIONS:				
Rear.....	159	141	131	187
Butting.....	94	104	87	102
Crossing.....	15	18	19	31
Unknown.....	11	15	23	72

	1876.	1875.	1874.	1873.
DERAILMENTS:				
Unexplained.....	185	222	218	315
Broken rail.....	80	107	42	111
Misplaced switch.....	89	81	67	72
Cattle on track.....	46	51	45	54
Wash-out.....	40	44	19	30
Loose or spread rails.....	48	40	14	13
Broken axle.....	38	39	20	21
Accidental obstruction.....	36	37	31	44
Snow or ice on track.....	16	36	13	9
Broken wheel.....	22	33	20	26
Broken bridge or trestle.....	20	26	33	19
Malignous obstruction.....	11	21	22	11
Broken truck.....	10	15	8	7
Broken or defective switch.....	4	15	12	10
Land-slide.....	9	11
Broken or defective joint.....	1	10	5	3
Broken or defective frog.....	3	8	8	4
Wind.....	2	7
Rail removed or displaced.....	7	8	7	16
Broken parallel or connecting-rod.....	2	5
In making flying switch.....	2	4
Failure of coupling or draw-bar.....	1	3	7	8
Broken car.....	2	3
Runaway engine.....	..	3	1	6
Running through siding.....	6	2	3	3
Loose wheel.....	3	2	4	2
Open draw-bridge.....	3	2	6	4
Bad track.....	4	2	13	7
Fall of brake or brake-beam.....	4	9
Carless stopping or starting.....	1	..	3	..
Overloading car.....	2	..
Bad switching.....	2	..
Running over man.....	2
Flood over track.....	2
Others (one each).....	1	3	11	7

	1876.	1875.	1874.	1873.
ACCIDENTS WITHOUT COLLISION OR DERAILMENT:				
Boiler and cylinder explosions.....	22	29	18	19
Broken parallel or connecting-rod.....	7	14	8	11
Broken axle.....	2	13
Cars burned while running.....	11	10	16	2
Broken tire.....	..	9
Broken crank-pin.....	..	1	4	..
Flue collapsed.....	..	5	10	19
Other breakage of rolling stock.....	4	..	2	..
Steam chest explosion.....	2	..
Flue plug blown out.....	2	..
Failure of bridge or trestle.....	2	..
Mass falling on running train.....	1	..	2	..
Accidental obstruction.....	1	11
Malignous obstruction.....	1	3
Unknown.....	2	9

	1876.	1875.	1874.	1873.
TOTALS.....	982	1,201	990	1,283
RECAPITULATION:				
Collisions.....	279	278	260	392
Derailments.....	655	840	654	815
Other accidents.....	48	83	76	76
TOTALS.....	982	1,201	990	1,283
Average number per day.....	2.69	3.29	2.68	3.51

The record of 1876 is more like that of 1874 than any

other. Both years had a mild winter, and the accidents resulting from broken rails were comparatively few. The very large number of accidents from misplaced switches this year is noticeable, and suggests that railroads may have been employing too cheap labor. The number of accidents for which no causes are assigned is smaller than heretofore.

Of the derailments for which causes are assigned, the percentage due to each of the chief causes was as follows in the several years:

	1876.	1875.	1874.	1873.
Broken rail.....	10.6	17.3	9.9	22.2
Misplaced switch.....	18.9	13.1	15.4	14.4
Cattle on track.....	9.7	8.2	10.3	10.8
Wash-out.....	8.5	7.1	2.3	6.0
Loose or spread rails.....	9.2	6.5	3.7	2.6
Broken axle.....	8.1	6.3	4.6	4.2
Accidental obstruction.....	7.1	6.0	11.7	8.8
Broken wheel.....	4.7	5.3	4.6	5.3

As indicating the effect of severe weather on track (not necessarily on iron, however,) we give below the breakages of rails reported for the first and third quarters respectively of each of the four years:

Accidents caused by broken rails in the Quarter including January, February and March and in that including July, August and September, for four years.

	1873.	1874.	1875.	1876.	Total.
First quarter.....	65	20	26	301	301
Third quarter.....	5	5	3	18	18

This indicates that there were eleven times as many accidents by broken rails in the cold as in the hot quarters of the year, and the effect of the severe weather is further shown by a comparison of the breakages in the cold winters of 1873 and 1875 with those in the milder winters of 1874 and 1876.

A more general classification of the causes of derailments gives the following:

	1873.	1874.	1875.	1876.
Defects or failures in permanent way.....	200	146	261	165
" " " " rolling stock.....	73	63	101	76
Negligence, carelessness or malice.....	96	107	114	119
Unforeseen obstructions not malicious.....	111	109	142	107

Considering the fact that the whole number of accidents was smaller than usual this year, it does not look well to have a larger number than ever before ascribed to "negligence or malice," especially as the cases of malicious obstruction were less last year than previously. "Negligence," however, would apply probably to many, if not most, of the cases of defects and failures of road and rolling stock as well to the cases of misplaced switches, open draws, etc., to which we have applied it above. The former, however, have not been unusually numerous, notwithstanding the severe economy exercised.

The great calamity at Ashtabula will doubtless cause renewed attention to one class of accidents at least. We have chronicled during the past four years 98 cases of the failure of a bridge or trestle, nearly every one under a train. None of them had results anything like as serious; but that most of them were comparatively harmless was much more "accidental" than the failure of the structures themselves. The one lesson of the accident record of 1876 likely to be longest remembered is, how terrible may be the results of an error in the construction of a bridge or of negligence in its inspection.

The Paris Exhibition.

From various dealers and manufacturers of railroad material and supplies we learn that quite a respectable foreign trade has grown up as the result of the Centennial Exhibition, and the evidences of the good effect of making our products more widely known by that means are becoming apparent by the demand for them from foreign countries. Most American exhibitors were, we think, very skeptical, at least before and during the early part of the Centennial, of the advantages to be derived from it; but as actual orders are now coming in, at least those who receive them begin to be convinced that it was a good thing to be represented there. It is probable, however, that the Paris Exhibition will afford us a much better opportunity to make our productions known to the whole world than our Centennial did. The attendance "from everywhere" will doubtless be much greater there than it was here, and for that reason exhibitors will be able "to reach to the uttermost parts of the earth." It would therefore, we think, be a cause of regret if American manufacturers and engineers should not make use of the opportunity which will then be presented and should not be adequately represented at Paris. It is especially desirable at the present time that as full and as clear and comprehensive an exhibit as possible should be made of our American system of railroads at Paris. It can of course hardly be expected that our method of doing things will supplant that adopted in the older countries, although the use of Pullman cars, the Westinghouse and Smith brakes makes even that seem not impossible; but in all the countries in which the railroad system is less completely developed our methods are probably better adapted than the more expensive ones in use in Europe.

In order to have a complete exhibit, and one which will represent correctly what we are doing, some systematic effort must be made to bring this about. The experience with the Centennial indicated what perhaps might have been known without it, that if manufacturers expect to make their exhibits what they should be, the

must make them so by their own exertions. Voluntary associations, government aid and Centennial Commissions really accomplished very little. The exhibits which were the best worthy of attention were those which were devised and prepared by the manufacturers themselves. While this was so in special cases, there is one defect in uncombined individual effort. This defect is the want of system. Each person or firm is bent on having its own productions fully exhibited, but usually feels no concern in having all the other products which are related thereto displayed. Thus the manufacturers of steel car-axes showed their products in the most complete and thorough manner, but were totally indifferent about the exhibit of car-wheels. Locomotive builders were anxious that American locomotives should be made known to the whole world, but felt little interest in American cars, and so on through the whole list. Now what we want to call attention to and make as clear as possible is the fact that each one of these parties, or rather that each manufacturer or engineer who supplies the material or machinery which forms a portion of our railroad system, is benefited if the whole system is exhibited. Thus, if the wheel manufacturers exhibit the American cast-iron wheels and show clearly their cheapness, and if orders are given for wheels, the probability is that that fact will lead to the axles being bought here too. If American locomotives are ordered, American boiler-plate will be sure to be used. If our method of laying track and of fastening rails should be exhibited by railroad companies, it would lead to orders for rail fastenings, spikes, switches, etc., being sent here, and so on indefinitely. For this reason each manufacturer or engineer whose productions are employed and form a part of the system is interested, or should be, in having the whole of it exhibited as completely as possible. Now in order to do this some careful forethought must be exercised and a plan must be devised by some one competent head. The mere desultory effort of individual parties or firms cannot, or at least will not, be able to think out and put in execution any systematic plan.

The subject has been discussed with various manufacturers of railroad material and machinery and also with engineers connected either directly or indirectly with railroad work, and it has been suggested that a meeting be called to take the subject into consideration, and to adopt some plan by which such a complete exhibit as has been described could be devised, and that steps be taken to have such a plan carried out. The expense attending it would not be very great if distributed among any considerable proportion of those directly interested in it. The chief difficulty would be in having some responsible head or authority to direct that expenditure. It has been suggested that if such a meeting were called, the subject could be discussed, and a committee then be appointed to report a plan of exhibiting our system of railroading, and that the report be submitted for approval and discussion, and the requisite working machinery be then employed to carry out whatever method is adopted. If these suggestions should meet with a sufficient amount of encouragement, we feel authorized in stating that such a meeting will be called, but it is first necessary to know whether the idea is likely to meet with the approval of those who are chiefly interested in it.

Exporting Fresh Meat.

In reviewing the live stock markets for the year, the New York *Tribune* reports an increase in arrivals of cattle at New York of about 5 per cent., compared with the arrivals in 1875, besides some increase in calves and sheep. As it has been a year of poverty among many and of little or no growth in population, this is somewhat noticeable. But it is probably wholly due to a new development in the trade this year, pointed out by the *Tribune*, which bids fair to become important for a large part of the country and to the railroads which carry cattle. This is the establishment and growth of the export of slaughtered cattle. It says that the average shipments per week are now about 1,000 carcasses from New York and 500 from Philadelphia. These exports were very small at the beginning of the year, but have grown so that several of the steamer companies have fitted up refrigerator compartments at considerable expense especially to accommodate this traffic. The increase in live stock receipts for the year does not indicate the bulk of this business, because there has been at the same an increase in the arrivals of slaughtered beef at New York, brought in refrigerator cars from Chicago, Kansas City, etc.

The importance of this new traffic is the greater because, in the first place, the newer settlements of the Far West are so distant from market that it does not pay to raise grain there; and, in the second place, because most of the country as far west as the middle of Kansas and Nebraska, say, is really good for little else than stock raising, but is very good for that. There is an immense territory which we cannot expect to see utilized for a generation or two unless a market can be found for a much greater than the present supply of cattle. It would not take much of it to overstock the present American market. But if fresh beef can be exported, we can compete for the supply of a market several times as large as our own. If we can supply Europe with fresh beef as we do with breadstuffs and salted provisions, we will find room for a new expansion of our agricultural industries and

occasion for the utilization of a vast territory now unoccupied, and we shall meanwhile add materially to the well-being of the poorer classes abroad. All traffic of this kind is a clear addition to the traffic which previously existed, not a diversion from one form to another, and therefore is to be especially encouraged. At present a considerable part of the profits of the trunk lines and of many Western railroads come from the live stock consumed in New York and New England. A small share even of the supply of a city like London, with four times the population of New York city, is worth contending for.

THE SUICIDE OF MR. CHARLES COLLINS, the Chief Engineer of the Lake Shore & Michigan Southern Railway, is one of the most painful events connected with the horrible Ashtabula disaster; for we suppose that the suicide was indirectly caused by the accident. Mr. Collins took great pride in the road under his charge, or rather he had an affection for it such as a parent has for a child. For many years he had devoted himself to it, and he had so nearly realized his high ideal that the track of the Lake Shore road was cited as a model the country over: such perfection of surface and alignment, ballasting and drainage was hardly to be found elsewhere, or at least was found on the Lake Shore earlier than almost anywhere else. To have his pet road fail and fail so disastrously was doubtless such grief to him as men with lower ideals and less devotion to their work never know, and many cannot comprehend. From the evidence taken during the pending investigations, it seems that Mr. Collins had absolutely nothing to do either with the construction or the erection of the bridge. Its maintenance, however, with that of the rest of the road, was in his charge, and he, we suppose, was properly responsible for its inspection and repair. If the bridge inspector was not competent, or if the inspections were insufficient or too infrequent, the Chief Engineer should have known it and should have had power to remedy the defects.

The report of Mr. Collins' suicide says that he had had little sleep for a long time, and it is altogether probable that he had lost his reason before he took his life. A quiet, unassuming man, he deserves to be remembered as one who has done much to encourage the highest quality of work in the construction and maintenance of permanent way in this country.

THE ERIE ARRANGEMENT SCHEME, which has made so little noise for some months past that many have concluded that it was dead or moribund, now shows some signs of life. Mr. James McHenry seems to give it the benefit of his opposition, but he no longer holds the company in the hollow of his hand. It is said that of the outstanding bonds on which the interest is overdue about \$36,000,000 is held in Great Britain and \$5,000,000 in this country. Holders of a majority of these can decide the fate of the scheme, and, for that matter, of the company itself. If the stockholders do not accept the arrangement while the bondholders do, the result will be simply that, while the reorganized company will not get the benefit of the stock assessments, the old stock will disappear from its capital account, have no voice in its management and no share in its future profits; and the Erie with its present enormous stock capital of \$86,000,000 wiped out would be a snug property for the bondholders. On this head *Herapaths Railway Journal* of Jan. 6 says:

"If shareholders have been hoping against hope that something would turn up to prevent the necessity for the heavy assessment on the shares, both ordinary and preference, they may deceive themselves. The reorganization scheme will be carried, involving the assessments in question. The company urgently want the money that will be thereby raised, and although the time for payment is postponed, it will evidently be enforced. When we say 'enforced' we mean practically so. There is no power to compel a shareholder to pay four or six dollars per \$100 share; but as he is only admitted into the reorganized company upon making such payment, failure in making it means forfeiture of shares."

This, however, is the first expression of confidence in the eventual success of the scheme that we have seen. Most of the English papers which interest themselves in Erie affairs do not venture an opinion on the matter.

THE CRACKING OF STEEL FIRE-BOXES, as discussed by our Master Mechanics' Association, has attracted attention in Germany, where the *Organ for Railroad Progress*, the leading German journal devoted to railroad engineering, publishes a long summary of the report on the subject made to the last convention.

NEW PUBLICATIONS.

Messrs. G. W. & C. B. Colton & Co. have added to their long list of maps a *County and Township Railroad Map of the State of New York*, and a *Railroad Map of Pennsylvania and New Jersey*, from a new plate, on a scale of about 8 1/4 miles to the inch, which excel in clearness and accuracy anything we have seen heretofore. They are substantially railroad maps, giving no towns or post-offices except stations, though the township boundaries and names are given. But the railroads are located with great care, from the actual surveys wherever practicable, and the lettering is of course clearer than it would be on a smaller map. Clear lettering, by the way, is usually a feature of the Colton maps; though in this rapidly growing country the introduction of new railroads and the development of a crop of new towns every year often make awkward work with an old plate which was a model of beauty and clearness when first engraved. The maps under consideration are especially valuable, because in all these States the railroad net work is so complicated, with meshes so small, that it is next to impossible to trace out all the lines on the commoner map on a smaller scale. On Long Island, in New Jersey opposite New York, and in many parts of Pennsylvania this is the case. The map of New York contains also a map of the country for 20 miles around the New York City post-office on a scale of five miles to the inch. We have not been unable to discover any errors in the railroads on this map; a few have been constructed since it was engraved. While speaking of these maps, we desire to call attention to the im-

portance of the work done by these cartographers, and especially to the desirability of the co-operation of railroad officers in their efforts to secure the absolutely accurate mapping of lines of railroad. Very great pains are taken to get this information, and usually the work left for the railroad engineer or officer to whom application is made is of the simplest possible kind, requiring but a very few minutes of work. Yet these applications are too often neglected, or the information sent is sometimes shamefully imperfect. There can be no excuse for not giving an accurate map of a line when it has once been finally located; and those in charge of the surveys might easily give a great deal more information which would be of great value in fixing the as yet imperfectly recorded topography of the country. Nearly all the maps are more or less imperfect—often very imperfect—and every accurate survey of a line, especially in a new district, fixes some points hitherto uncertain. This firm makes most conscientious efforts to secure accuracy and completeness, and preserves all the information obtainable with great care. The result of this labor is that maps have to be made over again periodically; and what with the expense of this work, the indifference of the great mass of map-buyers, and the carelessness of those who have much of the new information, there is no great encouragement to do good work. We certainly should not get as much as we do but that the cartographers put their hearts and their consciences into the work.

Every one has heard of the letters of Professor Reuleaux, the German Commissioner to the Centennial Exhibition, in which he criticised severely the quality of the objects exhibited by his countrymen, and incidentally the course of German manufactures. The letters have now been collected in a pamphlet (*Briefe aus Philadelphia*) of about 100 pages, which is sent us by L. W. Schmidt, of New York. The attention of those familiar with German brochures (and German books are not usually sold bound) will first be attracted to the elegance of the publication. Usually there is not a great deal to be said in favor of German books, aside from their contents. But Professor Reuleaux' pamphlet is as emphatic a protest against "cheap and bad" work as are the letters which it contains. And, when we read his report on the exhibition of books, we find that it was meant to be so. The whole burden of these letters is that German manufactures, or many of them, have deteriorated by the effect of a competition which has been directed entirely to price and not at all to quality. The letters are extremely interesting and suggestive, and though largely devoted to the criticism of German industries, they contain much on other European and American exhibits which is of special value. Professor Reuleaux being one of the best authorities in certain fields. He has a very high opinion of our machine tools, hardware, and many other of our manufactures. We quote the following passage: "Remark that the Exhibition showed America to be taking a leading place and in some things the leading place, among manufacturers of machinery, he adduces the following as evidence: 'In the first place, it has given further development in certain details, to the steam engine, and has been able to give it a perfection of form which is worthy of admiration: a notable sign; for where beauty of form has been developed, is made the object of special care, and has become a subject of criticism, there the difficulties of adapting the form to use must have been overcome already.'"

Valentine & Co., the varnish-makers, have designed some most ingenious methods of advertising, one of which, "*Silhouettes*," is so remarkable as to be well worth noticing, not simply for its artistic character, but for the modesty of its advertisements, which are not permitted to deform or distort the illustrations. They form a little bundle of tinted sheets about 9 in. square, fastened together by an eyelet at one corner, each of which has a silhouette drawn by Mr. F. S. Church. There are sixteen of them inside of the covers, each illustrating a scene to which the name of a vehicle can be attached, as "A Carryall," in which paterfamilias on all fours has his three little ones on his back, etc. There is a refinement, a homeliness and a humor in these which make them very attractive, and have undoubtedly given the collection a place on many parlor tables. The advertising is confined to the simple legend "Valentine's varnishes," on each sheet, a simple card on the front cover and a humorous one on the back cover. We doubt whether there has ever been a more successful attempt to design an advertisement which people would preserve.

Mr. John Woodbridge Davis, C. E., has prepared and published a little treatise, entitled *Formula for the Calculation of Railroad Excavation and Embankment*, which is recommended as affording means of doing the trying work of earth-work computations more expeditiously and much more accurately than by older methods. The work is used as a text-book in the School of Mines of Columbia College, Professors Vinton and Roberts esteeming it very highly. The work is sold by G. S. Roberts, School of Mines, Columbia College.

Reporting Foreign Cars.

Mr. C. H. Allen, Receiver of the Paducah & Memphis Railroad, has issued the following circular, directed to connecting lines dated Dec. 20, 1876:

Commencing this date, we will report daily to the proprietors of foreign cars passing over this road, the movement and mileage of each car separately, for which purpose we will use the enclosed form (No. 132), in connection with which, special attention is directed to the accompanying official time table, showing our stations by numbers which correspond with their actual distances from Paducah, so that the number of miles between any two stations is ascertained by taking the difference between the numbers of those stations.

By means of these reports you will be enabled to determine precisely and readily:

1. The location of each one of your cars on any given day, if upon this road, without incurring the trouble and delay of reference to us.
2. The mileage made over this road in any month or part of a month by any particular one of your cars.
3. The aggregate mileage made by all your cars over this

road in any month or part of a month. This can be read at a glance from the latest daily report issued.

Believing that to the extent of our interchange of cars with your line you will find the information thus imparted of undoubted value, we will ask you to give us in exchange the like information regarding our own cars, when they pass over your line, in the same or some similar shape, and with the same daily regularity with which we shall issue our reports.

The following is the heading of "Form 132," above referred to, which is on a slip 3 1/2 x 8 1/2 in.:

(FORM 132.)

PADUCAH & MEMPHIS R. R.

C. H. ALLEN, Receiver.

PADUCAH, Ky. 187..

Movement and Mileage of Individual Cars,

Belonging to

..... R. R. Co. 187..

Car Nos.	STATION.		Miles Run.
	FROM—	TO—	
Forward	from last Report,		

General Railroad News.

ELECTIONS AND APPOINTMENTS.

Hanover & York.—At the annual meeting in Hanover, Pa., Jan. 8, John S. Young was chosen President with the following directors: P. H. Glatfelter, Michael Schall, David E. Small, Alex. J. Frey, Wm. McConkey, Geo. D. Klinefelter, Wm. Young, Sr., Samuel Shirk, Isaac Loucks, S. H. Bechtel, W. Latimer Small, Dr. J. P. Smith. The road is worked by the Pennsylvania.

East Berlin Branch.—At the annual meeting in Abbottstown, Pa., Jan. 8, Capt. A. W. Eichelberger was chosen President, with the following directors: Wm. Grumbine, Stephen Keefe, Wm. Bittinger, Dr. S. Meisenhelter, Jacob Reiser, Robert M. Wirt, A. W. Storm, George Diehl, Wm. S. Hildebrand.

Bachman Valley.—At the annual meeting in Hanover, Pa., Jan. 8, Capt. A. W. Eichelberger was chosen President, with the following directors: C. J. Nourse, P. R. Payne, C. L. Johnson, C. N. Simma, Jos. Dellone, Reuben Young, Stephen Keefe, H. C. Shriver, J. W. Gitt, M. Sauble, Elias Wolfgang, Levi Dubbs.

St. Louis, Lawrence & Western.—The Kansas District Court has appointed Charles Summerfield Receiver, in place of George H. Rea.

Louisville, Paducah & Southwestern.—The statement that Gen. R. H. G. Minty had been appointed General Manager, made by the St. Louis papers, is pronounced to be untrue, or at least premature, as the future management is not yet decided.

Philadelphia & Reading.—Chief Engineer Lorenz has issued the following order: "Under the reorganization of the Roadway Department, the territories of the different residencies will be divided as follows:

"1. Pottstown Residency, with Mr. Wm. H. Blues as Resident Engineer, will comprise the Main Line and all its branches from the cooling station at Reading south and eastward, being bounded on the west by Sixth street, Reading.

"2. Lebanon Residency, with Mr. W. G. Meigs as Resident Engineer, will comprise all the territory west of Sixth street, Reading, the Lebanon & Tremont Branch, the Schuylkill & Susquehanna Branch west of Pine Grove, and the Berks & Lehigh Branch from Reading to near Slatersburg.

"3. Pottsville Residency, with Mr. H. K. Nichols as Resident Engineer, will comprise the Main Line and all its branches from the cooling station at Reading northward, the Schuylkill & Susquehanna Branch from Auburn to Pine Grove, and all the coal territory south of the crest line of the Broad Mountain between Tamaqua and Tremont.

"4. Mahanoy Residency, with Mr. Isaac E. Umstead as Resident Engineer, will comprise all the territory north of the crest line of the Broad Mountain and west of the Catawissa territory, taking in the East Mahanoy Branch as far south as East Mahanoy Junction.

"5. Catawissa Residency, with Mr. Wm. G. Yetter as Resident Engineer, will comprise the whole line of railroad, with all its branches, from Broad street, Tamaqua, to Williamsport.

"All roadway foremen will report to their respective engineers, to whom they have been transferred.

"The office of Principal Assistant Engineer having been discontinued, all employees of the Philadelphia & Reading Railroad Company who formerly had to report to the Principal Assistant Engineer, at Pottstown, will in future make their reports to the Chief Engineer, at No. 227 South Fourth street, Philadelphia."

New York Elevated.—At the annual meeting in New York, Jan. 17, the following directors were chosen: John F. Tracy, David Dows, Francis H. Tows, John H. Hall, John D. Mairs, Alfred S. Barnes, A. H. Barney, Harvey Kennedy, John Ross, Augustus Hall, James A. Cowing, William L. Wallace, Milton Courtwright. The board elected John F. Tracy, President; Milton Courtwright, Vice-President; James A. Cowing, Secretary and Treasurer.

Utica, Clinton & Binghamton.—At the annual meeting in Utica, N. Y., Jan. 18, the following directors were chosen: John Thorn, Isaac Maynard, Robert S. Williams, Henry Hopson, O. S. Williams, J. E. Elliott, A. W. Mills, D. M. Minor, J. W. Forward, Dr. B. West, George B. Phelps, Chas. H. Smythe, Alex. Holland. The board elected O. S. Williams, President; Isaac Maynard, Vice-President; J. W. Church, Secretary. Wm. H. Schuyler was reappointed Superintendent.

George's Creek & Cumberland.—The corporators of this new company have elected officers as follows: President, Dr. G. E. Porter, Lonaconing, Md.; Secretary and Treasurer, Charles Robb, Cumberland, Md. Messrs. Patterson and Sheridan, of Cumberland, have charge of the preliminary surveys.

Philadelphia & Reading Coal & Iron Co.—Mr. E. A. Quintard has been appointed General Sales Agent, with office in Philadelphia. Mr. D. T. Moore succeeds Mr. Quintard as Agent in New York.

Tennessee & Pacific.—Mr. Samuel Watkins has been chosen President, in place of George Maney, resigned. Mr. J. W. Thomas is appointed General Superintendent and R. C. Bransford, Secretary and Treasurer. The two last-named officers hold the same positions on the Nashville, Chattanooga & St. Louis, and Mr. Watkins is also a director of that company.

Grand Trunk.—Mr. John Porteous, late Terminal Agent at Portland, has been appointed General Agent, with office in Montreal, in place of Mr. Stevenson, who resigns on account of ill health. Mr. J. Main succeeds Mr. Porteous as Agent at Portland.

Delaware.—At the annual meeting in Dover, Del., Jan. 11, the following directors were chosen: S. M. Felton, Isaac Hinchley, A. C. Gray, Joseph Bringham, Charles Warner, Edward Bringham, Jr., A. B. Fiddeman, Dr. Isaac Jump, Alexander Johnson, Albert Curry, J. Turpin Moore, James Ross, Manlove Hayes. The board re-elected S. M. Felton, President; Manlove Hayes, Secretary and Treasurer. The road is worked by the Philadelphia, Wilmington & Baltimore.

Fall River.—At a meeting of the board held Jan. 13 Mr. Wm. Rotch was chosen a director in place of Charles R. Tucker, deceased. The board then re-elected J. A. Beauvais President and elected H. A. Blood Manager and Superintendent, in place of C. E. Barney, resigned, and E. D. Hewins Clerk and Treasurer, in place of T. B. Fuller, resigned. The new appointments take effect Feb. 1.

St. Louis, Bloomfield & Louisville.—The new board has elected John Thomas President; E. C. Wintanley, Vice-President; C. B. Parkman, Secretary; Edward Hurlbut, General Superintendent.

Toledo & Maumee.—The following officers have been elected for the ensuing year: President, C. C. Keyser; Vice-President and Superintendent, W. Taylor; Secretary and Treasurer, R. B. Mitchell. The offices are in Toledo, O.

Connecticut River.—At the annual meeting in Springfield, Mass., Jan. 17, the old board was re-elected, as follows: Daniel L. Harris, Chester W. Chapin, Springfield, Mass.; Oscar Edwards, Northampton, Mass.; Wm. B. Washburn, Greenfield, Mass.; Charles S. Sargeant, Brookline, Mass.; Roland Mather, Hartford, Conn.; S. M. Waite, Brattleboro, Vt.; J. M. Spellman, Edward A. Dana, Boston. The board re-elected Daniel L. Harris, President; Seth Hunt, Treasurer; John Mulligan, Superintendent.

Dallas & Wichita.—At the adjourned annual meeting in Dallas, Tex., recently, the following directors were chosen: W. L. Cabell, J. W. Crowder, F. M. Ervay, H. S. Ervay, Ira Harris, W. H. Gaston, G. W. Irvin, E. C. McClure, A. T. Obenchain, M. Pointer, W. G. Randall, Silas Reed, George Shields, C. M. Wheat.

Woodstock.—At the annual meeting in Woodstock, Vt., Jan. 10, the following directors were chosen: Albert G. Dewey, S. S. Thompson, Charles Dana, F. W. Clarke, Lewis Pratt, Frank N. Billings, Edward Dana, Charles S. Raymond, Otis Chamberlain. The board elected Albert G. Dewey President; Charles Dana, Vice-President; Luther O. Greene, Clerk; F. W. Clarke, Treasurer; Hosea Doton, Engineer; James G. Porter, Superintendent.

Troy & Boston.—At the annual meeting in Troy, N. Y., recently, the following directors were chosen: D. F. Vail, Daniel Robinson, Sylvander Johnson, Lyman Wilder, John H. Willard, Hiram Miller, Samuel M. Vail, Francis S. Thayer, Cornelius L. Tracy, Harrison Durkee, Joseph H. Parsons, Wm. Howard Hart.

Ohio & Baltimore Short Line.—At the annual meeting in Washington, Pa., Jan. 8, C. M. Reed was chosen President, with the following directors: W. W. Smith, S. B. Hays, Dr. Thomas McKennan, Wm. Workman, J. H. Garrett, Wm. Keyser, J. K. Cowen. The board elected J. B. Washington Secretary; W. H. Hays, Treasurer; W. T. Thelin, Auditor; J. L. Randolph, Chief Engineer. The company is controlled by the Baltimore & Ohio.

Waynesburg & Washington.—At the annual meeting in Waynesburg, Pa., Jan. 8, J. G. Ritchie was chosen President, with the following directors: John T. Hook, S. W. Scott, Samuel Luse, Wm. T. Lantz, Thomas Hays, Jacob Swart, James M. Dunn, John Ross, Henry C. Swart, Clark Hackney.

Addison.—At the annual meeting in Rutland, Vt., Jan. 17, the following directors were chosen: E. H. Birchard, Gasca Rich, John Hammond, John B. Page, James W. Hickok. The board re-elected John B. Page President. The road is worked by the Central Vermont.

Chicago & Lake Huron.—Mr. Day K. Smith has been appointed General Ticket Agent. His office will be, for the present, at Port Huron, Mich. Mr. Smith was formerly on the Toledo, Peoria & Warsaw.

Wilmington & Northern.—The bondholders who bought the Wilmington & Reading road at foreclosure sale met in Philadelphia Jan. 18 and organized a new company under this name by electing Robert Frazier President, with the following directors: Matthew Baird, Edward S. Buckley, Lewis Wain Smith, D. Dupont, Charles Baber, George Brooke. Mr. Frazier was President of the old company.

Lancaster.—At the annual meeting recently the following directors were chosen: George A. Parker, Jacob Fisher, Lancaster, Mass.; S. H. Howe, Bolton, Mass.; F. W. Warren, Stow, Mass.; C. H. Waters, Clinton, Mass.; W. E. Faulkner, South Acton, Mass.; Amory Maynard, Maynard, Mass.; F. D. Brigham, Hudson, Mass.; Peter B. Brigham, Boston.

South Mountain.—At the annual meeting in Jonestown, Pa., Jan. 8, Wm. H. Bell was chosen President, with the following directors: D. M. Rank, Wm. Lentz, Henry Brobst, Jacob W. Grove, Michael Miller, Henry Cameron, J. H. Ulrich, Simon Heilman, C. S. Maulair, Elias Stout, Frederick Harner, John H. Lick, John P. Seiler, John H. Speck. The board elected D. M. Rank Vice-President; Jacob Heilman, Secretary; Wm. Lentz, Treasurer.

Chicago, Burlington & Quincy.—Mr. J. Christy, formerly Master mechanic of the Burlington & Missouri River Railroad, has been appointed Mechanical Engineer at the Aurora shops of the Chicago, Burlington & Quincy—a new office on that road.

Baltimore & Ohio.—The Baltimore City Council has elected the following city directors in this company: Robert T. Banks, John F. Wiley, Joseph B. Stafford, Wm. H. Strauss, Thomas O. Sellers, B. F. Ullman, Wm. A. Boyd. The first three are re-elected; the last four succeed James Boyle, J. A. Henderson, C. E. Waters and J. J. Turner.

Great Western of Canada.—Mr. George B. Spriggs, late of the Baltimore & Ohio, has been appointed General Freight Agent, in place of Mr. John Crampton, resigned.

PERSONAL.

—The Hamilton (Ont.) Times of Jan. 16 says: "We regret to learn that Mr. Crampton, Assistant-General Manager and General Freight Agent of the Great Western Railway, is about to sever his connection with that company after a service of over twenty years. His friends both here and in the United States, who are interested in the prosperity of the Great Western Railway, are sorry that he has deemed it advisable to take this step, but trust that he will not remove too far from their midst to be lost sight of."

Mr. Samuel Carpenter, General Eastern Agent of the Pennsylvania Railroad, has been presented by Messrs. Jarrett & Palmer with a souvenir of their last train to San Francisco, consisting of a book containing engraved copies of the tickets used on that train, enclosed in a solid silver case.

—Mr. J. B. Shackelford, for a number of years General Baggage Agent of the Pittsburgh, Cincinnati & St. Louis road, died at his residence in Columbus, O., Jan. 18. He had been in poor health for a year past.

—Col. S. L. Fremont, late Chief Engineer and Superintendent of the Carolina Central Railroad, while on a visit to Rocky Mount, N. C., last week, slipped and fell on the ice, breaking one of his legs.

—Mr. James E. Cuthbert has resigned his position as Treasurer of the Atlantic, Mississippi & Ohio Company, and is now Cashier of the Citizens' Bank of Petersburg, Va.

—The Governor of Connecticut has nominated Mr. G. W. Woodruff as Railroad Commissioner for another year. The nomination has not been confirmed and probably will not be until the fate of the bill to reorganize the board, which is now before the Legislature, is decided.

—The New Hampshire Democrats have nominated Mr. Thomas J. Dinsmore as their candidate for Railroad Commissioner.

—Mr. John R. McPherson, who has just been elected United States Senator from New Jersey, is lessee of the Erie stockyards at Buffalo, Deposit and Weehawken, and is manager and chief owner of the stock-yards and abattoirs at Communipaw and at Harsimus Cove in Jersey City, the freight terminus of the Pennsylvania.

—Mr. Charles Collins, Chief Engineer of the Lake Shore & Michigan Southern, was found dead at his residence in Cleveland, O., on the morning of Jan. 20, under circumstances which left no doubt of the fact that he had committed suicide during the absence of his family, who were away on a short visit. It is believed that his mind had been unsettled by the worry and trouble connected with the Ashtabula accident and the fear that he would be in some way held responsible, although the evidence taken had not thrown the blame upon him. Mr. Collins had been connected with the road for many years (since 1859, we believe), having been Chief Engineer of the Lake Shore before the consolidation, and Chief Engineer of the whole line since Mr. Paine's appointment as General Superintendent. He was considered a very careful, conscientious man, and was remarkable for his great attachment to the road and the pride which he took in its good condition; and the terrible accident resulting from the failure of one of its structures must have been a great affliction to him, even though he could not be held personally responsible therefor.

TRAFFIC AND EARNINGS.

Railroad Earnings.

Earnings for various periods are reported as follows:

Year ending Sept. 30:	1875-76.	1874-75.	Inc. or Dec.	P. c.
Atlantic & Great Western	\$3,661,207	2,864,630	796,577	27.82
Expenses	2,864,630			
Net earnings	\$796,577			
Earnings per mile	7.293			
Per cent. of exps.	78.25			
Charlotte, Columbia & Augusta	524,562	\$614,014	Dec. \$89,452	14.6
Expenses	321,235	364,000	Dec. 42,774	11.8
Net earnings	\$203,327	\$250,005	Dec. \$46,678	18.7
Earnings per mile	2,690	3,149	Dec. 459	14.6
Per cent. of exps.	61.27	59.28	Dec. 1.99	3.4
Year ending Oct. 31:				
Westchester & Philadelphia	\$389,544	\$347,469	Inc. \$42,075	6.3
Expenses	201,575	194,861	Inc. 6,714	3.4
Net earnings	\$187,969	\$152,608	Inc. \$35,361	10.1
Earnings per mile	10,410	9,788	Inc. 622	6.3
Per cent. of exps.	54.48	56.08	Dec. 1.60	2.9
Year ending Nov. 30:				
Portland & Ogdensburg	\$234,979	\$226,150	Inc. \$8,829	3.9
Expenses	145,160	132,163	Inc. 12,997	19.0
Net earnings	\$89,819	\$104,047	Dec. \$14,228	14.4
Earnings per mile	2,513	2,661	Dec. 148	5.8
Per cent. of exps.	61.77	59.99	Dec. 1.78	14.4
Year ending Dec. 31:				
Cairo & St. Louis	\$263,968	\$282,385	Dec. \$18,417	6.9
Central of N. Jersey	7,322,000	7,411,697	Dec. \$89,697	1.3
Expenses	3,684,000	4,128,727	Dec. 444,727	10.8
Net earnings	\$3,638,000	\$3,282,910	Inc. \$355,090	10.8
Earnings per mile	21,285	20,501	Inc. 784	3.6
Per cent. of exps.	50.31	55.71	Dec. 5.40	9.7
Houston & Texas Central	3,162,518			
Expenses	1,885,197			
Net earnings	\$1,277,321	\$1,143,936	Inc. \$133,385	11.7
Earnings per mile	6,362			
Per cent. of exps.	59.60			
Nashville, Chattanooga & St. Louis	1,097,917	1,638,771	Inc. 540,854	8.8
St. Louis & Southwestern	1,108,941	1,006,649	Inc. 102,292	9.1
Six months ending Dec. 31:				
St. Joseph & Denver City	\$277,003	\$264,180	Inc. \$12,823	4.9
Month of December:				
Cairo & St. Louis	\$16,587	\$28,047	Dec. \$11,460	30.9
Nashville, Chattanooga & St. Louis	139,237	164,513	Dec. 25,276	18.4
Expenses	84,328	96,131	Dec. 11,803	12.1
Net earnings	\$54,909	\$68,382	Dec. \$13,473	18.7
Per cent. of exps.	60.58	58.44	Inc. 2.14	3.7
Rome, Watertown & Ogdensburg	86,659	92,628	Dec. 5,969	6.4
St. Joseph & Denver City	38,998	41,305	Dec. 2,307	5.9
St. Louis & Southwestern	91,531	91,308	Inc. 223	0.3
First week in January:				
St. Louis, Iron Mt. & Southern	\$92,500	\$93,549	Dec. \$1,049	1.1
Second week in January:				
Atchafalpa, Topeka & Santa Fe	\$33,560	\$31,699	Inc. \$1,861	5.9
Chicago, Milwaukee & St. Paul	79,121	125,000	Dec. 45,879	36.7
St. Louis, Iron Mt. & Southern	95,900	91,375	Inc. 4,525	0.9
Week ending Dec. 29:				
Great Western, of Canada	1876.	1875.		
Week ending Dec. 30:				
Grand Trunk	\$28,800	\$29,200	Dec. \$400	1.3

Coal Movement.

Coal tonnages for the week ending Jan. 13 are reported as follows:

	1876.	1875.	Inc. or Dec.	P. c.
--	-------	-------	--------------	-------

Anthracite..... 284,267
Semi-bituminous..... 32,217
Bituminous, Pennsylvania..... 37,197

There is serious trouble in the Cumberland Region, the mining companies having made a reduction of wages from 65 to 50 cents per ton. A large meeting of miners was held Jan. 19, when, after a long discussion, it was resolved to accept 55 cents per ton, but to hold out against anything less. The result is not known as yet, as the companies have not given the miners their answer. The operators claim that the old rate of 65 cents is very high compared with that paid in other re-

gions, and that the reduction is necessary to enable them to retain their trade under the sharp competition of the Clearfield coals and the low prices of anthracite.

Grain Movement.

From Jan. 1 to 13 the total receipts of grain of all kinds at Atlantic ports were 2,958,516 bushels in 1876, against 3,570,242 in 1875, showing a decrease of 17 per cent. Of the total receipts this year, 31½ per cent. went to New York, 28½ per cent. to Baltimore, 24 per cent. to Philadelphia, and 12 per cent. to Boston.

For the first half of the California crop year, from July 1 to Dec. 31, San Francisco wheat exports were as follows:

	1876.	1875.	Increase.	P. c.
Flour, barrels.....	296,500	232,300	64,200	27.6
Wheat, bushels.....	13,422,000	6,993,394	6,428,606	91.9
Total bushels.....	14,904,500	8,154,894	6,749,606	82.8

There is some difference of statement as to the surplus still remaining for export; the most general opinion seems to be that nearly three-quarters of the surplus has been exported, leaving only about one-quarter still in the State.

Railroad Traffic.

The passenger movement at San Francisco for the past year was as follows:

	By sea.	By rail.	Total, 1876.	Total, 1875.
Arrived.....	26,804	60,585	87,389	108,700
Departed.....	13,869	37,636	51,505	43,200
Total.....	39,173	98,221	137,374	151,900

Of the arrivals by sea 16,085 were from China and Japan, and only 4,581 from the East by way of Panama.

The freight traffic at the Utah Central and Utah Southern roads for the year ending Dec. 31 was as follows:

	1876.	1875.	Increase.	P. c.
Utah Central, tons.....	138,820	119,174	19,646	16.5
Utah Southern.....	96,775	71,443	25,332	35.5
Total.....	235,595	190,617	44,978	23.6

The leading item on the Central was 60,393 tons of coal and coke; on the Southern 35,861 tons ore and bullion. The Southern also carried 8,156 tons iron ore and 407 tons copper ore and matt.

Prices.

The Engineering and Mining Journal reports a sale of 1,000 tons of steel rails, said to be at \$49.50 at tide-water, with 12 months' interest. It says: "There is a very fair inquiry for rails, and indications that a large business will be done in steel rails at least. We quote iron rails at mills at \$34 to \$36, and steel at \$48 to \$54." No. 1 foundry pig is quoted at \$21 per ton in New York, No. 2 at \$19 to \$20, and forge at \$18.50 to \$19.

Rails continue to fall in price in Europe. On the 6th of December last bids were opened in Belgium for a lot of steel rails, and the John Cockerill Company bid \$34.30 gold per ton for 1,400 tons, to be delivered in December, and \$33.80 for 1,000 tons to be delivered by August, 1877. In England, a few days before, a contract for 6,000 tons to go to India was let at \$7 per ton—\$34.00 gold.

THE SCRAP HEAP.

Railroad Manufactures.

Thomas W. Godwin & Co., of Norfolk, Va., have recently completed a locomotive with 8 by 16 in. cylinders and 30 in. drivers for a lumber road in Norfolk County.

The King Iron Bridge Co., of Cleveland, O., has elected Zenas King President; James A. King, Vice-President; H. B. Gibbs, Secretary. There are a number of bridges under construction in the shops, but outside work has been much delayed by severe weather and the difficulty of getting masonry completed.

The Cleveland (O.) Rolling Mill Co. has re-elected A. B. Stone President; H. Chisholm, Vice-President and General Manager; E. S. Page, Secretary.

The blast furnace at Kutztown, Pa., is to be started up this month by the Hematite Iron Co., of Allentown.

The Cleveland (O.) Bridge & Car Works are building several street cars for Kingston, Ont.

During the week ending Jan. 13 the Edgar Thomson Steel Works, in 5½ days' run, turned out 1,200 tons 1,570 lbs. steel rails, 56 lbs. to the yard, the number of rails being 4,759.

Klein, Logan & Co., of Pittsburgh, manufacturers of picks, sledges and other contractors' tools, have an order from Tiflis in Asiatic Russia, near the Persian border.

On Jan. 13 the American Bridge Co. gave a dinner to its workmen employed in the erection of the Point Bridge at Pittsburgh, and to a number of invited guests. The occasion was the successful completion of the work of placing the main chains which are to carry the bridge. Mr. Edward Humberle, Engineer of the Bridge Company, made an address, and after dinner speeches were made by several of the guests.

Bowers, Dure & Co., at Wilmington, Del., are building 50 construction cars and have a good deal of repair work on passenger and sleeping coaches.

The Vulcan Iron Works, at St. Louis, have an order for light rails for 30 miles of the Tyler Tap Railroad in Texas.

The Litchfield (Ill.) Car Co. is building a number of cars for the Tyler Tap Railroad.

A shop for the manufacture of cars is to be established in Tyler, Tex. Only freight cars will be built at first.

W. H. Bailey & Co., at Connellsville, Pa., are building an engine for the Tyler Tap Railroad and have several others under way.

How Railroad Employees are Treated in Germany.

An English railroad man in Germany has written the following, which is published in the *Railway Service Gazette*:

"It would be a lesson, and a beneficial one, to our stungy directors at home if they came here and saw the kindness and care which the Prussian Government have for the servants employed on the State railways.

"In the workshops all the men are allowed to smoke as often and as much as they please. In going round one workshop, a kind-hearted German fitter took a bottle out of his pocket and offered me an 'international' drink. Of course (being no spirit-drinker), I politely declined the offer with many 'danks,' and we shook hands instead. To-day I saw a number-taker wearing an excellent suit of military clothing, with cap, and splendid top-coat. All the guards wear magnificent overcoats, which they can raise up so as to protect their necks and heads. The engine-drivers are equally well supplied with clothing.

"The whole of the staff connected with outdoor work have blue uniform suits. Porters, clerks, station-masters, and all connected with the stations, are similarly dressed in blue uniforms, with trimmings varying with the grade. As yet I have not been able to ascertain the wages paid to the running and out-door staff, but will try to do so for you.

"The fitters receive about £1 a week, which buys much more than a like sum does at home."

Paying Enginemen by Mileage.

The system of paying enginemen by the mileage run may sometimes result badly for the men, as is shown by the following from the Rochester Union:

"The enginemen on the New York Central & Hudson River Railroad are in some danger of having a small amount of money for this month's labor next pay day. They made a proposition to the company to receive pay for only as many

miles as they traveled, and the company accepted the offer. This arrangement was satisfactory enough, under ordinary circumstances, but the men did not calculate that the road would ever be in such a condition as it is now, and as a consequence they regard the snow drifts along the line with anything but love. If such winters as the present are to continue in this locality the men will probably move a reconsideration of the vote by which the arrangement with the company was adopted."

RAILROAD LAW.

Government Transportation on Land Grant Roads.

A Washington dispatch of Jan. 15 says: "The Supreme Court to-day decided that land-grant railroads are not bound to transport the troops and property of the United States free of charge, by reason of that fact; that they are only to allow the Government the free use of their tracks in return for the grants, and that they are each entitled to compensation for all such transportation they have performed, excepting the carrying of the mails, subject to a fair deduction for the use of their several roads. The general course of legislation on the subject of railroads is reviewed at length, and the conclusion is that it demonstrates the fact that in the early history of railroads it was very generally supposed that they could be public highways in fact as well as in name. In view of this fact it is thought that the conclusion is not to be reinstated, when construing a legislative declaration to the effect that a particular railroad shall be a public highway, that the meaning is that it shall be open to the use of the public with their own vehicles; and that when Congress, in granting lands in aid of such a road, declared that it should be and remain a public highway for the use of the Government, it only meant that the Government should have the right to use the road but not that it should have the right to require its transportation to be performed by the railroad company, and that when the right to use the road is granted, 'free from all toll or other charge for the transportation of any property or troops of the United States,' it only means that the Government shall not be subject to any toll for such use of the road. This decision is in the case of the Lake Superior & Mississippi, and the Atchison, Topeka & Santa Fe Railroad companies, which have been some time under advisement. This reverses the judgment of the Court of Claims. Justice Bradley delivered the opinion. Dissenting: Justices Clifford, Miller, Davis and Swaine; Justice Miller writing the opinion."

OLD AND NEW ROADS.

The Massachusetts Company.

The latest proposition for the disposal of the Hoosac Tunnel is to organize a new company, to be known as the Massachusetts Company, under a special charter, and with an ample capital. This company is to lease the Fitchburg road, lease the State road, or pay tolls for its use, and to build a new line from the western end of the tunnel by way of Schenectady and Rome, N. Y., where it will connect with the Rome, Watertown & Ogdensburg road and the Erie Canal. The project also includes a branch to connect with the anthracite region of Pennsylvania, and a connection with the Tioga coal region by the Utica, Ithaca & Elmira road.

Canadian Pacific.

The track on this road at latest advices was laid for 35 miles from the eastern terminus at Fort William on the Kaministiquia River, two miles from its mouth in Thunder Bay. At Fort William a wharf has been completed and a substantial stone round-house, repair shop, store-houses and other buildings are in progress, including dwellings for the railroad staff. A branch line has been located about four miles long to Prince Arthur's Landing, a flourishing mining settlement and the largest town in that region.

The line from Fort William to the Red River is now all under contract, the last section, No. 15, having been let to Sutton & Thomson. Several of the contractors are old Intercolonial men, having built sections of that line.

Cincinnati, Hamilton & Dayton.

Messrs. Winslow, Lanier & Co., New York, give notice that the 8 per cent. bonds of this company due June, 1877, will be paid in cash on presentation at their office, or they will be received at par and accrued interest in payment for the company's new consolidated bonds at 95.

Texas & Pacific.

A contract for the grading of the extension from Fort Worth, Tex., west to Weatherford has been let to Leavitt & Rowe, the work to be done by July next.

Meetings.

The following companies will hold meetings at the times and places given:

Eastern, annual, at the Meisner in Boston, Feb. 5, at 11 a. m.

Boston, Clinton, Fitchburg & New Bedford, annual, at South Framingham, Mass., Feb. 6.

St. Louis, Kansas City & Northern, annual, at the company's office in St. Louis, March 6, at 11 a. m.

San Diego & Yuma.

The people of San Diego, Cal., are afraid that their interests will suffer from the compromise between the Texas & Pacific and the Southern Pacific, and they propose to organize a company and build a road of their own from San Diego by the most direct route to Fort Yuma. They will also ask for the same subsidy or guarantee as Congress may decide to give to the main line.

Atlantic & Great Western.

The following statement for the year ending Sept. 30, 1876, is published in London by the reconstruction committee:

Gross earnings.....	\$3,661,206 84
Working expenses (78.25 per cent.).....	2,864,629 67
Net earnings.....	\$796,577 17
Rentals, interest, etc.....	721,406 01
Surplus.....	\$75,171 16

On application of James McHenry and other stockholders a meeting has been called to elect a new board of directors. Mr. McHenry is reported as saying that he intends to exercise all the powers which his securities give him and to elect a board to suit himself.

The Trustees of the reconstruction committee, learning that a requisition had been presented to the officers of the company on behalf of James McHenry and others desiring a meeting for the election of a new board of directors, and that in accordance with this requisition such an election will be held Feb. 15 next, addressed a letter to Mr. McHenry in which they protest, on behalf of the company's creditors, against his proposed action of the stockholders "as practically a breach of faith with the creditors." They add: "As regards yourself personally, as one of the originators of the scheme of arrangement, we feel that it is hardly necessary to point out that the one essential element of the scheme was to give the practical control of the line to the creditors, on certain terms of mutual concession and arrangement, and that this independent action on your part (which you commenced

last year, but after consideration advisedly relinquished) is under the circumstances not a fair and proper step as regards the creditors, who have such vast interests at stake." They asked Mr. McHenry, since the election must now be held, unless enjoined by a court, to place his proxies at their disposal, and offered to confer with him concerning changes in the board.

Mr. McHenry replied that he and others "intend to exercise the powers which we properly hold, in order to elect a board capable of protecting the interests of the creditors." He says that they, the reorganization trustees, cannot interfere with the company's affairs until a foreclosure; that the directors have now no executive power, "nor any other power than the interests of the creditors to support the scheme of reorganization." He adds: "I do not intend to relax my grip on the affairs of either one company or the other until I have justified before the public the several issues of bonds for which I am more or less responsible."

Cincinnati Southern.

A bill has been introduced in the Ohio Legislature providing for the leasing of this road. It authorizes the trustees, after advertising for three months, to lease the road to the parties making the bid most advantageous to the city of Cincinnati, provided they are responsible and have the necessary means to operate the road properly.

Another disposition is suggested by a wicked Cincinnati paper, which does not seem to have as much faith therein as formerly. The trustees having applied to the Court for additional compensation for their services, this paper suggests that the road itself be given them as an installment, and perhaps when the times improve and people are better able to pay their taxes they may be paid the rest of their compensation in money.

Dividends.

Dividends have been declared by the following companies:

Mill Creek and Minehill, 5 per cent., payable on demand.

Mt. Carbon & Port Carbon, 5½ per cent., payable on demand.

Schulyskill Valley, 2½ per cent., payable on demand.

Shenango & Allegheny, 10 per cent., from the earnings of the past year.

Ohio & Mississippi.

The Receivers publish the following notice: "Parties holding claims against the Ohio & Mississippi Railway Company, founded on accounts which accrued during four months prior to Nov. 18, 1876, are advised that the Receivers can assume no discretion in respect of their payments. Such accounts should be presented to Hon. W. L. Gresham, Judge of the United States Circuit Court for the District of Indiana, at Indianapolis, Ind., for his order in relation thereto."

The Receivers, Messrs. King and Torrance, have filed an inventory of all the property in their possession with the United States Circuit Court in Indianapolis. They also report that their receipts from Nov. 18 to Dec. 31 were \$545,969.72, and that they have paid all amounts due for labor at the time of their appointment. It is understood that they will ask the Court for authority to pay 25 per cent. on the outstanding bills and claims for supplies furnished.

In the United States Circuit Court in Indianapolis, Jan. 19, Allan Campbell, surviving trustee under the first and second mortgages, filed a petition for the removal of Daniel Torrance from the receivership. His petition charges mismanagement by Mr. Torrance and incompetency for the position. At the same time Wm. D. F. Manice, a stockholder, filed a petition for the removal of both Messrs. Torrance and King, his petition also alleging mismanagement and specifying several acts, chiefly the purchase of the Springfield Division. It also alleges that the bankruptcy proceedings, under which the present Receivers were appointed, were secret, without proper notice to those interested, and charges that the intention is to deprive stockholders of their interest.

The Court took the petitions and appointed Jan. 25 as the day for hearing argument thereon.

The Welland Canal Improvement.

The Buffalo Commercial Advertiser says: "The Welland Canal improvement is being pushed forward with considerable energy by the Canadian authorities. The masonry was advanced a good deal further during the past summer than was anticipated last spring. It is the opinion of those employed on the work that all the masonry will be completed between sections 1 and 12, inclusive, next summer. All the locks, bridges, etc., are in progress at present. Belder & Co.'s masonry on sections 2 and 3 is about finished, and if it is the wish they will complete it early next summer. Campbell & Co. have pushed the work on the bridge on section 4 with great rapidity of late. Peterson, on section 5, has also done well. He will finish his two locks next summer. The swing bridge on No. 6 will be completed early in the season. Blake's work on No. 5 is well along. The three locks on Nos. 8 and 9 are about finished. The same may be said of Nos. 10 and 11. The two locks on No. 12 are well advanced. The Great Western Railway tunnel, which will take about 30,000 yards of masonry, was started this fall, and has been advanced with wonderful rapidity to the fourth course, the full length of the tunnel. The contractors, Lobb & Co., intend dressing stone all winter on Point au Pelee Island, Lake Erie. About 35 cutters will be kept employed. They have some very fine quarries there. The stone is almost on the surface, and the quality very soft. They will cut the sheeting stone there this winter, and boat it down the lake next spring to Port Colborne, thence through the Welland Canal to the tunnel. Reports from the island state that life is rough and tough enough there. Osborn & Co., the contractors on section 13, commenced the two locks of this section late last summer. One has the seventh course on, and the other has one. On sections 14, 15 and 16, John Brown, contractor, the work is well advanced. On the old canal a great deal of dredging has been going on all summer, but it will require two or three summers more to complete the work of widening and deepening the old cut to correspond with the new. At present all the masons and cutters, except a few, are suspended till the voice of spring comes to summon them to wield their hammers and swing their picks once more. The reason of this early suspension is the fear that the frost will split the stone."

Sunbury & Lewistown.

The accounts having been audited and completely settled, the Treasurer is now ready to distribute among bondholders the very small balance remaining for them. The Treasurer is Mr. J. Hart, of Doylestown, Pa.

Southwestern & Rio Grande.

A vote is to be taken in Shreveport, La., on the question of voting \$300,000 aid to this company, \$150,000 for the line from Shreveport to Logansport on the Texas line, \$150,000 for that from Shreveport northeast to the Arkansas line.

Maryland & Delaware.

In the United States Circuit Court some of the bondholders have brought suit to foreclose the first mortgage on this road, and ask for the appointment of a receiver. The road extends from Clayton, Del., southwest to Easton, Md., 44 miles. The interest on the bonds has been in default three years.

Wilmington & Reading.

The purchasing committee of bondholders met in Philadelphia, Jan. 18, and organized a new corporation to be known as the Wilmington & Northern Railroad Company. The capital stock was fixed at \$1,500,000, the amount of the first mortgage

bonds, and it was resolved that each of the subscribing bondholders shall receive the face value of his bonds in new stock.

The bondholders met in Philadelphia, Jan. 23, and received the report of the committee, which was adopted. After some discussion it was resolved to admit to the new corporation, until Feb. 24, bondholders who did not sign the agreement to purchase the road, provided they can show that their failure to sign resulted from ignorance of the existence of the agreement.

Harrisburg & Potomac.

The contract for grading the Petersburg Branch has been let to Cyrus Diller, of Hanover, Pa., who has a small force employed on the work.

Cumberland Valley.

There is considerable agitation in favor of the proposed extension of this company's leased Martinsburg & Potomac road to Winchester, Va. At several meetings resolutions have been passed in favor of county subscriptions of \$10,000 per mile. The distance is about 23 miles.

Marietta & North Georgia.

This company asks the Georgia Legislature for a grant of \$5,000 per mile to buy iron for the road, a large part of which is graded. The necessary bill has been introduced and has many advocates. The road is to run from Marietta, Ga., north by east to Murphy, N. C., about 95 miles, where it will connect with the Western North Carolina Railroad, when that road is completed. It will pass through a section of Georgia especially rich in minerals, but not thickly peopled.

Junction & Breakwater.

It is stated that repair shops of sufficient size to do all the work for this road, the Breakwater & Frankford and the Worcester roads, are to be built at Georgetown, Del.

Mohave & Inyo.

A project is on foot to build a railroad from the Southern Pacific at Mohave, Cal., to the mining regions of Inyo County, a distance of about 100 miles, in a northeasterly direction.

Chicago, Milwaukee & St. Paul.

The shipments of freight from Chicago over this road for two years have been, in tons:

	1876.	1875.	Increase.	P. c.
Shipments.....	138,580	124,298	14,282	11.6

Chicago is a much less important point than Milwaukee on this road, but this is true of receipts much more than of shipments.

Swainsboro Branch.

It is proposed to build a branch from the Central Railroad of Georgia near Sebastopol southward to Swainsboro, about 17 miles, provided the people on the line will raise a reasonable amount. A part of the distance is covered by a lumber track built some time since by Wadley & Co., the work on which could be utilized for the branch.

Montana.

Montana papers state that a new proposition is to be submitted to the Territorial Legislature for the construction of a railroad having its northern terminus in the Beaverhead or the Jefferson Valley and connecting with the Union Pacific directly or through the Utah Northern, most probably the latter. Mr. Royal M. Bassett, who is largely interested in the Utah line, represents the parties making the proposition, and among those parties are several large owners of Union Pacific stock.

Keokuk & Des Moines.

This company's proposed new bridge and depot at Des Moines, Ia., are strongly opposed by the Des Moines & Fort Dodge Company, which owns the bridge and depot now in use and desires to compel the other company either to continue their use or to buy them. Quite an active contest is in progress, which will probably end in a law suit.

Southern Pacific.

A large force is now employed in the erection of machine and car shops in Los Angeles, Cal. Most of the tracklaying force has been transferred to Indian Wells, and the work of extending the track towards Fort Yuma has been resumed.

Central Pacific.

California papers state that the Railroad Commissioners of that State have begun suit against the Central Pacific Company for failure to comply with the law requiring companies to file with the Secretary of State and the clerks of counties through which the road passes copies of their freight tariffs and rates of fare for passengers.

Virginia Railroad Commission.

A bill is now before the Legislature of Virginia providing for the establishment of a board of three railroad commissioners to have a general supervision of the railroads of the State. They are also to have power to collect statistics and to receive annual reports from the companies, present them to the Legislature and make such recommendations as may seem necessary. There is much opposition to the bill.

Maryland Railroad Taxation.

The Baltimore *Gazette* says: "A deputation of the boards of the several counties through which the large railroad lines run, met in Annapolis Jan. 3, and continued their session until today, with a view to an equalization of the assessment of the road-beds of such railroads. The meeting adopted, for the minimum valuation of the lands occupied by the road-beds of the Baltimore & Ohio, the Northern Central, the Philadelphia, Wilmington & Baltimore, and the Washington Branch of the Baltimore & Potomac Railroad, the price of \$40 per acre, to be increased in the counties, if the adjacent lands are rated higher, according to the value of the adjacent lands. They also established the following rates for the assessment of the road-beds and appurtenances: Baltimore & Ohio, \$12,500 per mile; Metropolitan Branch, \$7,500 per mile; Philadelphia, Wilmington & Baltimore, \$12,500 per mile; Northern Central, \$12,500 per mile; Baltimore & Potomac, \$7,500 per mile; Pope's Creek Line, \$4,000 per mile; Cumberland & Pennsylvania, \$7,500; Eckhart Branch, \$6,000; Washington County Railroad, \$3,000; Pittsburgh & Connellsville, \$7,500; Annapolis & Elkridge, \$3,000; Union Railroad at \$6,000, and Frederick & Pennsylvania, \$6,000 per mile. Sidings to be assessed at \$2,500 per mile, and yard tracks at \$5,000 per mile."

Western North Carolina.

A select committee of the North Carolina Legislature has been investigating the affairs of this road and has presented a report which is thus summed up by the Raleigh *News*: "Find the work progressing tolerably well, but that the convicts are not properly managed, and that the labor is not made as useful as it might be. They find it the most governed railroad in the country; and that it has been run by the present commissioners as a personal charity. The report recommends an appropriation to buy iron for the railroad and suggests that steel rails be laid on the new portion. The committee think that by proper management of the work and convicts, the road can be finished to Asheville by Jan. 1, 1878. The committee also submitted a number of valuable propositions in connection with the management and operation of the road."

Erie.

In the suit against this company in the New York Supreme Court, Jan. 20, a motion was made for an order to reimburse

the Farmers' Loan & Trust Company, trustee, for the expenses incurred by it during the suit. A motion was also made for an order to fix the salary or compensation of the Receiver. Both motions were referred to James C. Spencer as Referee.

The Farmers' Loan & Trust Company, of New York, has been appointed Agent in New York for the Reconstruction Trustees in London. Bond and stockholders are requested to present their securities for adjustment under the amended plan of reconstruction at its office in New York as soon as possible.

Denver & Rio Grande.

The operations of the Main Line, 120 miles, for November are reported as follows:

Freight earnings.....	\$30,878 76
Passengers.....	10,147 25
Miscellaneous.....	75 00

Total (\$259 per mile).....\$31,101 01

Expenses (63.03 per cent.).....19,605 63

Net earnings (\$96 per mile).....\$11,495 38

As compared with November, 1875, there is an increase of \$653.25, or 2.8 per cent. in gross, and of \$107.36, or 1 per cent., in net earnings. The Government business for the month amounted to \$1,276.09. The net earnings may be increased hereafter by whatever the referees may award as this company's proportion of competitive earnings.

Alabama & Chattanooga.

This road was sold in Mobile, Ala., Jan. 22, and was bought in by Judge Grandin, of Mobile, for account of the holders of Receivers' certificates. The sale was under an order of the United States Circuit Court to satisfy the Receivers' debts, which the bondholders failed to pay.

Tennessee & Pacific.

On Jan. 16 this road was transferred to the Nashville, Chattanooga & St. Louis Company, which has bought the stock held by Davidson and Wilson counties and also nearly all of the small amount of stock held by individuals, and will work the road as a branch, with the same officers as the Main Line. The new owners have already begun work on many needed improvements and will put the road in good order, as it has been heretofore in very poor condition. The road extends from Nashville, Tenn., east by north to Lebanon, 31 miles.

Hanover Junction, Hanover & Gettysburg.

The board has directed a survey to be made from East Berlin, Pa., the terminus of the East Berlin Branch, westward to Deardorff's Mill, on the York Springs road. Mr. J. S. Gitt is to make the survey.

Hanover & York.

At the annual meeting in Hanover, Pa., Jan. 8, the President reported that the stock outstanding was \$207,200; bonds, \$150,000, and floating debt, \$37,400. The gross earnings as reported by the lessee, the Pennsylvania Railroad Company, for 11 months ending Nov. 30 were \$55,400.36; expenses, \$39,144.12; and net earnings, \$16,256.24. The road has been improved and is now in good condition. After settling with the lessees, deducting betterments, etc., and paying the coupons due Jan. 1, there remains a balance of \$6,009.14 to be applied to the floating debt. The lessee reports that the net earnings of the Littlestown Railroad, in which this company holds a controlling interest, and which is also worked by the Pennsylvania, were absorbed in necessary repairs. The interest on the \$40,000 bonds of the Littlestown Company, which became due Dec. 1, was not paid and the coupons went to protest.

Central, of New Jersey.

The following statement for the year 1876 has been published, the month of December being estimated:

Gross earnings (\$21,285 per mile).....	\$7,322,000
Expenses (50.31 per cent.).....	3,684,000

Net earnings (\$10,576 per mile).....\$3,638,000

Interest, taxes and rentals.....3,187,000

Surplus.....\$471,000

As compared with 1875 there is a decrease of \$89,637, or 1.2 per cent., in gross earnings, and an increase of \$355,090, or 10.8 per cent., in net earnings.

Reports come from the Philadelphia Stock Exchange of serious trouble with the Lehigh Coal & Navigation Company as to settlement of the amounts due that company for rental of the Lehigh & Susquehanna Railroad and the canals.

Houston & Texas Central.

The following statement for the year 1876 is published by the Commercial and Financial Chronicle:

Gross earnings (\$6,262 per mile).....	\$3,162,518 22
Expenses (59.60 per cent.).....	1,885,196 89

Net earnings (\$2,529 per mile).....\$1,277,321 33

As compared with 1875 the net earnings show an increase of \$133,385.68, or 11.7 per cent. The interest on the bonded debt was \$950,000, leaving a surplus of \$327,321.33. During the year the company changed the gauge of 120 miles of the main line from 5 ft. 6 in. to 4 ft. 8 1/2 in., and added 8 engines and 200 freight cars to the equipment.

North Landing.

Messrs. Baird & Roper are constructing and have nearly completed a railroad from North Landing, in Norfolk County, Va., to Mount Pleasant, a distance of seven miles. It is equipped with one locomotive and several cars, and is a private road, intended to carry lumber.

Central, of Iowa.

Hassler's Circular says: "It will be remembered that Mr. Cowdrey appealed from the decree of sale entered by Judge Dillon in October, 1875, and it was Mr. Cowdrey's intention that the appeal should act as a stay of all proceedings until it could be heard before the full bench of the Supreme Court at Washington. But, on motion to dismiss the appeal, the Chief Justice has delivered the opinion of the Court dismissing the appeal so far as it may act as a stay of proceedings.

"Judge Dillon has now ordered the sale of the property, and it seems quite certain that the wishes of the majority of the bondholders, as heretofore expressed, will be fully carried out."

Rochester & State Line.

Mr. Henry A. Taylor, the contractor, reports to the Rochester City Council that the track has been extended to Pearl Creek, 10 miles from LeRoy. The masonry and grading are all completed to Gainesville. The fencing is complete to LeRoy. All the bridges are under contract for immediate completion. Iron enough to lay track to Gainesville is at LeRoy. Two new locomotives, 30 box cars and 30 flat cars have been added to the rolling stock. The masonry is being pushed forward on the Salamanca Division as fast as possible. The work, however, has been delayed by the trouble with the Erie about the crossing at LeRoy and also by the severe weather and unusually deep snow. In view of all this, Mr. Taylor asks the Council to adopt such resolutions as will protect him and the sureties on the guarantees given to the City of Rochester, for a reasonable time after July 1, if he is unable to complete the road by that time.

Philadelphia, Wilmington & Baltimore.

The Baltimore *Gazette* says: "The suit of the State of Maryland by its counsel, John H. Handy, vs. the Philadelphia, Wilmington & Baltimore Railroad, to recover one-half of one per cent. tax upon the gross receipts of the company for its entire

line for two years, aggregating with interest about \$25,000, will, it is understood, be settled on the basis laid down in the opinion of the Court of Appeals of this State, filed in April, 1876. The cases were instituted in the Superior Court, and under a *pro forma* judgment in favor of defendants, on a statement of facts, were taken up to the Court of Appeals. The latter tribunal decided that the company was liable to taxation for the gross receipts on that part of the road from Baltimore to the Susquehanna River (being that portion formerly known as the Baltimore & Port Deposit Railroad), as also for its stationary property, track, etc., to the Delaware line. The amount of the judgment will be fully one-third of the sum claimed as tax upon the entire line, in the proportion of 37 miles from this city to the Susquehanna, to 98 miles from Baltimore to Philadelphia."

St. Paul & Pacific.

A bill has been introduced in the Minnesota Legislature providing for an extension of five years in the time for the completion of the St. Vincent Extension. The bill also provides for the repeal of the act of 1874, which provided for the relief of the contractors who furnished labor and materials for the extension of the road, and which has been decided to be unconstitutional.

Louisville & Nashville.

This company is considering the question of extending its Knoxville Branch from Livingston, Ky., south by west to Barbourville in Knox County, about 35 miles. It is said that the extension will be built if Laurel and Knox counties will raise a satisfactory amount of aid.

The Louisville Extension of the Louisville, Paducah & Southwestern road was formally transferred to this company Jan. 16. As heretofore noted, this line is 46 miles long, from Cecil Junction, Ky., to Louisville, and by using the six miles of the main line of the Paducah road from Cecil Junction to Elizabethtown it forms a loop line 52 miles long from Elizabethtown to Louisville. This is 10 miles longer than the Louisville & Nashville, but is said to have better grades. The extension has been owned by the bondholders, who bought it at foreclosure sale last August, it having been sold separately from the main line. The Louisville & Nashville Company agrees to give the Paducah road full facilities for all of its Louisville business.

The addition of this 46 miles makes the total mileage worked by the Louisville & Nashville Company 957 miles.

St. Louis & Kansas Southern.

Arrangements have been made to organize a company by this name to build a narrow-gauge railroad from Owego, Kan., the junction of the Missouri, Kansas & Texas and the Missouri & Western roads, westward through Labette, Montgomery, Chautauque and Cowley counties to Winfield, 120 miles. The proposed line is parallel to and about 20 miles north of the line between Kansas and the Indian Territory.

Nashville, Chattanooga & St. Louis.

The report for the six months ending Dec. 31, the first half of the fiscal year, is as follows:

	1876.	1875.	Inc. or Dec.	P. c.
Gross earnings.....	\$821,281 76	\$774,962 64	Dec. \$46,319 12	6.0
Expenses.....	512,262 13	494,824 65	Inc. 17,437 48	3.5
Net earnings.....	\$309,019 63	\$280,137 99	Dec. \$28,881 64	10.3
Per cent. of expenses.....	62.37	56.55	Inc. 5.82	10.3

The earnings this year were \$2,408 gross and \$906 net per mile. The increase in expenses was due to increase in cost of maintenance of way.

Amsterdam Prices of American Securities.

The following were the quotations Dec. 30 on the Amsterdam Exchange for some of the securities largely held there:

U. S. 4 1/2% of 1876.....	101
Chicago & Northwestern consols 7s.....	83 1/2
Central Pacific 6s.....	97 1/2
Union Pacific, Southern Branch 6s.....	49
Missouri, Kansas & Texas 7s.....	49 1/2
do. income bonds.....	19
Atlantic & Great Western Ohio 7s.....	70
St. Paul & Pacific, 1st section, 7s.....	39
do. 2d section, 7s.....	28
do. consolidated 7s.....	16 1/2
do. of 1869 7s.....	16 1/2
do. St. Vincent and Brainerd extension 7s.....	27 1/2
Toledo, Peoria & Warsaw 7s.....	27 1/2
Marietta & Pittsburgh 7s.....	46 1/2
do. consolidated 7s.....	7 1/2
Denver Pacific 7s.....	64 1/2
Atlantic, Miss. & Ohio 7s.....	20
Gilman, Clinton & Springfield 7s.....	58
Cleveland, Col., Cin. & Ind. shares.....	92
Baltimore & Ohio shares.....	146
Missouri Pacific 6s.....	61 1/2
Chesapeake & Ohio 6s.....	21
Oregon & California 7s.....	27
Port Huron & Lake Michigan 7s.....	12
St. Louis & Southeastern 7s.....	31 1/2
Cleveland, Mt. Vernon & Delaware 7s.....	44
Kansas Pacific 7s.....	35
Denver & Rio Grande 7s.....	45 1/2
Denver & Boulder Valley 7s.....	61 1/2
West Wisconsin 7s.....	45 1/2
Chicago & Southwestern 7s.....	61 1/2
do. Atchison Branch.....	31 1/2
Paducah & Memphis 7s.....	32
Calro & St. Louis 7s.....	32
Port Royal 7s.....	12
Atchison, Topeka & Santa Fe 7s.....	75
Des Moines & Fort Dodge 6s.....	51
Elizabethtown & Paducah 6s.....	32
St. Vincent and Brainerd Receiver's 10s.....	86

These prices are in gold.

Connecticut Railroad Commission.

A bill has been introduced in the Connecticut Legislature to abolish the present board of railroad commissioners, and to establish a new board, to be known as the Board of Railroad Inspectors, to consist of three members, one of whom must be a civil engineer, and another a lawyer, each of at least 10 years' practice. They are to be nominated by the Governor and approved by the Senate. The duties and powers assigned to the proposed new board do not differ materially from those of the present board.

Bangor & Piscataquis.

It is proposed to build a new line from Bangor, Me., to Milo, about 35 miles, and to take up the present track from Oldtown to Milo. It is claimed that the change would not only shorten the line but would take it through a better country with a much larger population to be served, and would avoid the use of the European & North American track from Bangor to Oldtown.

Eastern.

The appointment of Edward A. Abbott as Receiver of the Eastern Railroad of New Hampshire was made in a suit in equity brought by the New Hampshire company to set aside the lease of the road to the Eastern of Massachusetts. The bill filed in the suit claims that the lease was without legal authority in the first place; that the insolvency of the Eastern Company has made it unable to comply with the terms of the lease; that this insolvency is solely the fault of the lessee and that the New Hampshire company is thus deprived of all benefit or rental for the use of its road by the lessee.

The lease stipulated that the stockholders of the Eastern, of New Hampshire, should receive the same dividends as those of the Eastern of Massachusetts. As the Massachusetts company

has made no dividends for some time, of course the stockholders of the New Hampshire company have received nothing.

On behalf of the Eastern Railroad Company of Massachusetts a motion has been made to remove the case from the New Hampshire Supreme Court to the United States Circuit Court.

Central Vermont.

The petition of this company for an order to sell the Vermont Central and Vermont & Canada roads to pay the floating debt came up before the Vermont Chancery Court Jan. 18. Counsel for the Vermont & Canada Company, the second-mortgage bondholders, the guaranteed bondholders and some other parties appeared in opposition. But little was done beyond filing the necessary petitions and answers, and the Chancellor adjourned the hearing until the April term, the petitioners to have all their testimony filed by March 15, and rebutting testimony to be all filed by April 10.

Wheeling, Pittsburgh & Baltimore.

The sale of this road was to take place Jan. 18 under a decree of the United States Circuit Court in an action brought by the contractors who built the road, but, after several bids had been received, it was postponed to Feb. 2, in Pittsburgh.

Portland & Rochester.

The application for the appointment of a receiver came up in the Maine Supreme Court Jan. 18 and after hearing testimony and arguments the Court reserved its decision. All parties in the suit have united in requesting the appointment of George F. Westcott, President of the company, it is expected that the Court will grant the motion and appoint Mr. Westcott Receiver.

Chicago, Danville & Vincennes.

John D. Howland, Master in Chancery, gives notice that he will sell in Indianapolis, Feb. 9, the Indiana Division of this road, including 23.13 miles completed track, about 43 miles of partly completed road and all the equipment and appurtenances. The terms of sale will be one-quarter cash, one-half the remainder in three months and the balance in six months.

Marietta, Pittsburgh & Cleveland.

On Jan. 18 a tunnel near Newcomerstown, O., on this road caved in unexpectedly. Five trackmen, who were in the tunnel at the time, are believed to have been killed by the cave or shut up and subsequently suffocated.

New York Central & Hudson River.

The great snow blockade was broken at last, after a large expenditure of labor and money, last week, and freight trains have been running regularly since Jan. 19. An immense amount of freight has been forwarded since, much of which had been kept back from one to two weeks by the snow. The long delay to stock trains came near causing a temporary scarcity of meat in Boston and other New England towns, nearly all of whose supply comes by this road.

Waynesburg & Washington.

At the annual meeting recently the stockholders voted to authorize an issue of mortgage bonds for the purpose of completing the road, most of which is graded. The road is to run from Waynesburg, in Greene County, Pa., northward to Washington, about 24 miles.

Chicago, Dubuque & Minnesota.

At the bondholders' meeting in Boston, Jan. 17, it was resolved that it was not expedient for them to exchange their bonds for stock, as proposed by the trustees. A committee was appointed to prepare a plan of reorganization and to take such steps as may be necessary to secure the interests of the bondholders.

Battleboro & Whitehall.

At a meeting held in Battleboro, Vt., Jan. 16, Mr. B. D. Harris, the principal promoter of this project, reported that the preliminary survey had been completed. The distance was 87 1/2 miles and the estimated cost \$1,389,000, or about \$15,000 per mile. The line, if extended to Boston from Battleboro on the old Crocker line, would be the shortest road from Lake Champlain to the seaboard. A number of subscriptions were promised and committees appointed to canvass along the line. The meeting adjourned until Feb. 1, when the company will probably be organized.

Gulf, Western Texas & Pacific.

The sale of this road has been postponed for three months on account of an informality in advertising, and will take place some time in March.

Tyler Tap.

There are now 50 miles of this road graded, 45 miles of which have been accepted. Contracts have been made with the Vulcan Iron Works, of St. Louis, for the rails, with W. H. Bally & Co., of Connellsville, Pa., for an engine, and with the Litchfield (Ill.) Car Company for a number of cars. The company has bought the ties for a section of 20 miles from Tyler, Tex., and track will be laid as soon as the rails are received. The money thus far has been raised from local stock subscriptions, but the company intends, as soon as the first 20 miles are completed, to execute a mortgage for \$5,000 per mile, and to issue bonds with the proceeds of which it is believed that the road can be completed to Mt. Pleasant.

New London Northern.

In the case of Dawson, Taub & Co., contractors, who claimed some \$50,000 for extra work on this company's new wharf at New London, the matter was referred to arbitrators by mutual consent, and they have decided that there is \$10,500 due to the contractors.

New Albany & Northeastern.

A new organization has bought an old road-bed, graded several years ago, and purposes building a railroad from New Albany, Ind., northeast to Charlestown, about 13 miles. It is proposed also to continue the road up the Ohio River to Hanover and Vevay, connecting eventually for Pittsburgh. It is to be a narrow-gauge road.

Boston & Albany.

This company is now buying its stock of ties for the year, which are usually bought at this season in small lots from farmers and others along the line. About 170,000 are to be bought this year. Only chestnut ties are taken and the price ranges from 30 to 50 cents each, according to size and quality. The company is buying very little wood this year, as the wood-burning engines, a few of which are left on the western end of the line, are all to be changed to coal-burners.

Illinois & Michigan Canal.

The Illinois & Michigan Canal (Chicago to La Salle, Ill.) during the last season earned \$117,696.87, while its expenses were \$93,873.13. Tolls were a third lower and tonnage about one-half more than in 1875. There are now 22 steam canal boats running with success on the canal and the Illinois River.

Painesville, Canton & Bridgeport.

This company has concluded a contract with Weiss, Britton & Co., of Slaton, Pa., for the construction of a narrow-gauge railroad from Chagrin Falls, O., southward to the Pittsburgh, Fort Wayne & Chicago road near Canton, about 50 miles, the road to be completed this year. As soon as further arrangements can be made the same contractors will begin work on an extension from Chagrin Falls northwest to Cleveland, and from Canton south by east to Bridgeport on the Ohio

River. The whole length of the road from Cleveland to Bridgeport will be about 140 miles. Work on the first section will be begun as soon as the weather will permit. Messrs. Weiss, Britton & Co. are experienced contractors, and have lately completed the extension of the Parker & Karns City road to Butler.

Boston, Clinton, Fitchburg & New Bedford.

At a meeting of the directors in Fitchburg, Mass., Jan. 16, the resignation of Mr. H. A. Blood as Manager was accepted, to take effect Feb. 1. The board referred the subject of petitioning the Legislature for authority to issue \$2,000,000 preferred stock, to fund the floating debt, to the Executive Committee with power to act.

Portland & Ogdensburg.

At the annual meeting in Portland, Me., Jan. 16, the usual reports were received and read, but all other business was postponed to an adjourned meeting to be held Feb. 13.

Atlantic & Gulf.

Notice is given that the following Junction Branch bonds have been drawn by lot for redemption, according to the terms of the mortgage, and will be paid on presentation to the Savannah Bank & Trust Company: Nos. 39, 58, 80, 83 and 87 for \$500 each, Nos. 3, 28, 36, 38 and 41 for \$100 each.

The company has had outstanding for a long time what are known as fare notes or change bills, which are for small amounts and have entered largely into the currency of Savannah and other towns along the line. The entire amount of these outstanding by the last report was \$80,000. The company's default on its January coupons caused a sort of panic among the holders of these bills, and many persons refused to receive them, or took them only at a discount. To stop this the company has announced that they will be destroyed as fast as received in payment for fares and freights, instead of being paid out again, and already some \$57,000 of them have been canceled and burned, and they will soon be practically out of circulation.

A movement has been begun to have receivers appointed. It is said to be in the interest of stockholders and floating debt creditors, and a counter-application may be made by the bondholders.

ANNUAL REPORTS.

Connecticut River.

This company owns a line 50 miles long, from Springfield, Mass., northward through the Connecticut Valley to South Vernon, with branches from Chicopee Junction to Chicopee Falls, 2.35 miles, and from Mt. Tom to Easthampton, 3.50 miles. Besides serving a thickly settled farming and manufacturing district, its line is a connecting link between the Vermont system of roads and the Southern line to New Haven and New York. The thirty-second annual report covers the year ending Sept. 30, 1876. The equipment consists of 19 locomotives, 25 passenger and 13 baggage cars, and 326 freight cars.

The property is represented as follows in the capital account: Stock (\$37,601 per mile)..... \$2,100,000 00 Mortgage bonds (\$4,476 per mile)..... 250,000 00 Notes payable..... 220,400 00 Balances of accounts and vouchers unpaid..... 110,589 36 Premium on stock..... 138,785 62 Surplus earnings..... 357,650 15 Profit and loss..... 52,263 91

Total (\$37,828 per mile)..... \$3,229,689 04 The sinking fund amounts to \$186,751.28; during the year it suffered a loss of nearly \$12,000 by depreciation in Eastern Railroad bonds, of which it held \$25,000. The company holds \$87,000 Vermont Valley stock.

The work done for the year, with some general averages, was as follows:

	1875-76.	1874-75.	Inc. or Dec.	P. c.
Mileage of passenger trains	201,870
Mileage of freight and service trains	127,260
Total	329,130	329,582	Dec.	413 0.1
Passengers carried	921,335	1,050,846	Dec.	129,511 12.3
Passenger mileage	10,359,021	11,667,636	Dec.	1,308,615 11.2
Tons freight carried	278,506	298,822	Dec.	20,314 6.8
Tonnage mileage	6,454,027	7,387,921	Dec.	933,894 12.3
Average passenger train load, No.	51.32
Gross earn. per train mile	\$1.793	\$1.967	Dec.	0.174 8.8
Expenses	1.040	1.125	Dec.	0.085 7.6
Net earnings	0.753	0.842	Dec.	0.089 10.6
Receipt per passenger per mile	2.7 cts.	2.7 cts.
Receipt per ton per mile	3.3 cts.	3.2 cts.	Inc.	0.1 ct. 4.1

During the last year train expenses were 18.2 per cent.; station expenses, 8.4 per cent.; general expenses 2.1 per cent.; and taxes 6.5 per cent. of gross earnings. Maintenance of way cost \$1,265 per mile of road or 21.5 cts. per train mile. Locomotive service cost 17.5 cts. per mile for wood burners and 13.8 cts. per mile for coal-burners.

The earnings for the year were as follows:

	1875-76.	1874-75.	Inc. or Dec.	P. c.
Passengers	\$289,093 40	\$320,743 84	Dec.	\$31,650 44 9.9
Freight	256,411 50	292,033 92	Dec.	35,622 42 12.2
Mails and express	24,046 36	24,430 30	Dec.	392 94 1.6
Rents and other sources	19,985 60	12,032 20	Inc.	7,953 40 66.3
Total	\$289,536 86	\$649,249 26	Dec.	\$359,712 40 9.2
Working expenses	341,545 15	371,779 48	Dec.	30,234 33 8.1
Taxes and insurance	40,724 24	47,900 17	Dec.	7,175 88 15.0
Total	\$382,269 44	\$419,679 65	Dec.	\$37,410 21 8.9
Net earnings	\$207,267 42	\$229,569 61	Dec.	\$22,302 19 9.7
Gross earn. per mile	10,555 70	11,693 74	Dec.	1,038 04 9.2
Net earn. per mile	3,711 14	4,110 47	Dec.	399 33 9.7
Per cent. of working exps.	57.93	57.26	Inc.	0.67 1.2
Per cent. of exps. and taxes	64.84	64.84	Inc.	0.20 0.3

The income account is summed up as follows:

Net earnings	\$207,267 42
Accretion to the sinking fund	10,513 46
Total	\$217,780 88
Interest paid	\$32,411 77
Loss to sinking fund, and expenses of same	15,221 05
Dividends, 5 per cent.	168,000 00
Surplus for the year	\$2,148 06
Surplus from previous year, including sinking fund	546,551 62
Total surplus, Oct. 1, 1876	\$548,699 68

The report says: "From the table showing the annual income, expenses and dividends it will be seen that the gross

income has continued to decline from the large figures of 1873. The expenses have also been reduced and the accounts indicate a healthy financial condition. The road is enjoying the benefits of former liberal expenditures for steel rails, of which there are now some 47 miles in a total of 71 miles of track. About 450 tons of steel rail have been added during the year and cross ties to the number of 26,000 have been renewed, placing our track in such order as to compare favorably with the tracks of other roads.

"The equipment of the road has not been allowed to deteriorate, although there has been somewhat less than the usual expenditure for renewals of cars and engines.

"The station grounds at Northampton have been enlarged and improved by the purchase of adjoining lands to the amount of some \$10,000, which was carried to the construction account."

Delaware.

This company owns a line from Delaware Junction, Del., southward to Delmar, 83 miles, with branches from Smyrna Junction to Smyrna, 1 1/4 miles; Townsend to Massey's 9 miles, and from Seaford to the Maryland line, 6 miles. The Townsend Branch is leased to the Queen Anne's & Kent, and the Seaford Branch to the Dorchester & Delaware Company. The line owned is 99 1/2 miles; worked 84 1/2 miles, the latter being worked by the Philadelphia, Wilmington & Baltimore Company for 70 per cent. of the receipts. The report is for the year ending Oct. 31, 1876.

During the year the Delaware State loan of \$170,000, with \$5,100 interest, was paid from the sinking fund. Deducting these payments and adding the accumulation of the year the fund amounted at its close to \$26,496.15.

The train mileage and the fruit traffic for the year were as follows:

	1875-76.	1874-75.	Inc. or Dec.	P. c.
Passenger-train mileage	108,837	92,220	Inc.	16,617 18.0
Freight " "	155,294	183,432	Dec.	28,138 15.3
Other " "	5,608	12,114	Dec.	6,506 53.8
Total	269,739	287,766	Dec.	18,027 6.3
Cars peaches carried	2,117	9,072	Dec.	6,955 76.4
" other fruit	892	905	Dec.	23 2.5

The net earnings for the year were as follows:

	1875-76.	1874-75.	Inc. or Dec.	P. c.
Passengers	\$157,799 82	\$145,967 85	Inc.	\$11,831 97 8.1
Freights	220,618 18	349,094 06	Dec.	128,475 88 36.8
Mails and Miscellaneous	13,730 87	15,032 21	Dec.	1,301 34 8.7
Total	\$392,078 87	\$510,094 12	Dec.	\$118,015 25 23.1
Paid lessee 70 per cent. for operating	274,455 21	357,065 88	Dec.	82,610 67 23.1
Net earnings	\$117,623 66	\$153,028 24	Dec.	\$35,404 58 23.1
Interest and dividends less rent of branches	137 153 06	129,221 38	Inc.	7,932 26 6.1
Deficit or surplus	\$19,530 00	\$23,806 86
Gross earnings per mile	4,653 79	6,054 53	Dec.	\$1,400 74 23.1

The decrease in earnings was chiefly due to the great falling off in the peach traffic. The lessee has maintained the road in excellent condition and has worked it efficiently. During the year new stations were built at Mt. Pleasant and Harrington; new station, coal shed and yard at Smyrna; new sidings at Seaford, Delmar and other places; the bridge over Broad Creek repaired and altered and many smaller improvements made.

The lease to the Philadelphia, Wilmington & Baltimore has been renewed, that company agreeing, instead of 70 per cent. of the earnings, to pay all interest and 6 per cent. dividends, a deficiency in any year to be a charge on the future earnings of the leased road.

Train Accidents in December.

On the afternoon of the 1st the rear car of an express train on the Boston & Providence road was thrown from the track and somewhat damaged, near Hebronville, Mass., by the breaking of the forward truck.

On the evening of the 1st the engine of a train on the Seaboard & Roanoke road ran off the track in Portsmouth, Va.

On the night of the 1st a freight train on the New York, New Haven & Hartford road broke in two near Portchester, N. Y., and the rear section afterwards ran into the forward one, wrecking four cars and blocking the road several hours.

On the morning of the 2d the engine and four cars of a passenger train on the Long Island Railroad were thrown from the track by a misplaced switch at Fresh Pond, N. Y.

On the 2d a freight train on the Illinois Midland road ran off the track near Morton, Ill., blocking the road several hours.

On the night of the 2d a heavy freight train, drawn by two engines, ran off the track near Glade Spring, Va., on the Atlantic, Mississippi & Ohio road. Both engines and several cars were wrecked, and the conductor hurt.

Early on the morning of the 5th there was a butting collision between a freight and a coal train on the Lake Shore & Michigan Southern road, in Buffalo, N. Y., by which both engines were damaged and several cars badly broken.

On the morning of the 5th a freight train on the Baltimore & Ohio road ran into a preceding freight near Grafton, W. Va., wrecking three cars.

On the morning of the 5th a passenger train on the Nashville, Chattanooga & St. Louis road struck a broken rail near Waverley, Tenn., and the rear car was thrown from the track and upset down a bank. Eight passengers were hurt.

On the morning of the 5th the engine and baggage car of a train on the Nashville & Decatur road were thrown from the track by a broken rail at McDonald, Tenn., and both were badly broken. The engineman and fireman were hurt.

On the evening of the 6th a through freight train on the Vandalia Line ran into the rear of a local freight at Eagle Creek switch in Indianapolis. An engine and several cars were damaged, and the engineman hurt.

On the morning of the 7th a passenger train on the Ohio & Mississippi road was thrown from the track near Georgia, Ind., by the breaking of an axle under the engine.

On the morning of the 7th a passenger train on the New York, New Haven & Hartford road ran over a misplaced switch and into an engine which was just coming out of the roundhouse at Stamford, Conn., both engines being somewhat damaged.

On the morning of the 7th a car of a freight train on the Pennsylvania Railroad ran off the track at Allegripps, Pa., delaying trains a short time.

On the morning of the 8th a freight train on the Peoria Branch of the Chicago, Rock Island & Pacific ran into some cars which had broken loose from a preceding mixed train, damaging the engine and wrecking two cars. A signal had been sent back, but it was snowing hard and the freight could not be stopped in time.

On the 8th the two rear cars of a passenger train on the Jacksonville, Pensacola & Mobile road were thrown from the track by the spreading of the rails near Baldwin, Fla. One of them upset and was badly broken, injuring four passengers.

On the evening of the 8th, at the Union depot in Indianapolis, a Cincinnati, Hamilton & Dayton engine ran into some freight cars which had broken loose from a freight train which was switching in the yard. The engine was damaged and several cars broken up.

On the morning of the 9th, in a heavy snow storm, a passenger train on the Erie Railway ran off the track at a switch at Dale, N. Y.

A few minutes later a freight train ran into the rear of the passenger, throwing the two rear cars from the track and breaking them badly. The wreck caught fire and the whole train of four cars, baggage, smoking, passenger and sleeping cars, was burned. A passenger who had escaped from the sleeper, but returned to get his baggage, was burned to death.

On the afternoon of the 9th a freight train on the New York Central & Hudson River ran into the rear of a preceding freight which had become stalled in a snow-bank near Kirksville, N. Y., wrecking several cars. The stalled train had sent back a signal, but the tracks were slippery and the train could not be stopped in time. The road was blocked six hours.

Late on the night of the 9th the engine and seven cars of a freight train on the Atlantic & Great Western road were thrown from the track in a deep snow-bank near Genesee, N. Y.

Very early on the morning of the 10th, a passenger train on the New York Central & Hudson River ran into the rear of a freight train, which was stalled in a snow-bank near Wende, N. Y. Both engines on the passenger train were badly wrecked and the wreck partly destroyed by fire. An express messenger was burned to death, and an engine and fireman badly hurt. It is said that the conductor of the freight sent back a brakeman with a signal, but the man took shelter from the storm and allowed the express to pass him. Testimony at the coroner's inquest showed that the man had had hardly any rest for several days, and was worn out.

On the 10th a train on the International & Great Northern road ran off the track near Troupe, Tex., and two trainmen were badly hurt.

On the 10th a freight train on the Savannah & Charleston road ran off the track near Yemassee, S. C., blocking the road some hours.

On the morning of the 11th, at Short's, Ohio, there was a butting collision between a freight and a mixed train on the Indianapolis, Cincinnati & Lafayette road, by which both engines and several cars were damaged and three persons hurt.

On the morning of the 11th, the engine of a local passenger train on the Pennsylvania Railroad blew out a cylinder head at South Elizabeth, N. J., delaying the train an hour.

On the 13th, some cars of a freight train on the Chicago, Rock Island & Pacific road were thrown from the track near Perlee, Ia.

On the morning of the 14th, two cars of a freight train on the Erie Railway ran off the track at the western end of the Bergen Tunnel, delaying trains an hour.

On the night of the 14th, the caboose car of a mixed train on the St. Louis, Keokuk & Northwestern road caught fire from the stove when the car was near Alexandria, Mo., and was destroyed. A workman was badly burned while trying to put out the fire.

On the 15th, a special train on the Cincinnati, Lafayette & Chicago road, consisting of an engine and one passenger car, was thrown from the track near Lafayette, Ind., by the breaking of a driving-wheel under the engine. The car rolled over down a high bank and was completely wrecked, injuring all the passengers, 10 in number.

On the 15th, on the Mobile & Ohio road, near Lockhart, Miss., there was a butting collision between a north-bound mail and a south-bound freight train, by which one engine was badly damaged and a brakeman killed. The freight train was running on the mail's time.

On the 15th, a freight train on the Pennsylvania Railroad ran into the rear of a ballast train at the Fish House, near East Newark, N. J., damaging several cars and injuring two trainmen.

On the morning of the 16th, at Carroll Switch, near Baltimore, on the Baltimore & Ohio, a freight train from Mount Clare station struck the engine of a passenger train going towards Camden station. Both engines were badly broken and a baggage car damaged. It is stated that the usual crossing signal was displayed, but the freight train could not be stopped in time. One engine and a fireman were hurt.

On the morning of the 16th a passenger train on the Intercolonial Railway struck an engine which was just coming out of the round-house in St. John, N. B., damaging both engines and several cars. The road was blocked all day.

On the morning of the 16th a ballast train on the Philadelphia & Reading road was thrown from the track near Mt. Carbon, Pa., by a misplaced switch, and several cars went into the canal. A brakeman was badly hurt.

On the 16th a freight train on the Boston, Concord & Montreal road ran into a freight car which had been blown out of a siding upon the main track at Whitfield, N. H., during a heavy storm. The engine and car were badly damaged.

On the 17th there was a butting collision between a north-bound and a south-bound freight train, near Malvern, Ark., on the St. Louis, Iron Mountain & Southern road, both engines being wrecked.

On the morning of the 18th the engine and two cars of a freight train on the Erie Railway ran off the track in Paterson, N. J., blocking the west-bound track several hours.

On the 18th two cars of a freight train on the Erie Railway were thrown from the track near Great Valley, N. Y., by the breaking of an axle.

Very early on the morning of the 19th ten cars of a freight train on the Chicago, Rock Island & Pacific road were thrown from the track at Peru, Ill., by a broken frog. The cars were badly damaged and the road blocked nine hours.

On the 19th a freight train on the Nashville, Chattanooga & St. Louis road struck a hand car loaded with rails which was standing on the track near Nashville, Tenn. The engine and several cars were thrown from the track and the engine was badly damaged, a rail going through the boiler.

On the evening of the 19th, near Fox Station, Ill., on the Fox River Branch of the Chicago, Burlington & Quincy road, a passenger train was thrown from the track by a broken rail and delayed about an hour and a half.

Late on the night of the 19th an express train on the Great Western Railway was thrown from the track near Dorchester, Ont., by the breaking of a wheel under the baggage car. The whole train left the track, and the baggage car upset and was badly broken. The wreck caught fire, but was quickly put out with snow. Five persons were hurt.

Early on the morning of the 20th an express car of the newspaper train on the Pennsylvania Railroad ran off the track in the yard at Jersey City, N. J., delaying the train an hour.

On the 20th a freight car of a transfer train on the Illinois & St. Louis Bridge ran off the track near the east end of the bridge, in East St. Louis, Ill. Five cars following were piled up on it and badly broken.

On the 20th six cars of a freight train on the Harlem Extension road ran off the track near Manchester, Vt., and were somewhat damaged.

On the 20th an express train on the Missouri, Kansas & Texas road struck a broken rail near Stringtown, Indian Ter., and two cars were thrown into the ditch and badly broken, injuring 10 passengers.

On the afternoon of the 20th a north-bound train on the New York Elevated Railroad ran over a misplaced switch at the Vandam street turnout in N. Y. and into a south-bound train, damaging an engine and a car and injuring a fireman seriously.

On the afternoon of the 20th, near Princeton, Mass., on the Boston, Barre & Gardner road, there was a butting collision

between a north-bound passenger and a south-bound mixed train by which both engines and several cars were badly damaged, an engine, a brakeman and a passenger fatally hurt, a conductor and baggage man less seriously injured. The north-bound train is said to have had the right to the track.

On the evening of the 20th the engine and three cars of a passenger train on the Pennsylvania Railroad ran off the track in Altoona, Pa.

On the night of the 20th a coal train on the Belvidere Division of the Pennsylvania Railroad ran into the rear of a freight train which was standing on the track at Andover Furnace, N. J., wrecking several cars, killing a brakeman, injuring another brakeman and a conductor. It is said that the freight had sent no signal back.

Early on the morning of the 21st an express train on the Kansas Pacific road went through a bridge near Hays City, Kan., and the engine and three cars were wrecked and the wreck burned up. The express messenger was killed and a mail clerk hurt.

On the evening of the 21st the engine and one car of a train on the Raleigh & Augusta Air Line were thrown from the track at Sanford, N. C., by a misplaced switch.

On the morning of the 22d a car in a freight train on the Little Miami Division of the Pittsburgh, Cincinnati & St. Louis road caught fire when the train was near Columbus, O. The car was loaded with oil and was entirely destroyed.

On the 22d the engine of a train on the Ohio & Toledo road ran off the track at Oneida, O., blocking the track all day.

On the 22d, on the Grand Trunk Railway at St. Lambert, P. Q., there was a butting collision between two passenger trains, by which both engines were damaged.

On the afternoon of the 22d two cars of an accommodation train on the Philadelphia & Reading road were thrown from the track by a broken switch rod at Locust Gap, Pa., and one of them upset and was badly damaged.

On the evening of the 22d a mixed train on the Old Colony road broke in two near Newport, R. I., and the rear section afterward ran into the forward one, wrecking several cars, one of which caught fire and was destroyed.

Very early on the morning of the 23d, as a freight train on the St. Louis & Southeastern road was passing over a bridge at Drivers' near Mt. Vernon, Ill., the bridge gave way and eight cars went down and were wrecked. The wreck caught fire and two cars were burned up. A brakeman was hurt.

On the afternoon of the 23d the boiler of an engine on the Illinois Midland road exploded while the train was standing on a siding at Paris, Ill., destroying the engine, killing the engineer, fireman and a brakeman. The cause of the explosion is not known, though it is reported that the boiler was old and the safety-valve loaded down.

On the night of the 23d a freight train on the Houston & Texas Central road ran into the rear of a mixed train which had stopped to take water at Howe, Tex., wrecking two cars, killing a tramp who was stealing a ride, injuring two trainmen and three passengers.

Very late on the night of the 23d a passenger train on the Cleveland & Pittsburgh road was thrown from the track by a misplaced switch at Adams street station in Cleveland, O., and the baggage car was badly broken.

Near midnight on the 23d a passenger train on the Pittsburgh, Fort Wayne & Chicago road was thrown from the track by a misplaced switch near Fort Wayne, Ind. A frightened passenger, who tried to jump off, was caught between two cars and killed.

On the afternoon of the 24th a milk train on the Erie Railway ran into the head of an engine which was coming into the yard at Port Jervis, N. Y., and both engines were damaged.

On the afternoon of the 24th the engine and three cars of an express train on the Hannibal & St. Joseph road were thrown from the track near St. Joseph, Mo., by a broken rail, and the cars upset.

On the morning of the 25th a freight train on the New York Central & Hudson River road ran into the rear of a preceding freight near Utica, N. Y., damaging several cars. There was quite a fog at the time.

On the morning of the 25th a passenger train on the Cleveland, Columbus, Cincinnati & Indianapolis road was thrown from the track by a broken rail near Bellfontaine, O., and one car upset, injuring eight passengers.

On the 25th a construction train on the Galveston, Harrisburg & San Antonio road broke in two near Marion, Tex., and the rear half afterwards ran into the forward one, wrecking two cars, killing one train-man, injuring another and two tramps who were stealing a ride.

On the afternoon of the 25th an express train on the New York Central & Hudson River road was thrown from the track in Little Falls, N. Y., by the breaking of a truck wheel under the engine. The entire train left the track and one car was badly damaged.

On the night of the 25th, the parallel road of an engine on the Indianapolis, Cincinnati & Lafayette road broke when the train was near Guilford, Ind., and the loose ends broke up the cab and injured the engine man badly.

Late on the night of the 25th part of an express train on the Atlantic, Mississippi & Ohio road was thrown from the track near Bellevue, Va., by some obstructions put on the rails, evidently for the purpose of wrecking the train.

On the night of the 26th, as some freight cars were being taken down the incline to the transfer ferry at Evansville, Ind., on the St. Louis & Southeastern road, two of them broke loose, ran across the ferry-bank, breaking the stopping post, and jumped into the Ohio River.

On the evening of the 27th three cars of a freight train on the Erie Railway were thrown from the track by a broken rail at Middletown, N. Y., blocking both tracks for two hours.

On the 28th an express train on the Chicago & Iowa road was thrown from the track and wrecked by a broken rail near Shabbona, Ill.

On the 28th, an axle broke under a freight car in a train on the Quincy, Missouri & Pacific road, as it was passing over a bridge near Edina, Mo. Three cars left the track, went off the bridge into the creek and were wrecked; the bridge was also badly damaged.

On the 28th a passenger train on the Erie Railway ran over a misplaced switch at Gainesville, N. Y., and into the head of a freight which was standing on a siding, doing some damage.

On the 28th a freight train on the Cairo & St. Louis road broke through a trestle near Roseborough, Ill., and some cars were damaged.

On the 28th there was a collision between two trains on the St. Louis & Southeastern road near Earlinton, Ky., by which one passenger was hurt.

On the afternoon of the 28th two cars of an express train on the Chicago & Iowa road were thrown from the track by a broken rail near Shabbona, Ill., blocking the road two hours.

On the evening of the 28th, at Jacksonville, Ill., on the Toledo, Wabash & Western Railway, as a passenger train was going on the siding, the engine ran off an open switch into a culvert, delaying the train three hours.

On the morning of the 29th three cars of a passenger train on the Marietta & Cincinnati road ran off the track in Cincinnati, causing a short delay.

On the 29th the two rear cars of a freight train on the Louisville, New Albany & Chicago road was thrown from the track by a broken rail near Bainbridge, Ind., and wrecked. A drover in the caboose was badly hurt.

On the evening of the 29th, about 8 o'clock, an express train on the Lake Shore & Michigan Southern road broke through a bridge over Ashtabula Creek, at Ashtabula, O., and fell some 70 feet into the creek below. The train, which was running

slowly at the time, the track being obstructed by snow, consisted of two engines and 11 cars—a baggage, a mail and an express car, five passenger and three sleeping coaches. The first engine broke loose and reached the western end of the bridge, but all the rest of the train went down, the cars breaking through the ice of the shallow creek and being, of course, badly broken up. Before anything could be done to rescue passengers from the wreck it caught fire in several places and the flames spread so rapidly that many were burned to death. The number of killed cannot be definitely ascertained, but by what seems to be the most correct estimate there were 128 passengers and 19 employees on the train, of whom 75 are missing; 67 were saved in an injured condition, five of whom have since died, and five only escaped unhurt. The bridge which gave way was an iron Howe truss of 150 feet span, built at Cleveland 11 years ago. It had been recently inspected and was believed to be in good order. The theory has been advanced that part of the train ran off the track just before reaching or while on the bridge, and that the resulting jar was the occasion, if not the cause, of the giving way, but the facts as known hardly seem to substantiate this, and it would not account for the breakage of a good bridge. There has been a great deal of discussion as to the merits of the bridge, which was almost the only one of its kind in existence. Two investigations are in progress into the accident, which have not yet revealed much that is new.

On the night of the 29th an express train on the Utica & Ashtabula Road broke through a wooden bridge at Pittsford, Vt., and the whole train, an engine, baggage car, passenger car and sleeping car fell 15 feet upon the frozen creek below, the cars being badly broken. Only one passenger was slightly hurt, though several were scratched and bruised. The train is believed to have left the track before the bridge fell. By a singular coincidence the sleeping car left New York and ran to Albany in the same train with the sleeping cars which went through the bridge at Ashtabula on the Lake Shore road.

On the morning of the 30th a passenger train on the Vandalia Line ran into the rear of a coal train which was standing on the track at Bartlett's Mine, Ill., wrecking several coal cars, injuring a brakeman and blocking the road two hours.

On the night of the 30th a passenger train on the Rutland Railroad was thrown from the track by a misplaced switch in Rutland, Vt., blocking the road two hours.

On the morning of the 31st the rear car of an express train on the New York Central & Hudson River road was thrown from the track and upset near Buffalo, N. Y.

On the afternoon of the 31st a freight train on the Utica Division of the Delaware, Lackawanna & Western ran off the track in a snow-bank near Clayville, N. Y., blocking the road an hour.

This is a total of 88 accidents, whereby 94 persons were killed and 141 injured. Eleven accidents caused the death of one or more persons, 21 caused injury less than death, while 56, or 63.6 per cent. of the whole caused no injury serious enough for record.

These accidents may be classified as to their nature and causes as follows:

COLLISIONS:	
Rear collisions.....	16
Butting collisions.....	11
Crossing collisions.....	1
Unexplained.....	1
Total.....	29
DERAILMENTS:	
Unexplained.....	16
Broken rail.....	10
Misplaced switch.....	7
Broken bridge.....	5
Broken axle.....	3
Broken wheel.....	3
Snow or ice.....	3
Broken truck.....	1
Broken frog.....	1
Broken switch rod.....	1
Broken coupling.....	1
Spreading of rails.....	1
Accidental obstruction.....	1
Malevolent obstruction.....	1
Total.....	54

Cars burned while running.....	2
Boiler explosion.....	1
Cylinder head blown out.....	1
Broken connecting rod.....	1
Total.....	5

Four collisions were caused by trains breaking in two; four by want of or neglect to use signals; three by misplaced switches; two by misunderstanding or disobedience of orders, and one each by snow, by fog, and by cars blown out of siding. There were 31 accidents caused directly by defect or failure of road or equipment. Of the five broken bridges one was a wooden trestle, three others wooden truss bridges and the fifth was the iron Howe truss which fell at Ashtabula, and the cause of whose failure cannot be said to be known as yet, in spite of the two investigations in progress.

As compared with December, 1875, there is an increase of four accidents, of 82 in the number killed and of 79 in that injured.

The last half of the month was one of severe weather, especially in the Middle and Eastern States, with many storms and heavy snow. As might be expected, there were many broken rails and several failures of wheels and axles. Three accidents are traced directly to snow and several of the unexplained derailments and collisions are doubtless due to the same cause. Collisions still form a large proportion of the number of accidents, about one-third, and there is evidently on many roads not care enough in the use of signals by trainmen. The number of killed and injured is swelled to great proportions by the casualties at Ashtabula, the accident there being the most terribly destructive of human life on record.

For the year ending with December the record is as follows:

	No. of accidents.	Killed.	Injured.
January.....	60	8	29
February.....	91	15	68
March.....	109	30	66
April.....	86	6	47
May.....	64	13	118
June.....	52	19	73
July.....	79	17	60
August.....	78	23	71
September.....	106	41	120
October.....	103	40	115
November.....	96	23	122
December.....	98	94	141
Totals.....	992	328	1,097

The averages per day for the month were 2.84 accidents, 2.08 killed, and 4.55 injured; for the year they were 2.68 accidents, 0.90 killed and 3.00 injured. The averages for the month were all above those for the year. The average casualties per accident for the month were 1.068 killed and 1.602 injured; for the year 0.334 killed and 1.117 injured.

L. COES'
GENUINE IMPROVED PATENT
Screw Wrenches
MANUFACTURED BY
L. COES & CO.,
Worcester, Mass.




Established in 1839.
Registered March 31, 1874.

We invite the particular attention of the trade to our New Straight Bar Wrench, widened, full size of the larger part of the so called Lindsay's "REINFORCED OR JOG BAR." Also our enlarged jaw, made with ribs on the inside having a full bearing on front of bar (see sectional view), making the jaw fully equal to any strain the bar may be subjected to.

These recent improvements in combination with the nut inside the ferrule firmly screwed up flush, against square, solid bearings (that cannot be forced out of place by use) verifies our claim, that we are manufacturing the strongest Wrench in the market. None genuine unless stamped

"L. COES & CO."
Warehouse, 97 Chambers and 81 Reade Streets, New York.
HORACE DURRIE & CO., Agents.

BRADLEY'S CUSHIONED HELVE HAMMERS
Has won golden opinions from the Mechanical World during the four years it has been before the public, and has reached a sale of 190 Hammers, all in successful operation, in this and foreign countries.

**It Has More Good Points,
Less Complication,
More Adaptability,
Larger Capacity,
Does More and Better Work,
Takes Less Power,
Costs Less for Repairs
than any Hammer in the World.**

GUARANTEED AS REPRESENTED.
Western Office, 29 South Canal St.,
CHICAGO, ILL.
A. B. BARNES, Manager.

BRADLEY MANUFACTURING CO.,
[Established 1832.]
SYRACUSE, N. Y.

J. M. JONES & CO., WEST TROY, N. Y.,



Manufacturers of STREET CARS (Exclusively),
Embracing every variety of Close and Open Cars for either one or two horses.



PASSENGER CARS,
Of the Finest Finish, as well as Every Description of CAR WORK, furnished at Short Notice and at Reasonable Prices by the
HARLAN & HOLLINGSWORTH COMPANY, Wilmington, Del.

RICHARD DUDGEON.
24 COLUMBIA ST., NEW YORK.

MAKER AND PATENTEE
OF IMPROVED
HYDRAULIC JACKS.




Punches,
Roller - Tube
Expanders, &
Direct-Acting

STEAM HAMMERS.
Communications by letter will receive prompt attention.

**JACKS FOR PRESSING ON CAR-WHEELS
OR CRANK PINS MADE TO ORDER.**

BAKER'S PATENT CAR WARMER.



Hot Water Pipes at the Feet of
Each Passenger.
Full Descriptive Pamphlets Furnished on Application.

BAKER, SMITH & CO.
Cor. Greene & Houston sts.,
NEW YORK.



HOOPES & TOWNSEND,
MANUFACTURE

machine and Car Bolts, Wood Screws, Cold-Punched square and Hexagon Nuts, Washers, Keystone Boiler Rivets, Tank Rivets, Railroad Track Bolts, Chain Links, Car Irons, Bridge Bolts, Bridge Irons, Rods and Belts for Buildings, &c.,

No. 1330 Buttonwood st., Phila.



Very respectfully yours,

A. C. ARMSTRONG

Gen'l. Purchasing Agent,
L. S. & M. S. & F. Co.

PHILADELPHIA CAR WORKS.



J. G. BRILL & CO.,

Manufacturers of cars of every description. Street Cars of the most approved styles. Narrow Gauge, Passenger and Freight Cars.
Thirty-First and Chestnut Streets,
PHILADELPHIA.
Cars built in sections for shipment.

TRI-NITRO-GLYCERIN,

THE MOST POWERFUL EXPLOSIVE KNOWN.

Mica Blasting Powder,

The New Explosive, whose safety, power and economy may be estimated from the subjoined letter:
HOOSAC TUNNEL CONTRACT.
NORTH ADAMS, MASS., Aug. 30, 1874.
DEAR SIR.—Within the last six months we have used some 30,000 lbs. of your "Mica Powder," and with the exception of the "Tri-Nitro-Glycerin" (which we have had no better explosive in our works here. It is light to carry, safe (as far as that term can be applied to any explosive) to handle, "aimable" to explode, and thorough in combustion—a very essential quality in all preparations of Nitro-Glycerin. Where pure Nitro-Glycerin is not wanted we do not ask any better substitute than Mica Powder.

Yours truly,

W. SHANLY.

GEO. M. MOWBRAY, Esq., North Adams.

Mowbray's "Powder Keg" Battery, for simultaneous firing a series of mines or drilled holes.

Gutta Percha insulated leading wire for electric blasting.
Electric Fuses for sub-marine blasting.
Electric Fuses for rock blasting.
Gutta Percha and Cotton-covered Electric Wire.
Tape Fuse Exploders for Contractors' use, etc., etc.

All the above materials are manufactured by the undersigned, guaranteed to perform as represented, being the result of seven years' experience at the Hoosac Tunnel, and in various sub-marine works throughout the State.

GEO. M. MOWBRAY,

Hoosac Tunnel Tri-Nitro-Glycerin and Gutta Percha Works, North Adams, Mass.
New York Agency, A. W. DESFARD, 22 Cedar street, New York.

CROCKER'S TICKET PUNCH.

Patented April 30,
1867, and Sept.
21, 1869.



N. B.—Any punch with spiral springs to throw off tickets is an infringement on my patent. All persons are warned against purchasing them.

L. O. CRUCKER,
Lock Box 17, Weymouth Landing, Mass.

LUDLOW VALVE MFG. CO.,

OFFICE AND WORKS:

938 to 954 River St. and 67 to 83 Vail Ave., Troy, N.Y.

VALVES

(Double and Single Gate, 1/2 in. to 48 in.—outside and inside Screws, Indicator &c.) for Gas, Water and Steam. Send for Circular.

Also, FIRE HYDRANTS.

PEET VALVE COMPANY,

152 Hampden Street, Boston, Mass.,

MANUFACTURERS OF

Quick-opening Valves,

FOR

RAILROAD WATER TANKS;

Also Valves for Steam, Water, Gas, &c.

In use on the BOSTON & ALBANY; BOSTON, CLINTON & FITCHBURG;
NEW YORK & NEW ENGLAND, and other roads.

CHERRY HEAT WELDING COMPOUND.



SCHIERLOH MANUFACTURING COMPANY,
Office, 34 Exchange Place,
Jersey City, N. J.



OFFICE OF PURCHASING AGENT,
Lake Shore & Michigan Southern R'y.,
Cleveland, O., March 1, 1876.

IRON CLAD PAINT CO., Cleveland, O.

Gentlemen—Your "Metallic Paints," known as "Iron Clad Paints," have in the past nine years been extensively used and thoroughly tested by this Company as to their covering capacity, durability and resistance to atmospheric changes, latter "paint destroyer" the most difficult to overcome in outside paints. We have used over 100 tons and can emphatically accord them the highest position over any paint heretofore produced for Cars, Roofs, Stations, Bridges, &c. The monthly increase of our orders is the best evidence that your paint is constantly growing in favor with our mechanics.

Very respectfully yours,

A. C. ARMSTRONG

Gen'l. Purchasing Agent,
L. S. & M. S. & F. Co.


THE CLEVELAND ROLLING MILL COMPANY,
CLEVELAND, OHIO,
MANUFACTURERS OF
Bessemer Steel and Iron Rails,
From 35 lbs. to 70 lbs. per yard,
AND FASTENINGS,
BOILER PLATE, TIRE, AXLES AND OTHER FORGINGS,
Of Siemens-Martin and Bessemer Steel, and of Iron.
Galvanized and Black Sheet Iron.
CORRUGATED ROOFING AND SIDING.
SPRING STEEL AND WIRE OF ALL KINDS.
WIRE CLOTH.
Agents for the Sale of Steel Screws of all Sizes.

Using Lake Superior Iron Ore, from its own mines, and having a long experience in manufacturing, this company can warrant the quality of its products.

A. H. STONE,
President, 20 Nassau st., New York.

H. CHISHOLM,
Vice-Pres. and Gen. Manager, Cleveland, O.

NORTH CHICAGO ROLLING MILL COMPANY,



MANUFACTURERS OF
PIG METAL, IRON RAILS,
AND
Bessemer Steel Rails.
OFFICE:
17 Metropolitan Block,
CHICAGO.

O. W. POTTER, President.
S. CLEMENT, Treasurer.
R. O. HANNAH, Secretary.

Established - - 1857.
Incorporated - - 1869.
CAPITAL, \$3,000,000.

WORKS OF THE NORTH CHICAGO ROLLING MILL COMPANY.
The Company possesses facilities for the production of Iron and Steel Rails of BEST QUALITIES. Any of the usual patterns of rails applied on short notice. New patterns will be made to order. Capacity of Works, 50,000 tons Iron and 50,000 tons Steel per annum.



Orders Solicited for Iron Rail
Of any Weight not Less than 30 lbs. per yd.
RE-ROLLING PROMPTLY DONE
On the Most Favorable Terms.

The Iron Rail Piles made by this Company are all heated with Siemens' Gas Furnace, thereby securing perfect welds.

CHARLES RIDGELY, President.
JOHN W. BURN, Vice-President.
GEO. M. BRINKERHOFF, Sec'y.

Capacity of Works 3,000 Tons per Month.

THE ALBANY & RENSSELAER IRON & STEEL CO.

ERASTUS CORNING, Pres.; CHESTER GRISWOLD, V. Pt.;
SELDEN E. MARVIN, Sec'y & Treas.; JAMES E. WALKER, Gen'l Manager.

TROY, N. Y.

NEW YORK OFFICE, 56 BROADWAY.

PROPRIETORS OF

The Albany Iron Works, The Rensselaer Iron Works, The Bessemer Steel Works, The Fort Edward Blast Furnace, The Columbia Blast Furnace.

Manufacturers of Bessemer Steel and Iron Rails, Fish-Plates, Bolts and Nuts for Fish-Joints, Railroad Frogs, Railroad, Boat and Ship Spikes. All sizes Merchant and Angie Iron, Merchant, Bar and Spring Steel, Bessemer Steel Shafting, Crow-Bars and Cut and Clinch Nails, Boiler Rivets, Finger Bars and Shapes, Railroad Car, Truck and Engine Axles.

WALKER'S PATENT IMPROVED HORSE-SHOES.

We refer with especial pleasure to the quality of the articles manufactured by us, and warrant the same equal to any other manufactures in the United States.

All orders addressed to us will receive prompt attention.

THE STANDARD STEEL WORKS.

Crucible Steel Tires,
STANDARD & BRAND.
Forgings, Axles, Castings.


Works at Lewistown, Pa. Office, 218 S. 4th St., Philadelphia, Pa.

THE CAMBRIA IRON WORKS,

Situated on the line of the Pennsylvania Railroad, at the western base of the Allegheny Mountains, are the largest of their class in the United States, and are now prepared to make 2,000 tons per week of Iron and Steel Railway Bars.

The Company possesses inexhaustible mines of Coal and Ore, of suitable varieties for the production of Iron and Steel of BEST QUALITY. Their location, coupled with every known improvement in machinery and process of manufacture, enables them to offer Rails, when quality is considered, at lowest market rates. Address CAMBRIA IRON COMPANY, No. 218 South Fourth street, Philadelphia, or at the Works, Johnstown, Pa., or J. S. KENNEDY & CO., Selling Agents, No. 41 Cedar street, New York.

DICKSON MANUFACTURING COMPANY,
Scranton and Wilkesbarre, Pa.



Manufacturers of Locomotives adapted to every kind of service. Pumping and Mining Machinery a specialty. Cars, Car Wheels, Forgings and Machinery of all kinds. Specifications promptly furnished on application.

GENERAL OFFICE, Scranton, Pa.

G. L. DICKSON, President.

W. H. PERKINS, Treasurer.

W. B. CULVER, Gen. Sup't

THE EDGAR THOMSON STEEL CO., LIMITED,
MANUFACTURERS OF

STEEL RAILS, BLOOMS & INGOTS

General Office and Works at Bessemer Station (Penn. R.R.), Allegheny County, Pa.

New York Office, No. 57 Broadway.

The members of the Edgar Thomson Steel Company, Limited, have had large experience in manufacturing and in railway management; their works are the most complete in the world, with all the late improvements, and are located in the best Bessemer metal district in the United States, and their managing officers are experienced in the manufacture of Bessemer Steel. The Company warrants its rails equal in quality to any manufactured in the United States. Rails of any weight or section furnished on short notice. Orders for trial lots solicited.


Branch Office and P. O. Address,
D. McCANDLESS,
Chairman.

No. 41 Fifth Ave., Pittsburgh, Pa.
WM. P. SHINN,
General Manager.

EDWIN HARRINGTON & SON,

MANUFACTURERS OF

ENGINE LATHES,
Planers, Boring Mills,
Upright Drills, Centering
and Tapping Machines,
Lathes and Planer Chucks,
Hand Shearing & Punching
Machines, Three Tool
Shafting Rests, and other
Machinists' Tools.



Corner North 15th St. and Pennsylvania
Avenue, Philadelphia, Pa.

**MORSE TWIST DRILL
AND MACHINE COMPANY,**
MANUFACTURERS OF

TAPS, DIES, SCREW PLATES, Etc.

These tools are furnished with V or U. S. standard shape of threads and any desired pitch or number of threads per inch. Having completed our special gauges and machinery for making the U. S. or Flat Top and Bottom of thread, we invite attention of R. R. men to our manufacture of long shank or nut taps, which we in all cases guarantee against imperfections such as fire cracks, temper or gauge. For descriptive circular of Machinists', Blacksmith, Pipe and other taps, and screw plates, etc., send to

H. S. MANNING & CO.,

Sole agents for the sale of above tools,
111 LIBERTY STREET, NEW YORK.

PHOSPHOR BRONZE SMELTING WORKS.

C. J. A. DICK, Proprietor,
2038 WASHINGTON AVENUE, PHILADELPHIA, PA.,
Patentee and sole manufacturer of Phosphor Bronze in the United States.

REGISTERED TRADE MARK:




"Phosphor-Bronze."

Several principal railway corporations are using Phosphor Bronze bearings exclusively. Particulars on application at the works, or to Licensed founders: GEO. K. TAYLOR, Callowhill, west of Broad street, Philadelphia; ATWOOD & McCaffrey, 50 to 60 Third avenue, Pittsburgh.



THE CELEBRATED LINDSAY WRENCH.



The Lindsay Wrench was very favorably received by the Master Mechanics when first introduced.

We have added the "Coes" improvements to that of Lindsay, and claim to make now the strongest wrench known.

Manufactured under

John P. Lindsay's
Patent, Dec. 12, 1865.

A. G. Coes' Patent,
May 2, 1871.

A. G. Coes' Patent,
Dec. 26, 1871.

F. L. Coes' Patent
Aug. 1, 1876.

Manufactured expressly for Railroad use.

A. G. COES & CO.,
Worcester, Mass.

**CAST STEEL WORKS
OF FRIED. KRUPP,
Essen, Rhenish Prussia.**

TIRES, AXLES SPRING STEEL.
Crank Pins, Connecting Rods, Piston Rods, Boiler Plates, &c., &c.
Special Tool Steel,
A Very Superior Article, Suitable for All Kinds of Cutting Tools, Dies, &c.


Represented by
THOS. PROSSER & SON,
15 Gold street, New York.

DEAD-STROKE POWER HAMMERS.

Improved Hydraulic Jacks,

Manufactured by
PHILIP S. JUSTICE,
PHILADELPHIA, PA.


THE MASON MACHINE WORKS, TAUNTON, MASS.



WM. MASON, Pres. WM. H. BENT, Treas. FRED'K MASON, Agent.

BUILDERS OF ALL KINDS OF
LOCOMOTIVES,
INCLUDING DOUBLE-TRUCK LOCOMOTIVES FOR WIDE OR NARROW-GAUGE RAILROADS
ALSO ALL KINDS OF COTTON MACHINERY

THE HINKLEY LOCOMOTIVE WORKS,



439 ALBANY STREET, BOSTON,
MANUFACTURE


Locomotive Engines and Tenders, Boilers and Tanks,
Gun Metal and Common Iron Castings, Brass and Composition
Castings.

LOCOMOTIVES AND BOILERS REPAIRED.

Sole manufacturers of the "HINKLEY PATENT BOILER." All orders will be executed with
dispatch.

ADAMS AYER, Pres't. F. L. BULLARD, Treas. FRANK D. CHILD, Supt.
GEO. F. CHILD, Secretary. H. L. LEACH, General Manager.

ROGERS LOCOMOTIVE AND MACHINE WORKS
Paterson, N. J.; New York Office, 44 Exchange Place.



MANUFACTURERS OF

Locomotive Engines and Tenders and Other Railroad Machinery.

J. S. ROGERS, President.
R. S. HUGHES, Secretary. PATERSON, N. J.
WM. S. HUDSON, Supt.

R. S. HUGHES, Treas.,
44 Exchange Place, New York.

TAUNTON LOCOMOTIVE MANUFACTURING CO.,



F. I. PERRIN, Supt. [ESTABLISHED IN 1846.] HARRISON TWEED, Treas.

TAUNTON, MASS.


MANCHESTER LOCOMOTIVE WORKS,



MANUFACTURERS OF LOCOMOTIVE ENGINES.
All work accurately fitted to gauges. All parts duplicated and guaranteed of best material and work-
manship. JOHN A. BURNHAM, President.
ARTHUR BLOOD, Agent, Manchester, N. H. WM. G. MEANS, Treas., Boston, Mass.

PORTER, BELL & CO., Pittsburgh, Pa.


Exclusive Specialty: Light Locomotives
For Narrow-Gauge Passenger and Freight, Street Railway, Mine, Shifting, and all kinds of Special Service



All work built of best material to thorough system of standard templates
and gauges.

OUR NEW CATALOGUE WILL BE MAILED ON APPLICATION.


SCHENECTADY LOCOMOTIVE WORKS,



SCHENECTADY, N. Y.

JOHN C. ELLIS, Pres. CHAS. G. ELLIS, Treas. JOHN SWIFT, Supt


BROOKS LOCOMOTIVE WORKS, DUNKIRK, N. Y.



Orders Solicited for Locomotives Adapted for Every Class of
Railway Service.

M. L. HINMAN, Sec'y & Treas. H. G. BROOKS, Pres't & Supt

DANFORTH LOCOMOTIVE AND MACHINE CO.




JOHN COOKE, President.
J. T. BLAUVELT, Vice-President.
WM. BERDAN, Sec'y & Treasurer.
JAMES COOKE, Superintendent.

PATERSON, N. J.

New York Office, 52 Wall St
H. A. ALLEN, AGENT.

NATIONAL LOCOMOTIVE WORKS.




W. H. BAILY & CO.,

MANUFACTURERS OF LOCOMOTIVES. LIGHT and NARROW-GAUGE LOCOMOTIVES A SPECIALTY

All Material and Workmanship Guaranteed to be of the Very Best.

OFFICE AND WORKS AT CONNELLSVILLE, PA.

PITTSBURGH LOCOMOTIVE & CAR WORKS, PITTSBURGH, PA.



MANUFACTURERS OF

LOCOMOTIVE ENGINES FOR BROAD OR NARROW GAUGE ROADS,

From standard designs, or according to specifications, to suit purchasers.

Tanks, Locomotive or Stationary Boilers Furnished at Short Notice.


D. A. STEWART, Pres't

WILSON MILLER, Sec. and Treas.

THORNE, DeHAVEN & CO., Drilling Machines,

21st Street, above Market, Philadelphia.

PORTABLE DRILLS. Driven by power in any direction.
 RADIAL DRILLS. Self-feed—Large Adjustable Box Table.
 VERTICAL DRILLS. Self-feeding.
 MULTIPLE DRILLS. 2 to 20 Spindles.
 HORIZONTAL BORING AND DRILLING MACHINES.
 HAND DRILLS. CAR BOX DRILLS.
 SPECIAL DRILLS. For Special Work.



BUERK'S Watchman's Time DETECTOR.

Important for all Large Corporations
and Manufacturing Concerns.

Capable of controlling with the utmost accuracy the motion of a watchman or patrolman as the same reaches different stations of his beat. The instrument is complete in itself, portable and as reliable as the best lever watch. It requires no fixture or wires communicating from room to room, as is the case with the ordinary watch clocks. A small, inexpensive stationary key is alone required at each station. The instrument will, in all cases, be warranted perfect and satisfactory.


N. B.—The suit against Imhauser & Co., of New York, was decided in my favor, June 10, 1874. Another suit has been decided against them and a fine assessed Nov. 11, 1876, for selling contrary to the order of the Court. Persons using clocks infringing on my Patent, will be dealt with according to law.

J. E. BUERK, Proprietor,

P. O. Box 979.

No. 230 Washington Street, Boston.


In sending for circular or ordering the above, please mention this paper.



The rail flanges being bolted vertically between heavy horizontal plates, the load is taken directly by the bolts, and the rails are supported on their bases, instead of being hung "by the ears" on the narrow edges of fish bars. As there are no cross strains on these vertical bolts, no "washers" or rubber inventions are required to keep the nuts tight. The FISHER system of fastening admits the use of any form to the head of the rail, and, by smoothness of track, preservation from battering of ends of rails, and little care required, gives the most durable and economical joint yet devised. They have been in extensive use on many important roads for from four to thirteen years past. Further information will be furnished by the manufacturers, FISHER & NORRIS, Trenton, N. J.

PENNSYLVANIA STEEL COMPANY,

MANUFACTURERS OF THE



STEEL-RAIL RAILROAD HAMMERED STEEL RAILS
FROGS AND CROSSINGS, AND STEEL FORGINGS.

SAMUEL M. FELTON, President.

EBEN F. BARKER, Secretary. HENRY C. SPACKMAN, Treasurer.
 L. S. BENT, Superintendent. WORKS: Baldwin Station (Near Harrisburg), Pa.
 OFFICE: 216 South Fourth Street, Philadelphia.

THE ERIE RAILWAY COMPANY.**TO THE TRAVELING PUBLIC.**

During the Centennial Season—six months, closing November 10, 1876—the Erie Railway carried almost 3,000,000 passengers, without a single accident to life or limb, or the loss of a piece of baggage.

And for a whole year, the official records of the United States Post Office Department show the arrivals of Erie Railway trains in New York, on time, to be from 15 to 27 per cent. ahead of competing lines.

Facts well worthy the consideration of travelers.

E. S. BOWEN,

General Superintendent.

JNO. N. ABBOTT,

General Passenger Agent.

THE ATLANTIC & GREAT WESTERN RAILROAD, in connection with the ERIE RAILWAY.

forms the Great Broad-Gauge Route to the WEST and SOUTH. For Chicago, Cleveland, Omaha and all points in the Northwest. For Cincinnati, Louisville, St. Louis, Kansas City and points in the Southwest.

THIS IS THE ONLY LINE, in connection with the Erie Railway, which runs through sleeping coaches from New York and local stations to Chicago, Cleveland, Mansfield, Galion, Dayton and Cincinnati without change.

The Southern system of railways are now running palace sleeping coaches from Cincinnati (in direct connection with express trains on this line) to Memphis, Jackson and New Orleans; from Cincinnati to Nashville, Decatur, Montgomery, Mobile and New Orleans—making but one change from New York to any prominent point South—via this line.

For through tickets at lowest rates, palace coach locations, and further information concerning the route, please apply at ticket offices Erie Railway and at offices of connecting lines. Ask for tickets via the Atlantic and Great Western Railroad.

P. D. COOPER, Gen. Supt.,

CLEVELAND, O.

W. B. SHATTUC, Gen. Passenger Agent,

CINCINNATI, O.

NEW YORK CENTRAL & HUDSON RIVER R. R.

THE ONLY 4-TRACK RAILROAD IN THE WORLD, ALL LAID WITH
HEAVY STEEL RAILS.

This is the favorite route between the East and West, sixty miles the shortest, and eight to twelve hours the quickest between Boston and New England and the West.

Wagner Palace Sleeping and Drawing Room Cars Attached to All Trains.

Through cars New York and Boston to Buffalo, Niagara Falls, Cleveland, Toledo, Detroit, Chicago, Indianapolis, Louisville and St. Louis, &c. No extra charge via Niagara Falls.

New York Ticket Offices—252, 261, 413, 785 and 942 Broadway; 7 Park Place and Grand Central Depot.

C. B. MEEKER,

GENERAL PASSENGER AGENT.

NEW YORK AND NEW ENGLAND RAILROAD.

FOUR POPULAR LINES.

New and popular line between Boston and Philadelphia without change of cars, via N. Y. & N. E. H. P. & F., N. Y., N. H. & H. Railroads. Transfer steamer Maryland (between Harlem River and Jersey City). Two express trains each way, each week day, between Boston and Philadelphia. Most direct route between Boston and Brooklyn.

Elegant drawing-room cars on all trains. Baggage checked through.

A. C. KENDALL, Gen. Pass. Agent.

CHAS. P. CLARK, Gen. Manager.

PENNSYLVANIA RAILROAD.

GREAT TRUNK LINE AND UNITED STATES MAIL ROUTE. THE BEST
CONSTRUCTED AND MOST COMPLETELY EQUIPPED
RAILWAY IN AMERICA.

Connecting all the principal cities on the Atlantic Coast with those in the Mississippi Valley and on the Great Lakes. Through trains with Palace Cars attached, between New York, Philadelphia, Washington and Baltimore and Chicago, St. Louis, Cincinnati and Louisville.

Baggage Checked to Destination. Fare always as low as by any other route.

For tickets, palace and parlor car accommodations, and all desired information, apply at the offices of the Company: Nos. 293 and 295 Washington st., Boston; No. 1 Astor House, Nos. 526 and 944 Broadway, and Desbrosses and Cortlandt street ferries, New York; Nos. 838 and 1348 Chestnut street, and Depot, Thirty-second and Market streets, Philadelphia; N. E. cor. Baltimore and Calvert streets, Union Depot and Northern Central Railway Depot Baltimore; N. E. corner Thirtieth street and Pennsylvania avenue, N. E. corner Sixth street and Pennsylvania avenue, and Baltimore and Potomac R. R. Depot, Washington City.

FRANK THOMPSON, General Manager

D. M. BOYD, Jr., General Passenger Agent.

NORTH PENNSYLVANIA RAILROAD.

THE SHORT AND FAVORITE ROUTE FROM PHILADELPHIA
To the Lehigh, Wyoming and Susquehanna Valleys, Scranton, Elmira, Rochester, Buffalo, Niagara Falls, New York State, the West and Northwest.

FAST TIME, SURE CONNECTIONS, PARLOR AND SLEEPING CARS.

Philadelphia Passenger Depot, Berks and American Streets.

FREIGHT FACILITIES:

Daily Fast Freight Trains are run between Philadelphia and the above-named districts, delivering freight with regularity and dispatch on terms as low as any other route.

PHILADELPHIA FREIGHT DEPOT, FRONT AND NOBLE STREETS.
 ELLIS CLARK, Gen. Agent, Front and Willow Streets, Philadelphia.
 Philadelphia City Office: Fifth and Chestnut sts. and 733 Chestnut st.

THE BEST ROUTE TO INTERIOR PENNSYLVANIA.

Express Trains daily from Philadelphia to Reading, Harrisburg, Tamaqua, Portsville, Mahanoy City, Ashland, Shamokin, Danville, Williamsport, and all points on the Coal, Lumber and Ore Regions of the State.

EXPRESS TRAINS FROM ALLENTOWN FOR SAME POINTS IN CONNECTION WITH TRAINS OF
CENTRAL RAILROAD OF NEW JERSEY FROM NEW YORK.

Purchase Tickets via Reading.

J. E. WOOTTEN, Gen. Supt., Reading.

C. G. HANCOCK, Gen. Ticket Agent, Phila.

CLEVELAND, COLUMBUS CINCINNATI & INDIANAPOLIS RAILWAY, THE GREAT CENTRAL TRUNK ROUTE TO THE OHIO AND MISSISSIPPI RIVERS.

Evening trains leave CLEVELAND daily with Rotunda Sleeping Cars, for COLUMBUS, CINCINNATI, INDIANAPOLIS, LOUISVILLE, TERRE HAUTE, EVANSVILLE, ST. LOUIS and all points West and South.

Morning trains leave daily except Sunday, with through Palace Coaches, for COLUMBUS, CINCINNATI, INDIANAPOLIS, LOUISVILLE and ST. LOUIS without change.

This is the only line making direct connection with all the Principal Trunk Lines of the East for NASHVILLE, MEMPHIS, NEW ORLEANS and all points in Texas, either by way of LOUISVILLE or ST. LOUIS.

Direct connection at ST. LOUIS for all Railway Towns in Kansas, Nebraska and Colorado.

EQUIPMENT COMPRISES ALL VALUABLE IMPROVEMENTS.
 THE BEST ROAD-BED AND SAFEST ROAD IN THE WEST.

Tickets by this route for sale at all regular ticket offices.

E. S. FLINT, General Superintendent.

S. F. PIERSON, General Ticket Agent.

UNION PACIFIC RAILROAD VIA OMAHA.

THE ONLY DIRECT ALL RAIL ROUTE; being 226 miles the Shortest Route.

Salt Lake, Sacramento, San Francisco, and the Mining Districts of Utah, Montana, Nevada, California, Etc., Etc.

Five Hours the Quickest Route to Denver.

Close connections made at Cheyenne with Denver Pacific Railway. At Denver with the Colorado Central. At Golden City with Daily Coaches for the Mines. At Denver with Denver & Rio Grande Railway for all points in Southern Colorado, New Mexico and Arizona.

Baggage checked through from Chicago to Denver, and from Omaha to Salt Lake City, Sacramento, San Francisco, etc.

T. E. SICKELS, Chief Engineer and Superintendent.

THOS. L. KIMBALL, General Ticket Agent, Omaha, Neb.

EMPIRE LINE.

THE EMPIRE TRANSPORTATION COMPANY OFFERS TO THE BUSINESS COMMUNITY A
RELIABLE FAST FREIGHT LINE BETWEEN THE EAST AND THE WEST AND THE
GREAT OIL REGION OF PENNSYLVANIA.

Via the Philadelphia & Erie Railroad and its Connections.

IT OWNS AND CONTROLS ALL THE CARS OF ITS LINE, which are new and built expressly for trade, and furnished with BROAD TREAD WHEELS, which enable it to run through irrespective change of gauge, thus avoiding the injurious delays prevalent at transshipping points. The Line is managed by men of long experience in the business, and no effort will be spared on their part to render satisfaction to its patrons.

Parties ordering goods from the East will please direct shippers to mark packages "EMPIRE LINE" and refer them to the agents of the company for shipping directions, &c., &c.

GEO. W. RISTINE, Western Supt., Cleveland, Ohio.

W. F. GRIFFITHS, Jr., General Freight Agent, Philadelphia, Pa.

GEORGE M. RALI, Eastern Superintendent, Philadelphia, Pa.

THE FAVORITE ROUTE—EAST OR WEST.

MICHIGAN CENTRAL RAILROAD,
AN IMPORTANT LINK IN THE
GREAT CENTRAL ROUTE
Between the East and West.THREE EXPRESS TRAINS EACH WAY DAILY. THE ONLY LINE EAST FROM CHICAGO
RUNNING THE CELEBRATED DINING CARS.

WAGNER SLEEPING AND PARLOR CARS.

THROUGH CARS FROM AND TO

CHICAGO, NEW YORK AND BOSTON.

H. B. LEDYARD, Gen'l Sup't, Detroit. HENRY C. WENTWORTH, Gen'l Pass. and Tkt. Agt., Chicago.

BALTIMORE & OHIO RAILROAD.

Leave New York from foot of Desbrosses and Cortlandt streets:
8:40 a. m. for Washington and the West, Richmond, Charleston and the South. Pullman Parlor cars
from New York to Baltimore and Washington, making close connection for Cincinnati, St. Louis, Louis-
ville, &c.1 p. m. for Washington, Pittsburgh, Cincinnati, Chicago, and for Richmond, via Gordonsville. Pull-
man cars from New York to Baltimore and Washington.9 p. m. daily for Washington, the South and West. Pullman's sleepers from New York to Baltimore
and Washington, making close connection for Chicago, Cincinnati, Louisville, St. Louis, Pittsburgh,
the South and Southwest. Connect at Washington with trains for Lynchburg, Florida, New Orleans and
the South. For through tickets please call at Company's office, 315 and 1,238 Broadway, New York;
and at the ticket offices, foot of Cortlandt and Desbrosses streets; and Depot, Jersey City.
ASK FOR TICKETS VIA BALTIMORE & OHIO RAILROAD.

PHILADELPHIA, WILMINGTON & BALTIMORE RAILROAD.

The connecting link between the EAST, WEST, NORTH, SOUTH, the centre of the GREAT
THROUGH LINE between the cities of NEW YORK, PHILADELPHIA, BALTIMORE and
WASHINGTON, the only route between the EAST, WEST and SOUTHWEST, via WASHINGTON,
D. C., and the shortest and only direct route between the NORTH and SOUTH.
In every respect a first-class Railway. Tickets via BALTIMORE for sale in all principal ticket offices
throughout the country.

H. F. KENNEY,

Superintendent.

General Offices at Philadelphia, Pa.

GEO. A. DADMUN,

General Ticket Agent.

CHICAGO, MILWAUKEE & ST. PAUL RAILWAY.

THE DIRECT ROUTE TO

MILWAUKEE, ST. PAUL AND MINNEAPOLIS,

And all portions of Wisconsin, Minnesota and Northern Iowa.

Purchase Tickets Via Milwaukee.

Passengers going via this NEW DIRECT ROUTE to Milwaukee leave from and arrive at the most
Central and best located Depots in Chicago, Milwaukee and St. Paul.

BAGGAGE CHECKED THROUGH BY THIS ROUTE!

Passengers from Chicago can obtain these Advantages only by taking the trains of Chicago, Milwau-
kee & St. Paul Railway, at Union Depot, corner West Madison and Canal streets.

SPECIAL NOTICE.

This Line connects more important Business Centres than any other route in
the Northwest, is as short as the shortest, and is fully equipped with the best of
Day and Sleeping Coaches.

A. V. H. CARPENTER,

Gen. Passenger Agent, Milwaukee.

S. S. MERRILL,

Gen. Manager, Milwaukee.

T. E. CHANDLER,

Passenger and Ticket Agent, 37 West Madison street, Chicago.

CHICAGO & NORTHWESTERN RAILWAY.

This great corporation now owns and operates over two thousand miles of road radiating from
Chicago like the fingers of a man's hand, its lines reach in all directions and cover about all of the country
north, northwest and west of Chicago. With one branch it reaches Racine, Kenosha, Milwaukee and the
country north thereof; with another line it pushes through Janesville, Watertown, Oshkosh, Fond du
Lac, Green Bay, Escanaba to Negaunee and Marquette; with another line it passes through Mad-
ison, Elroy and for St. Paul and Minneapolis; branching westward from Elroy it runs to and
through Winona, Wabasha, St. Peter, Mankato, New Ulm, and stops not until Lake Kampeska,
Dakota, is reached; another line starts from Chicago and runs through Elgin and Rockford to Free-
port, and, via the Illinois Central, reaches Warren, Galena and Dubuque; and the country beyond.
Still another line runs almost due westward, and passes through Dixon, Sterling, Fulton, Clinton (Iowa),
Cedar Rapids, Marshalltown, Grand Junction, Missouri Valley Junction, to Council Bluffs and
Omaha. This last-named is the "Great Trans-Continental Route," and the pioneer overland line for
Nebraska, Colorado, Utah, Idaho, Montana, Nevada, California and the Pacific Coast.
It runs through the Garden of Illinois and Iowa, and is the best, safest, shortest and quickest route for
Omaha, Lincoln and other points in Nebraska, and for Cheyenne, Denver, Salt Lake City,
Virginia City, Carson, Sacramento, San Francisco, and all other points west of the Mis-
souri River.On the arrival of the trains from East or South, the trains of the Chicago & Northwestern
Railway leave CHICAGO as follows:For Council Bluffs, Omaha and California—Two through trains daily, with Pullman Palace
Drawing-Room and Sleeping Cars through to Council Bluffs.For St. Paul and Minneapolis—Two through trains daily, with Pullman Palace Drawing
Room Sleeping Cars attached, for St. Paul and through to Minneapolis.For Green Bay and Lake Superior—Two trains daily, with Pullman Palace Cars attached.
For Milwaukee—Four through trains daily. Pullman Cars on night trains. Pullman parlor chair
cars on day trains.For La Crosse, Wis., Winona and points in Minnesota—One through train daily, with
Pullman sleepers to Winona.

For Dubuque via Freeport—Two through trains daily, with Pullman Cars on night train.

For Dubuque and La Crosse via Clinton—Two through trains daily, with Pullman cars on
night train to McGregor, Iowa.

For Sioux City and Yankton—Two trains daily. Pullman cars to Missouri Valley Junction.

For Rockford, Sterling, Kenosha, Janesville and other points you can have from two to ten trains
daily.

MARVIN HUGHITT,

General Manager.

L. P. BOOTH,

Gen. Ea. Agt., 415 Broadway, N. Y. city.

W. H. STEWART,

General Passenger Agent.

CHICAGO, ROCK ISLAND & PACIFIC RAILROAD.

The direct route for Joliet, Morris, Ottawa, LaSalle, Peru, Henry, Peoria, Lacon, Geneseo, Moline,

ROCK ISLAND, DAVENPORT,

Muscatine, Washington, Iowa City, Grinnell, Newtown, Des Moines,

COUNCIL BLUFFS AND OMAHA.

Connecting with Trains on the Union Pacific Railroad for CHEYENNE, DENVER, CENTRAL CITY
ODGEN, SALT LAKE, WHITE PINE, HELENA, SACRAMENTO, SAN FRANCISCO, and Points in Up-
per and Lower California, and with Ocean Steamers at San Francisco, for all points to
China, Japan, Sandwich Islands, Oregon and Alaska.

DEPOT, HEAD OF LA SALLE STREET; TICKET OFFICE, 56 CLARK STREET.

OMAHA AND LEAVENWORTH EXPRESS (Sundays excepted)..... 10.15 A. M. 4.00 P. M.
PERU ACCOMMODATION (Sundays excepted)..... 8.00 P. M. 9.35 A. M.
OMAHA AND LEAVENWORTH EXPRESS (Saturdays excepted)..... 10.00 P. M. 6.50 A. M.

KANSAS LINE.

The Chicago, Rock Island and Pacific Railroad Company have now opened their South Western Di-
vision, between

LEAVENWORTH, ATCHISON AND CHICAGO.

CONNECTING WITH KANSAS RAILROADS,


For all points in Western Missouri, Colorado and the Territories.
The Company have built a full complement of PALACE DRAWING ROOM AND SLEEPING CARS,
which for external beauty and interior arrangements for the comfort, convenience and luxury of passen-
gers are unequalled, if equaled, by any other cars of the kind in the world.For Through Tickets and all desired information in regard to Rates, Routes, etc., apply
at the Company's office, Chicago, or 257 Broadway, New York.

HUGH RIDDLE, Gen. Supt.

A. M. SMITH, Gen. Pass. Agent.

CHICAGO, ALTON & ST. LOUIS

AND

CHICAGO, KANSAS CITY & DENVER
SHORT LINES.The Best Line, via St. Louis, to Memphis, Mobile, New Orleans and
all points South.

THE SHORT LINE TO TEXAS, VIA ST. LOUIS.

No change of cars on any train by this line between Chicago and St. Louis. Pullman Palace Sleeping
Cars—the newest, safest and best in use on any road—run through between Chicago and Springfield and
Chicago and St. Louis without change. *Seals in Dining Cars only 75 cents.* No change of Recul-
ing Chair Cars and Pullman Palace Sleeping Cars between Chicago and Kansas City. No extra charge for
seats in Reculining Chair Cars. Two hours the quickest route from Chicago to KANSAS CITY, DENVER,
FUEBLO and all points in Kansas and Colorado. No change of cars between Chicago and Peoria.
JAMES CHARTLTON, J. C. McMULLIN,
General Passenger and Ticket Agent, Chicago. General Superintendent, Chicago.

ILLINOIS CENTRAL RAILROAD.

Trains Leave Chicago from the Great Central Depot, of Lake Street,
CHICAGO AND ST. LOUIS THROUGH LINE.

No Change of Cars to St. Louis!

8:40 A. M. DAY EXPRESS. Sundays Ex- | 8:30 P. M. FAST LINE. DAILY. Arriv-
cepted. Arriving St. Louis at | ing at St. Louis at 8:30 A. M.
8:45 P. M.

CAIRO, MEMPHIS, MOBILE AND NEW ORLEANS LINE.

No Change of Cars to New Orleans!

8:40 A. M. DAY EXPRESS. Sundays ex- | 4:30 P. M. GILMAN PASSENGER.
cepted, arriving at Cairo 2:30 A. M.; | Sundays Excepted. Arriving at
Memphis 8:15 P. M.; Vicksburg, 10:10 A. M.; | Gilman at 8:50 P. M.
Mobile, 8:00 P. M.; and New Orleans at 11:45 A. M.8:30 P. M. NIGHT EXPRESS. DAILY. Arriving at Cairo 1:45 P. M., making direct connec-
tions for Arkansas and Texas.
This Route is from 100 to 175 MILES SHORTER and from 12 to 24 HOURS QUICKER than any other.

PEORIA, BURLINGTON AND KEOKUK LINE.

8:40 A. M. EXPRESS. Sundays excepted. Arriving at El Paso 2:30 P. M.; Peoria 3:00 P. M. Through
coach from Chicago to Peoria8:30 P. M. EXPRESS. Sundays excepted. Arriving at Peoria 3:10 A. M.; Burlington 7:45 A. M.
Keokuk 8:15 A. M.; Hannibal 11:30 A. M. Sleeping cars from Chicago to Peoria and
Chicago to Hannibal.

CLINTON AND SPRINGFIELD LINE.

8:40 A. M. DAY EXPRESS. Sundays Excepted. Arriving at Gibson 1:57 P. M.; Farmer City 2:57
P. M.; Clinton 3:48 P. M.; Springfield at 6:05 P. M.8:30 P. M. NIGHT EXPRESS. Sundays excepted. Arriving at Gibson 12:30 A. M.; Farmer City
1:55 A. M.; Clinton, 2:38 A. M.; Springfield, 4:35 A. M.

DUBUQUE AND SIOUX CITY LINE.

9:30 A. M. DAY EXPRESS. Sundays Excepted. Arriving at Dubuque 7:00 P. M.; Waterloo, 12:07
A. M.; Fort Dodge, 5:35 A. M.; Sioux City, 12:32 P. M.9:30 P. M. NIGHT EXPRESS. Sundays Excepted. Arriving at Dubuque 6:55 A. M.; Waterloo
12:05 P. M.; Fort Dodge, 7:00 P. M.; Sioux City, 7:10 A. M.

This is the only Route to Dubuque and Sioux City without Change.

For Tickets, Sleeping Car Berths and information, apply at the Illinois Central Railroad Ticket Office
121 Randolph street, near Clark, and at the Central Depot, foot of Lake street.

W. P. JOHNSON, Gen. Pass. Agt.

J. F. TUCKER, Gen. Supt.

ILLINOIS CENTRAL FREIGHT DEPARTMENT.

Freight taken for St. Louis, and points West and Southwest. For Hannibal and all points on the M. & K.
& T. R. R. for all landings on the Mississippi, Red and White Rivers, via Cairo and regular packets.
THE ONLY RAIL LINE TO MEMPHIS AND NEW ORLEANS, with

CARS RUN THROUGH WITHOUT CHANGE.

via the N. O., St. L. & O. R. R. and, by its connection at Frost, Tenn., the Direct Route to all points
reached by the Green Line of the South; to Mobile, and points on the M. & O. R., via Jackson, Tenn., to
Dixon, Freeport, Warren, Galena, Dumbell, and all landings on the Upper Mississippi during season of
navigation, and without change of cars to Dubuque, Waterloo, Fort Dodge and Sioux City, Iowa; Ver-
million and Yankton, Dakota Territory; and via Missouri Packets to points on the Upper Missouri.
Bills Lading and Rates furnished upon application at 121 RANDOLPH street, or foot of South Water
street.

HORACE TUCKER, General Freight Agent.

WISCONSIN CENTRAL RAILROAD.

GARDNER COLBY, Pres., Boston, Mass. E. H. ABBOTT, Treas., Boston.

Built and operated by Phillips & Colby Construction Company. E. B. Phillips, Pres. and Gen. Manager,
Milwaukee; Charles L. Colby, Vice-Pres. and Land Commissioner, Milwaukee; E. Bacon, Superin-
tendent, Milwaukee; Henry Pratt, Asst. Gen. and Gen. Ticket Agent, Milwaukee.

OFFICES: Milwaukee, Wis., and 94 State Street, Boston, Mass.

SHORT LINE TO GREEN BAY, the WISCONSIN and CHIPPEWA PINERIES,
ASHLAND and RAYFIELD, LAKE SUPERIOR,
Via MENASHA and STEVENS POINT.

TWO DAILY TRAINS FROM MILWAUKEE FOR MENASHA AND GREEN BAY.

ONE TRAIN FOR STEVENS POINT, WAUPACA, AMHERST, GRAND RAPIDS, PLOVER, PLAIN-
FIELD, COLBY, MEDFORD, PHILLIPS, FIFIELD AND ASHLAND.Through Sleeping Cars on 9:30 p. m. train from Chicago (C. M. & St. Paul Depot), and from Milwau-
kee on 1:30 a. m. train for Green Bay, Menasha and Stevens Point. Sleeping car at Milwaukee ready at
8:30 p. m.

ELEGANT NEW CARS HAVE BEEN ADDED.

Price of berth only \$1.50.

CONNECTIONS: At Milwaukee, with Chicago, Milwaukee & St. Paul, and Western Union Railways; at
Plymouth, with Sheboygan & Fond du Lac Railroad, for Fond du Lac and Sheboygan; at Forest Junction,
with Milwaukee, Lake Shore & Western Railway; at Green Bay, with Green Bay & Minnesota's Railway, for
New London, and Chicago & Northwestern Railway, for points North; at Dale, with fast stage line for
New London; at Amherst Junction, with Green Bay & Minnesota's Railway, for Grand Rapids and points
West; at Junction City, with Wisconsin Valley Railway, for Wausau; at Portage with C. M. & St. Paul
Ry., for Madison and the West.

ESTABLISHED 1848.

WILLIAM SELLERS & CO.

PHILADELPHIA.

Machine and Railway Shop Equipments, Turn Tables,
Pivot Bridges, Shafting, Etc.

CIFFARD'S INJECTOR--SELLERS' IMPROVEMENTS.

NEW PATTERNS, SIMPLE, EFFECTIVE.


No. 2, 10 H. P., \$14.	No. 3, 20 H. P., \$25.	No. 4, 40 H. P., \$36.	No. 5, 70 H. P., \$45.	No. 6, 100 H. P., \$55.	No. 7, 140 H. P., \$65.	No. 8, 190 H. P., \$75.	No. 10, 275 H. P., \$95.
------------------------------	------------------------------	------------------------------	------------------------------	-------------------------------	-------------------------------	-------------------------------	--------------------------------

Send for circular giving particulars.

Branch Office, 79 Liberty Street, New York.

MIDVALE STEEL WORKS.

Works and Office, NICETOWN, Philadelphia, Pa.



MANUFACTURERS OF

Crucible and Open Hearth Steel,

Steel Locomotive Tires, Steel Axles of Every Description, Steel Forgings, up
to 8,000 lbs. in Weight, Solid Steel Castings, Hammer Dies,
Frogs, &c. Best Tool, Machinery and Spring Steels.

WM. SELLERS, Pres. MARRIOTT C. SMYTH, Sec'y and Treas. CHAS. A. BRINLEY, Sup't.

GILES BRO. & CO.,

266 & 268 Wabash Avenue,
CHICAGO, ILL.


FINE WATCHES A SPECIALTY.

Railroad Time-Keepers, One-Fourth Seconds, Sporting Watches, Repeaters, &c.
AGENTS FOR JURGENSEN, HOWARD & ELGIN WATCHES.

VALENTINE & COMPANY,



393 PEARL STREET, NEW YORK.



THOS. S. MORTON,

Manufacturer


OF
COPPER AND
IRON SASH
CHAIN,
WITHPatented
Attachments.This chain is intend-
ed to take the place of
Sash Cord, which is
continually breaking.
The Sash Chain will last
Twenty Years.

No. 65 Elizabeth St.

New York.
(P. O. Box 3,597.)

BLACK DIAMOND FILE WORKS

TRADE MARK.

G. & H. BARNETT.
Nos. 39, 41 & 43 Richmond Street,
PHILADELPHIA.
SEND FOR CATALOGUE.ZELL'S
ENCYCLOPEDIA.
NEW REVISED EDITION.
AGENTS WANTED.150,000 articles, 3,000
engravings and 18 splen-
did maps. The BEST BOOK
of universal knowledge in
the language. Now in
course of publication.
SPECIMEN with map sent
for 20 cents.
By addressing the pub-
lishers, canvassers will
learn of a new plan by which the work is selling
rapidly.T. ELLWOOD ZELL, DAVIS & CO.,
Philadelphia.





B. W. BOND, 5 Beekman st., New York

HELLER & BRIGHTLY, Engineering and
Surveying Instruments, 39 N. Seventh St., Phila.Without decreasing size of any
part of our "Engineers' Transit"
we have reduced the weight one-
half. An ordinary Transit Tele-
scope magnifies from 10 to 12 diam-
eters, our new Transit Telescope
(length 10 1/2 inches, shows objects
erect and not inverted) magnifies
28 diameters and will read time on
a watch-dial at 933 feet. For de-
scription of our new Mining Transit
(weight 5 1/2 lbs.) and Plummet
Lamp, see Van Nostrand's Engi-
neering Magazine, June, 1873.Extract from report of Committee
of Civ. Engs. appointed by Frank-
lin Inst. to examine H. & B.'s new
Transit (Dec., 1871): "It exhibits
several novelties of construction
which, in the opinion of the committee, render it supe-
rior to those now in use, and in its opinion the deviations
which they have made from the common styles of Transit
are decided improvements."JOHN C. TRAUTWINE, Chairman.
Descriptive and Illustrated Price List sent Post-paid on
Application.

TRADE MARK.

REGISTERED

HEYWOOD'S PATENT SNOW PLOW.

HEYWOOD'S PATENT SNOW PLOW,
FOR SINGLE OR DOUBLE TRACKS, with
Safety Wings and Flange Clearers; safe
to run at full passenger-train speed,
leaving the track and flanges entirely
free from ice and snow.Reference may be made to the Super-
intendents, Master Mechanics or Road
Masters of the following railroads, where
they have been fully tested: First used
on the Fitchburg Railroad and Branches;
next in order on the Vermont & Mas-
sachusetts, Troy & Greenfield, Flushing &
North Side, Flint & Pere Marquette, Chi-
cago & Michigan Lake Shore, and Inter-
Colonial & Wisconsin Central Railroads.
The Pattern required, also a Foreman,
can be sent to the shops of the railroads
who wish to build them, using common
car-trucks for the Plow.1. Application of Wings. 2. Tool House. 3. Caboose. 4. Application of Plow to Car. 5. Brake for
Extending Wings.

TESTIMONIALS.

BOSTON, CLINTON & FITCHBURG RAILROAD,
SUPERINTENDENT'S OFFICE,
FITCHBURG, Mass., March 10, 1873.C. L. HEYWOOD, Esq.,
Dear Sir—I think C. L. Heywood's Combination
Snow Plow and Flange Clearer which we have in
use on the Framingham & Lowell Railroad the best
of anything now in use for the purpose of clearing
snow and ice from the track.
Respectfully yours, H. A. BLOOD, Sup't.INDIANAPOLIS & CINCINNATI RAILROAD,
MASTER MECHANIC'S OFFICE,
CINCINNATI, Ohio, Nov. 28, 1865.

Mr. C. L. Heywood, Boston, Mass.:

Your letter, requesting me to give an opinion
relative to the merits of your Snow Plow and
Scraper, is received. It affords me pleasure to say
that while engaged on the Fitchburg Railroad I
had an opportunity to examine it carefully,
and witness its operation. It is the best machine I have
ever seen, not only for clearing snow and ice from
the track, but at the same time removing it deep
enough so that the flanges suffer no impediment
whatever. The great speed at which it can be run
with perfect safety gives it an advantage over any
other machine now used for that purpose. Its
simplicity and durability render it a desirable
machine for any railroad obstructed by snow or
ice.
Yours truly,
H. M. BRITTON, Master Mechanic.The undersigned fully concur in the above state-
ments.
H. W. BULLENS,
Master Mechanic Fitchburg Railroad.
L. J. SPAULDING,
Road Master Fitchburg Railroad.

APPLY TO

C. L. HEYWOOD, Boston, Mass.; or to

PORTLAND LOCOMOTIVE WORKS, Portland, Me.

WASON CAR WORKS, Springfield, Mass.

FLINT & PERE MARQUETTE RAILWAY,
OFFICE MASTER MECHANIC,
EAST SAGINAW, Mich., Jan. 16, 1871.C. L. HEYWOOD, Boston, Mass.:
Dear Sir—In regard to the Snow Plow, I can say
it is the most perfect one I ever saw. We have just
had one of the most severe snow storms ever expe-
rienced in this country, and if we had not had your
Plow we should have been entirely blocked in until
we could have shoveled it out. The snow was
heavy, like sand; in fact it was nothing but hail,
and with one locomotive attached to the Plow, we
cleared the road with perfect ease—in fact, we think
so much of it that we have another nearly com-
plete, with the exception of the side wings, which
we did not think necessary to have on both.Hoping your Plow will meet with the success it
deserves, I remain, Yours truly,
SANFORD KEELER, Master Mechanic.VERMONT & MASSACHUSETTS AND
TROY & GREENFIELD RAILROADS,
SUPERINTENDENT'S OFFICE,
FITCHBURG, Mass., June 13, 1870.C. L. HEYWOOD, Esq.:
Dear Sir—In answer to your inquiry, all I can say
is that your Snow Plow gives perfect satisfaction.
You well know that for the nineteen years that I
have been Superintendent of this road of snows
and snows, that I have not been slow to adopt any
improvement that would relieve us during the
snowy season; but with all my efforts I never was
contented until I adopted your Plow. Now let
snow come—I am ready.
Yours truly,
OTIS T. RUGGLES, Sup't.

ESTABLISHED 1820.

PATENT TRANSITS.

W. J. YOUNG & SONS,

Engineering Instrument Makers,

43 NORTH SEVENTH STREET,

Philadelphia.

Tapes, Chains, Draughting Instru-
ments. Catalogues on application.

JAMES PRENTICE,

164 Broadway, New York.

Manufacturer of Transits, Sur-
veyors' Levels, and Compasses,
Land Chains, Station Staffs, &c.
&c.A large assortment on hand
warranted for quality and at
reasonable prices.